

NOTICE TO CONTRACTORS

CALL ORDER F13  
FEDERAL PROJECT NO. EACIM-80-3(106)  
LOCATION: I-80 WEST OF SUTHERLAND.  
COUNTIES: LINCOLN

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on September 20, 2001. At that time the bids will be opened and read for GR CONC PAVE CULV SEED GDRL FENCE

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR:

CONCRETE PAVEMENT  
CULVERTS

START DATE 06/03/02 WORKING DAYS 85  
Price Range \$ 500,000 to \$ 1,000,000

THIS PROJECT CONTAINS A DBE GOAL.

Plans and specifications may be seen beginning August 28, 2001 at the Lincoln Central Office and September 04, 2001 at the District Engineer's Office at NORTH PLATTE

Additional letting information may be found at the Nebraska Department of Roads' Web Site at <http://www.dor.state.ne.us/letting/>

Contractors must meet the provisions of the Fair Labor Standards Act of 1938 (52 Stat. 1060) as amended. The Secretary of Labor has determined minimum wage rates for this project. This contract is subject to the Work Hours Act of 1962, P.L. 87-581 and implementing regulations.

This project is subject to the provisions of the utilization of Disadvantaged Business Enterprises.

Prequalification for bidding is required by Nebraska Revised Statute 39-1351-R.R.S. 1943.

A Department of Roads' Bid Bond Form for 5% of the bid must be submitted with the proposal. The successful bidder will furnish bond for 100% of the contract.

The contractor, with regard to the work performed by it during the contract, shall not discriminate on the grounds of race, religion, sex, color, national origin, age or disability.

THE DEPARTMENT RESERVES THE RIGHT TO WAIVE ALL TECHNICALITIES AND REJECT ANY OR ALL BIDS.

DIRECTOR: JOHN L. CRAIG

DISTRICT ENGINEER: LESTER D. O'DONNELL

LIST OF PLANS

SHEET NO.	TITLE
1	TITLE PAGE
2T1-2T2	TYPICAL CROSS SECTIONS
2S	SUMMARY OF QUANTITIES
2W	WETLANDS
2N	GENERAL INFORMATION
2P	CONSTRUCTION PHASING
3	PLAN & PROFILE SHEET
4	PLAN SHEET--CONSTRUCTION & REMOVAL
5	EASTBOUND & WESTBOUND DETOUR PLAN
6 - 8	TRAFFIC CONTROL PLAN

F13NTC09.TXT

9 TRAFFIC CONTROL PLAN--LANE CLOSURE  
 10 - 12 ROADWAY LIGHTING PLANS  
 13 EARTHWORK DATA SHEET  
 14 - 17 DRAINAGE STRUCTURE CROSS SECTIONS  
 18 - 21 SPECIAL PLAN 1C 6 TO 16 INCH CONCRETE PAVEMENT  
 22 SPECIAL PLAN 2C 64 FT. MEDIAN CROSSOVER DETOUR  
 23 SPECIAL PLAN 3C 9' X 10' TRIPLE SPAN  
 RC BOX CULVERT  
 STA. 3192+02.00  
 24 SPECIAL PLAN 4C GUARDRAIL PLAN  
 25 SPECIAL PLAN 5C SILT FENCE DETAILS  
 X1 - X7 CROSS SECTIONS

STANDARD PLANS

501-R2 EROSION CONTROL  
 702-R6 (2 SHEETS) CABLE GUARDRAIL  
 710-R3 (2 SHEETS) FENCE DETAILS  
 920-R5 (2 SHEETS) TRAFFIC CONTROL

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	30 SHEETS	\$ 6.00
CROSS SECTIONS (SHEETS X1 THRU X7)	7 SHEETS	1.40
STANDARD PLANS	7 SHEETS	1.40

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

COVER CROP SEEDING		5 ACRE
EROSION CONTROL		4,117 SY
FABRIC SILT FENCE, COIR FIBER		160 LF
MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)		1,703 CY
WATER		76 MGAL
EARTHWORK MEASURED IN EMBANKMENT		7,390 CY
REMOVE PAVEMENT		1,069 SY
REMOVE FENCE		335 LF
REMOVE GUARDRAIL		1,224 LF
RENTAL OF LOADER, FULLY OPERATED		10 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED		10 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED		10 HOUR

GROUP 3 CONCRETE PAVEMENT

MOBILIZATION	LUMP	LUMP
SURFACING		245 SY
6"		
TIE BARS		86 EACH
12" CONC PVMT, 47B-3625		657 SY
12" DOWELED CONC PVMT, 47B-3625		1,072 SY
TEMPORARY SURFACING		5,024 SY
9"		

GROUP 4 CULVERT AT STA. 3192+02

F13NTC09.TXT

MOBILIZATION	LUMP	LUMP
RIPRAP FILTER FABRIC		48 SY
REMOVE STRUCTURE		1 EACH
AT STA. 3192+00 LT.		
EXCAVATION FOR BOX CULVERTS		1,032 CY
TEMPORARY SHORING		135 LF
47B-3000 OR AX-3000 CONC FOR BOX CULV		565 CY
RE-STEEL FOR BOX CULVERT		63,141 LB
REMOVE STRUCTURE		1 EACH
AT STA. 3192+04 LT		
REMOVE STRUCTURE		1 EACH
AT STA. 3192+04 RT.		
BROKEN CONCRETE RIPRAP		48 TON
GROUP 5 SEEDING		
SEEDING, TYPE A		2 ACRE
SEEDING, TYPE B		3 ACRE
MULCH		10 TON
MOBILIZATION	LUMP	LUMP
GROUP 7 GUARDRAIL		
MOBILIZATION	LUMP	LUMP
CABLE GUARDRAIL		272 LF
TERMINAL ANCHORAGE SECTIONS		4 EACH
GROUP 7B FENCING		
MOBILIZATION	LUMP	LUMP
RIGHT-OF-WAY FENCE		347 LF
END POSTS		4 EACH
CORNER POSTS		4 EACH
GROUP 10 GENERAL ITEMS		
TEMP LIGHTING SYSTEM, TYPE		1 EACH
DETOUR		
OPER & MAINT OF TEMP LIGHT SYSTEM, TYPE		70 DAY
DETOUR		
SURV OF TEMP TRAFFIC CONT DEVICES		70 CDAY
BARRICADE, TYPE II		9,177 BDAY
BARRICADE, TYPE III		1,035 BDAY
TYPE B HIGH INTENSITY WARNING LIGHT		695 LDAY
TEMPORARY SIGN DAY		450 EACH
SIGN DAY		4,221 EACH
PAVEMENT MARKING REMOVAL		10,000 LF
TEMP PVMT MARKING, TYPE II		9,600 LF
TEMP PVMT MARKING, TYPE RPM		16,230 LF
FLASHING ARROW PANEL		154 DAY
FLAGGING		30 DAY
INSTALL CONC PROTECT BARRIER		640 LF
RELOCATE CONC PROTECTION BARRIER		180 LF
RELOC INERTIAL BARRIER SYSTEM		1 EACH
INERTIAL BARRIER SYSTEM		3 EACH
REPLACEMENT MODULE		5 EACH
FIELD OFFICE		1 EACH
MOBILIZATION	LUMP	LUMP