

NOTICE TO CONTRACTORS

CALL ORDER N24
STATE PROJECT NO. PEP-8-5(1009)
LOCATION: ON N-8 BETWEEN US-81 AND REYNOLDS.
COUNTIES: JEFFERSON THAYER

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on February 07, 2002. At that time the bids will be opened and read for GUARDRAIL, BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR:

BITUMINOUS
Length: 15.4 MILES
START DATE 05/13/02 WORKING DAYS 85
Price Range \$ 1,000,000 to \$ 3,000,000
Plans and specifications may be seen beginning January 15, 2002 at the Lincoln Central Office and January 22, 2002 at the District Engineer's Office at GRAND ISLAND

Additional letting information may be found at the Nebraska Department of Roads' Web Site at <http://www.dor.state.ne.us/letting/>

Prequalification for bidding is required by Nebraska Revised Statute 39-1351-R.R.S. 1943.

A Department of Roads' Bid Bond Form for 5% of the bid must be submitted with the proposal. The successful bidder will furnish bond for 100% of the contract.

The contractor, with regard to the work performed by it during the contract, shall not discriminate on the grounds of race, religion, sex, color, national origin, age or disability.

THE DEPARTMENT RESERVES THE RIGHT TO WAIVE ALL TECHNICALITIES AND REJECT ANY OR ALL BIDS.

DIRECTOR: JOHN L. CRAIG
DISTRICT ENGINEER: V. CHARLES MCCANN

LIST OF PLANS

SHEET NO.	
1	TITLE PAGE
2	INDEX OF SHEETS
2T1-2T4	TYPICAL CROSS SECTIONS
2S1-2S2	SUMMARY OF QUANTITIES
3 - 30	PLAN SHEETS
31	TRAFFIC CONTROL PLAN--BRIDGE CURB REPAIR
32	TEMPORARY PAVEMENT MARKING PLAN
33 - 34	SPECIAL PLAN 1C BRIDGE CURB END TREATMENT STA. 558+65.00
35 - 36	SPECIAL PLAN 2C BRIDGE CURB END TREATMENT STA. 782+65.00
37 - 48	SPECIAL PLAN 3C GUARDRAIL PLAN
49 - 51	SPECIAL PLAN 4C CABLE GUARDRAIL
52 - 53	SPECIAL PLAN 5C MAILBOX SUPPORT POST
X1 - X21	CROSS SECTIONS

STANDARD PLANS

N24NTC02.TXT

108-R1 SUPERELEVATION PLAN FOR CONCRETE AND
BITUMINOUS SURFACING
501-R2 EROSION CONTROL
901-R8 HIGHWAY DELINEATORS
920-R5 (2 SHEETS) TRAFFIC CONTROL
922-R5 TRAFFIC CONTROL DEVICES

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	59 SHEETS	\$11.80
CROSS SECTIONS (SHEETS X1 THRU X21)	21 SHEETS	4.20
STANDARD PLANS	6 SHEETS	1.20

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
47BD-4000 CONC FOR BRIDGE		7 CY
RE-STEEL FOR BRIDGE		1,980 LB
CULV MOUNTED GDRL POST		12 EACH
W-BEAM GUARDRAIL		2,737 LF
CABLE GUARDRAIL		1,568 LF
REMOVE GUARDRAIL		5,774 LF
BRIDGE APPROACH SECTIONS		8 EACH
TERMINAL ANCHORAGE SECTIONS		12 EACH
GUARDRAIL END TREATMENT, TYPE II		24 EACH

GROUP 9 BITUMINOUS

SEEDING, TYPE B		46 ACRE
EROSION CONTROL		13,764 SY
MULCH		104 TON
OVERLAY BROKEN LINES		1,625 STA
OVERLAY SOLID LINES		3,251 STA
MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		96 MGAL
DELINEATOR, TYPE III		92 EACH
INSTALL CHEVRONS		64 EACH
REMOVE DELINEATOR UNITS		92 EACH
EARTHWORK MEASURED IN EMBANKMENT		6,450 CY
REMOVE ASPHALT SURFACE		1,683 SY
MAILBOX POST		11 EACH
CONC PVMT REPAIR TYPE B FULL DEPTH		28 SY
CONC PVMT REPAIR TYPE C FULL DEPTH		97 SY
HYDRATED LIME		700 TON
HYDRATED LIME SLURRY STABILIZATION		810 STA
ASPH CONC FOR STATE MAINT PATCHING, TYPE SP2(0.375)		1,000 TON
ASPH CONCRETE FOR PATCHING, TYPE SP2(0.375)		500 TON
ASPH CONC, TYPE SP2(0.375)		35,220 TON
PERF GRAD BIND (64-22)FOR ST MAINT PATCH		54 TON
PERF GRADED BINDER (64-22)		1,901 TON
EMUL ASPH FOR HYDRATE LIME STABILIZATION		170,640 GAL
TACK COAT		43,410 GAL
WATER		405 MGAL

N24NTC02.TXT

EARTH SHOULDER CONSTRUCTION	1,621 STA
TRENCHED WIDENING	1,621 STA
SURFACE UNDER GUARDRAIL	3,080 SY

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	560 BDAY
--------------------	----------

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE III	724 BDAY
TYPE B HIGH INTENSITY WARNING LIGHT	306 LDAY
TEMPORARY SIGN DAY	500 EACH
SIGN DAY	12,706 EACH
FLAGGING	120 DAY
FURNISHING AND OPERATING PILOT VEHICLE	20 DAY
FIELD OFFICE	1 EACH
MOBILIZATION	LUMP LUMP
RENTAL OF LOADER, FULLY OPERATED	80 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	80 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	80 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	80 HOUR