

STATE OF NEBRASKA
DEPARTMENT OF ROADS
ADDENDUM NO. 2
PROJECT NO. EACSTPD-EACBR-92-5(105)
CONTROL NO. 41908
CALL ORDER F22
JCT. US-30/N-92 NEAR CLARKS
LETTING DATE: FEBRUARY 7, 2002

The Special Provisions are amended to include the following:

REMOVAL OF EXISTING STRUCTURE AT STA. 122+81.4

The removal of the existing structure shall be in accordance with Section 203 of the Standard Specifications and Section 732 of the Supplemental Specifications and shall include the following:

1. No material shall be permitted to fall into an area 12 feet either side of the railroad tracks. The Contractor shall construct a temporary floor, acceptable to the Engineer, under the superstructure of the existing bridge to prevent any debris from falling to the track area below during removal of the existing structure and during construction of the new work.
2. It is anticipated that the paint on the existing structure contains the metals lead and/or chromium in quantities above the acceptable maximums and should be handled accordingly.
3. Blast boards containing asbestos materials are attached to the existing structure over the railroad tracks. The Contractor shall perform all work associated with the removal of the blast boards in accordance with all applicable Federal, State and local laws and regulations concerning the removal, handling and disposal of asbestos materials. Asbestos material shall be disposed of at an EPA, State and local approved asbestos landfill. For temporary storage, sealed impermeable containers shall be stored in an asbestos waste load-out unit or in a storage/transportation conveyance in a manner as accepted and approved by the Engineer. Procedure for hauling and disposal shall comply with Federal, State and local standards. The Contractor shall complete and provide to the Engineer final completed copies of the Waste Shipment Record within 3 days of delivery to the landfill.

GENERAL CLEARING AND GRUBBING

Paragraph 1. of Subsection 202.03 in the Supplemental Specifications is amended to provide that General Clearing and Grubbing shall include all tree removal.

Paragraphs 2.a., b., and c. of Subsection 202.03 in the Supplemental Specifications are void.

Paragraph 3. of Subsection 202.04 in the Supplemental Specifications is void and superseded by the following:

3. All tree removal is subsidiary to the pay item "General Clearing and Grubbing".

DEPARTMENT OF ROADS

Claude Oie
Construction Engineer

Issued: January 28, 2002

CO:KM:F22AD202

NOTICE: Only the contractors issued bidding proposals receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the contractor.