

NOTICE TO CONTRACTORS

CALL ORDER F03  
FEDERAL PROJECT NO. BR-3015(2)  
LOCATION: ON A COUNTY ROAD SOUTH OF PLYMOUTH.  
COUNTIES: JEFFERSON

The Nebraska Department of Roads will receive sealed bids for JEFFERSON COUNTY in Room 104 of the Central Office Building at 1500 Hwy. 2 at Lincoln, until 1:30 P.M. on March 14, 2002. At that time the bids will be opened and read for GRAD, CONC PAVE, BR, GDRL

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR:

BRIDGES

Length: 0.2 MILE  
START DATE 07/08/02 WORKING DAYS 80  
Price Range \$ 500,000 to \$ 1,000,000

Plans and specifications may be seen beginning February 19, 2002 at the Lincoln Central Office and February 25, 2002 at the District Engineer's Office at LINCOLN

Additional letting information may be found at the Nebraska Department of Roads' Web Site at <http://www.dor.state.ne.us/letting/>

Contractors must meet the provisions of the Fair Labor Standards Act of 1938 (52 Stat. 1060) as amended. The Secretary of Labor has determined minimum wage rates for this project. This contract is subject to the Work Hours Act of 1962, P.L. 87-581 and implementing regulations.

This project is subject to the provisions of the utilization of Disadvantaged Business Enterprises.

Prequalification for bidding is required by Nebraska Revised Statute 39-1351-R.R.S. 1943.

A Department of Roads' Bid Bond Form for 5% of the bid must be submitted with the proposal. The successful bidder will furnish bond for 100% of the contract.

The contractor, with regard to the work performed by it during the contract, shall not discriminate on the grounds of race, religion, sex, color, national origin, age or disability.

THE DEPARTMENT RESERVES THE RIGHT TO WAIVE ALL TECHNICALITIES AND REJECT ANY OR ALL BIDS.

DIRECTOR: JOHN L. CRAIG

DISTRICT ENGINEER: RICHARD J. RUBY

LIST OF PLANS

SHEET NO.	TITLE PAGE
1	TITLE PAGE
2T	TYPICAL CROSS SECTIONS OF IMPROVEMENT
2S	SUMMARY OF QUANTITIES
2N	GENERAL INFORMATION
2L	GEOMETRICS & GRADES
3	PLAN & PROFILE SHEET
4 - 13	CROSS SECTIONS
14	DRAINAGE STRUCTURE CROSS SECTIONS
15 - 23	SPECIAL PLAN 1 CONCRETE SLAB BRIDGE STA. 201+72.00

F03NTC03.TXT

24 - 28 SPECIAL PLAN 1C GUARDRAIL PROTECTION  
 29 - 32 SPECIAL PLAN 2C 6 TO 16 INCH CONCRETE PAVEMENT  
 R1 R-O-W DATA

STANDARD PLANS

301-R7 (3 SHEETS) PAVEMENT DETAILS  
 410-R3 (2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES  
 425-R3 COLLARS AND ELBOWS FOR CONCRETE PIPES  
 920-R5 (2 SHEETS) TRAFFIC CONTROL  
 921-R4 TRAFFIC CONTROL  
 923 TRAFFIC CONTROL--ROAD CLOSURE

PLANS (NOT INCLUDING STANDARDS) 36 SHEETS \$ 7.20  
 STANDARD PLANS 10 SHEETS 2.00

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

COVER CROP SEEDING		2	ACRE
MOBILIZATION	LUMP		LUMP
LARGE TREE REMOVAL		56	EACH
GENERAL CLEARING AND GRUBBING	LUMP		LUMP
EXCAVATION (ESTABLISHED QUANTITY)		11,220	CY
WATER		24	MGAL
REMOVE ASPHALT SURFACE		2,411	SY
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL		105	CY
48" CULVERT PIPE		68	LF
48" FLARED-END SECTION		1	EACH

GROUP 3 CONCRETE PAVEMENT

MOBILIZATION	LUMP		LUMP
8" CONC PVMT, 47B-3500		2,640	SY
AGGREGATE FOUNDATION COURSE 4"		2,640	SY
WATER		13	MGAL
EARTH SHOULDER CONSTRUCTION		21	STA
SUBGRADE PREPARATION		2,640	SY

GROUP 6 BRIDGE AT STA. 201+72

MOBILIZATION	LUMP		LUMP
RIPRAP FILTER FABRIC		1,076	SY
CONC FOR PVMT APPROACHES CLASS 47BD-4000		137	CY
EPOXY COATED RE-STEEL FOR PVMT APPROACH		11,785	LB
ABUTMENT NO.1 EXCAVATION	LUMP		LUMP
ABUTMENT NO.2 EXCAVATION	LUMP		LUMP
BENT NO.1 EXCAVATION	LUMP		LUMP
BENT NO.2 EXCAVATION	LUMP		LUMP
47B-3000 CONC FOR BRIDGE		201	CY
47BD-4000 CONC FOR BRIDGE		195	CY
REMOVE STRUCTURE		1	EACH
AT STA. 201+94			
STRUC STEEL FOR SUBSTRUCTURE		1,695	LB
ROCK RIPRAP, TYPE B		906	TON
EPOXY COATED RE-STEEL		49,610	LB
HP 10"X42# STEEL PILING		1,400	LF

F03NTC03.TXT

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
BRIDGE APPROACH SECTIONS		4 EACH
BREAKAWAY CABLE TERMINAL		4 EACH

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE III		1,752 BDAY
---------------------	--	------------

GROUP 10 GENERAL ITEMS

TYPE B HIGH INTENSITY WARNING LIGHT		292 LDAY
SIGN DAY		2,920 EACH
FIELD OFFICE		1 EACH
MOBILIZATION	LUMP	LUMP