

NOTICE TO CONTRACTORS

CALL ORDER F18
FEDERAL PROJECT NO. BRO-7093(18)
LOCATION: ON A COUNTY ROAD NORTHWEST OF BENEDICT.
COUNTIES: YORK

The Nebraska Department of Roads will receive sealed bids for YORK COUNTY in Room 104 of the Central Office Building at 1500 Hwy. 2 at Lincoln, until 1:30 P.M. on April 18, 2002. At that time the bids will be opened and read for CULV BR GDRL

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR:

BRIDGES

Length: 0.4 MILE

START DATE 07/22/02 WORKING DAYS 70

Price Range \$ 100,000 to \$ 500,000

Plans and specifications may be seen beginning March 26, 2002 at the Lincoln Central Office and April 01, 2002 at the District Engineer's Office at GRAND ISLAND

Additional letting information may be found at the Nebraska Department of Roads' Web Site at <http://www.dor.state.ne.us/letting/>

Contractors must meet the provisions of the Fair Labor Standards Act of 1938 (52 Stat. 1060) as amended. The Secretary of Labor has determined minimum wage rates for this project. This contract is subject to the Work Hours Act of 1962, P.L. 87-581 and implementing regulations.

This project is subject to the provisions of the utilization of Disadvantaged Business Enterprises.

Prequalification for bidding is required by Nebraska Revised Statute 39-1351-R.R.S. 1943.

A Department of Roads' Bid Bond Form for 5% of the bid must be submitted with the proposal. The successful bidder will furnish bond for 100% of the contract.

The contractor, with regard to the work performed by it during the contract, shall not discriminate on the grounds of race, religion, sex, color, national origin, age or disability.

THE DEPARTMENT RESERVES THE RIGHT TO WAIVE ALL TECHNICALITIES AND REJECT ANY OR ALL BIDS.

DIRECTOR: JOHN L. CRAIG

DISTRICT ENGINEER: V. CHARLES MCCANN

LIST OF PLANS

SHEET NO.

1	TITLE PAGE
2T	TYPICAL CROSS SECTIONS & SUMMARY OF QUANTITIES
3	PLAN & PROFILE
4 - 7	ROADWAY CROSS SECTIONS
8 - 10	DRAINAGE STRUCTURE CROSS SECTIONS
11 - 17	SPECIAL PLAN 1 DOUBLE TEE BEAM BRIDGE STA. 10+00.00
18 - 22	SPECIAL PLAN 1C SAFETY BEAM GUARDRAIL
23	SPECIAL PLAN 2C PIPE CULVERT HEADWALLS &

F18NTC04.TXT
STRUTTING DIAGRAM FOR
CORRUGATED METAL PIPE

24 RIGHT-OF-WAY STRIP MAP

STANDARD PLANS

410-R3 (2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
617-R3 (2 SHEETS) CONCRETE PILING
920-R5 (2 SHEETS) TRAFFIC CONTROL
921-R4 TRAFFIC CONTROL
923 TRAFFIC CONTROL--ROAD CLOSURE
1210 (2 SHEETS) REINFORCED CONCRETE BOX CULVERTS
 TWIN SPAN WITH 10 & 12-FOOT RISE

PLANS (NOT INCLUDING STANDARDS)	24 SHEETS	\$ 4.80
STANDARD PLANS	10 SHEETS	2.00

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 4 CULVERTS

MOBILIZATION	LUMP	LUMP
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL		24 CY
47B-3000 OR AX-3000 CONC FOR HDWL		1 CY
RE-STEEL FOR HEADWALL		40 LB
24" CORRUGATED METAL PIPE		74 LF
24" METAL FLARED-END SECTION		1 EACH

GROUP 4A CULVERT AT STA. 20+25

MOBILIZATION	LUMP	LUMP
EXCAVATION FOR BOX CULVERTS		99 CY
47B-3000 OR AX-3000 CONC FOR BOX CULV		146 CY
RE-STEEL FOR BOX CULVERT		15,238 LB
REMOVE STRUCTURE		1 EACH
AT STA. 20+25		

GROUP 6 BRIDGE AT STA. 10+00

MOBILIZATION	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)		170 CY
ABUTMENT NO.1 EXCAVATION	LUMP	LUMP
ABUTMENT NO.2 EXCAVATION	LUMP	LUMP
BENT NO.1 EXCAVATION	LUMP	LUMP
BENT NO.2 EXCAVATION	LUMP	LUMP
47B-3000 CONC FOR BRIDGE		339 CY
47BD-4000 CONC FOR BRIDGE		92 CY
PRECAST/PRESTRESSED CONC SUPERSTR	LUMP	LUMP
AT STA. 10+00		
RE-STEEL FOR BRIDGE		28,000 LB
REMOVE STRUCTURE		1 EACH
AT STA. 10+00		
STRUC STEEL FOR SUBSTRUCTURE		1,570 LB
STRUC STEEL FOR SUPERSTRUCTURE		1,025 LB
BROKEN CONCRETE RIPRAP		63 TON
CONCRETE PILING		1,380 LF

GROUP 7 GUARDRAIL

F18NTC04.TXT

MOBILIZATION	LUMP	LUMP
BRIDGE APPROACH SECTIONS		4 EACH
BREAKAWAY CABLE TERMINAL		4 EACH

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE III		1,584 BDAY
TYPE B HIGH INTENSITY WARNING LIGHT		264 LDAY
SIGN DAY		2,640 EACH
FIELD OFFICE		1 EACH

GROUP 10 GENERAL ITEMS

MOBILIZATION	LUMP	LUMP
--------------	------	------