

## NOTICE TO CONTRACTORS

CALL ORDER F05  
 FEDERAL PROJECT NO. STPP-275-7(183)  
 LOCATION: US-275/N-92 ("L" STREET) AT 60TH, OMAHA.  
 COUNTIES: DOUGLAS

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on May 23, 2002. At that time the bids will be opened and read for GRAD CONC PAVE CULV ELEC

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR:

CONCRETE PAVEMENT

ELECTRICAL

START DATE 10/07/02 WORKING DAYS 25

Price Range \$ 100,000 to \$ 500,000

Plans and specifications may be seen beginning April 30, 2002 at the Lincoln Central Office and May 06, 2002 at the District Engineer's Office at OMAHA

Additional letting information may be found at the Nebraska Department of Roads' Web Site at <http://www.dor.state.ne.us/letting/>

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

## LIST OF PLANS

## SHEET NO.

1	TITLE PAGE
2T	TYPICAL CROSS SECTIONS
2S	SUMMARY OF QUANTITIES
2H	CONTROL POINT TIES
2N	GENERAL INFORMATION
2L1-2L2	GEOMETRICS & GRADES
2L3	DRAINAGE
2L4-2L5	CONSTRUCTION
2L6-2L7	REMOVALS
3 - 4	PLAN & PROFILE SHEETS
5 - 7	TYPICAL URBAN TRAFFIC CONTROL PLAN
8 - 10	TRAFFIC SIGNAL PLAN
11 - 14	ROADWAY LIGHTING PLANS
15	DRAINAGE STRUCTURE CROSS SECTIONS
16 - 19	SPECIAL PLAN 1C 6 TO 16 INCH CONCRETE PAVEMENT
X1 - X3	CROSS SECTIONS

## STANDARD PLANS

301-R7	(3 SHEETS) PAVEMENT DETAILS
425-R3	COLLARS AND ELBOWS FOR CONCRETE PIPES
443-R6	(2 SHEETS) CURB INLETS AND JUNCTION BOX
501-R2	EROSION CONTROL
914-R3	PULL BOX DETAIL
920-R5	(2 SHEETS) TRAFFIC CONTROL

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)

29 SHEETS \$ 5.80

## F05NTC05.TXT

CROSS SECTIONS (SHEETS X1 THRU X3)	3 SHEETS	0.60
STANDARD PLANS	10 SHEETS	2.00

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

## GROUP 1 GRADING

EROSION CONTROL	1,131 SY
MOBILIZATION	LUMP LUMP
GENERAL CLEARING AND GRUBBING	LUMP LUMP
EXCAVATION (ESTABLISHED QUANTITY)	56 CY
REMOVE PAVEMENT	114 SY
SAWING PAVEMENT	1,074 LF
REMOVE CURB	886 LF
REMOVE CONCRETE MEDIAN SURFACING	385 SY

## GROUP 3 CONCRETE PAVEMENT

MOBILIZATION	LUMP LUMP
TIE BARS	330 EACH
CONC 47B-3500 CURB TYPE II	1,434 LF
CONC 47B-3000 MEDIAN SURFACING	1,039 SY
6" CONC CLASS 47B-3000 MEDIAN SURFACING	143 SY
10" CONC PVMT, 47B-3500	464 SY
AGGREGATE FOUNDATION COURSE-D 4"	447 SY
WATER	2 MGAL
SUBGRADE PREPARATION	447 SY

## GROUP 4 CULVERTS

MOBILIZATION	LUMP LUMP
REMOVE INLET	1 EACH
CAST IRON COVER & FRAME	125 LB
REMOVE SEWER PIPE	16 LF
47B-3000 CONC FOR INLET & JUNCTION BOXES	3 CY
47B-3000 OR AX-3000 CONC FOR CONCRETE CO	1 CY
RE-STEEL FOR INLET & JCT BOX	245 LB
RE-STEEL FOR COLLARS	43 LB
24" REINF CONCRETE SEWER PIPE	12 LF

## GROUP 8B ELECTRIC

PULL BOX, TYPE PB-1	2 EACH
PULL BOX, TYPE PB-1A	1 EACH
PULL BOX, TYPE PB-6	1 EACH
TRAFFIC SIGNAL, TYPE TS-1L	4 EACH
VEHICLE DETECTOR, TYPE TD-5A	12 EACH
ST LIGHT UNIT SL-BT-45-8-0.40	3 EACH
C.M.A. SIG & LGHT POLE, CMP-60-12	1 EACH
SERVICE DISCONNECT PEDESTAL	1 EACH
1 1/2" CONDUIT IN TRENCH	608 LF
2" CONDUIT IN TRENCH	86 LF
1 1/2" CONDUIT, JACKED	133 LF
3" CONDUIT, JACKED	104 LF
2/C #14 AWG TRAF SIG CABLE	930 LF

F05NTC05.TXT

GROUP 8B ELECTRIC

16/C #14 AWG TRAF SIG CABLE	465 LF
2/C #14 AWG DETECTOR LEAD-IN CABLE	682 LF
GROUNDING CONDUCTOR	164 LF
SERVICE CABLE	96 LF
STREET LIGHT CABLE, NO. 6 BARE	791 LF
STREET LIGHT CABLE, NO. 6 USE	1,582 LF
INSTALL TRAFFIC SIGNAL, TS-1	3 EACH
INSTALL PEDSTRIAN SIGNAL PS-1	2 EACH
INSTALL PEDESTRIAN PUSHBUTTON	1 EACH
REMOVE LIGHTING UNIT	3 EACH
REMOVE TRAFFIC SIGNAL	1 EACH
TYPE TS-1	
REMOVE TRAFFIC SIGNAL	1 EACH
TYPE TS-1LL	
REMOVE MAST ARM SIGNAL POLE	1 EACH
TEMPORARY TRAFFIC SIGNAL	1 EACH
60TH & "L" STREET	
MOBILIZATION	LUMP LUMP

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	2,350 BDAY
BARRICADE, TYPE III	460 BDAY
TYPE B HIGH INTENSITY WARNING LIGHT	220 LDAY
TEMPORARY SIGN DAY	84 EACH
SIGN DAY	1,930 EACH
FLASHING ARROW PANEL	80 DAY
FLAGGING	14 DAY
MOBILIZATION	LUMP LUMP