

NOTICE TO CONTRACTORS

CALL ORDER F03
FEDERAL PROJECT NO. EACIM-80-8(102)
LOCATION: I-80, MILFORD - LINCOLN.
COUNTIES: LANCASTER SEWARD

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on September 05, 2002 At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR:

BITUMINOUS

Length: 13.3 MILES
START DATE 03/31/03 WORKING DAYS 70
Price Range \$ 3,000,000 to \$ 5,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 5.0 %.
Plans and specifications may be seen beginning August 13, 2002 at the Lincoln Central Office and August 19, 2002 at the District Engineer's Office at LINCOLN

Additional letting information may be found at the Nebraska Department of Roads' Web Site at <http://www.dor.state.ne.us/letting/>

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

NOTICE TO BIDDERS

To be eligible for the award of this contract, bidders shall submit a completed bidding proposal for both Call Order No. N22 {Project No. PEP-6-6(1037)} and Call Order NO. F03 {PROJECT NO. EACIM-80-8(102)}.

Award of Contract, if awarded, will be made on the combined bid for both contracts.

Separate contracts will be awarded for each Call Order Number.

LIST OF PLANS

SHEET NO.	
1	TITLE PAGE
2T1-2T4	TYPICAL CROSS SECTIONS
2S1-2S2	SUMMARY OF QUANTITIES
2N	GENERAL INFORMATION--MILLED RUMBLE STRIPS
3 - 5	PLAN SHEETS
6	TRAFFIC CONTROL PLAN
7	TRAFFIC CONTROL PLAN--LANE CLOSURE
8	TRAFFIC CONTROL PLAN--MOBILE OPERATIONS
9	TYPICAL PAVEMENT MARKING PLAN--INTERSTATE/ EXPRESSWAY WITH PLOWABLE MARKERS
10	TEMPORARY PAVEMENT MARKING PLAN
11	SPECIAL PLAN 1C VEHICLE CLASSIFICATION DETECTOR

STANDARD PLANS
 914-R3 PULL BOX DETAIL
 920-R5 (2 SHEETS) TRAFFIC CONTROL

PLANS (NOT INCLUDING STANDARDS) 17 SHEETS \$ 3.40
 STANDARD PLANS 3 SHEETS 0.60

□

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

PULL BOX, TYPE PB-5	2	EACH
TRAFFIC DETECTOR	1	EACH
AT STA. 284+79 (LANE 1)		
TRAFFIC DETECTOR	1	EACH
AT STA. 284+79 (LANE 2)		
TRAFFIC DETECTOR	1	EACH
AT STA. 283+62 (LANE 3)		
TRAFFIC DETECTOR	1	EACH
AT STA. 283+62 (LANE 4)		
BARRICADE, TYPE II	35,000	BDAY
BARRICADE, TYPE III	1,200	BDAY
TYPE B HIGH INTENSITY WARNING LIGHT	1,000	LDAY
TEMPORARY SIGN DAY	3,400	EACH
SIGN DAY	4,000	EACH
OVERLAY BROKEN LINES	4,220	STA
OVERLAY SOLID LINES	8,772	STA
PLOWABLE PAVEMENT MARKER	1,925	EACH
FLASHING ARROW PANEL	140	DAY
FLAGGING	50	DAY
TRAFFIC CONTROL MANAGEMENT	70	DAY
FIELD OFFICE	1	EACH
MOBILIZATION	LUMP	LUMP
CONC PVMT REPAIR TYPE A FULL DEPTH	43	SY
CONC PVMT REPAIR TYPE B FULL DEPTH	21	SY
CONC PVMT REPAIR TYPE C FULL DEPTH	41	SY
CONC PVMT, PR-3500	638	SY
JOINT REPAIR		
4" YELLOW THERMOPLASTIC	151,000	LF
4" WHITE THERMOPLASTIC	326,000	LF
12" WHITE THERMOPLASTIC	3,400	LF
ASPH CONC FOR STATE MAINT PATCHING, TYPE SPS	100	TON
ASPH CONCRETE FOR PATCHING, TYPE SP6	250	TON
ASPH CONC, TYPE SPS	15,330	TON
ASPH CONC, TYPE SP6(0.375)	35,180	TON
ASPH CONC, TYPE SP6(0.5)	55,000	TON
PERF GRAD BIND (58-28)FOR ST MAINT PATCH	5	TON
PERF GRADED BINDER (58-28)	827	TON
PERF GRADED BINDER (70-28)	5,235	TON
TACK COAT	110,240	GAL
RENTAL OF LOADER, FULLY OPERATED	130	HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	130	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	130	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	130	HOUR
COLD MILLING, CLASS 4	1,407	STA
COLD MILLING, CLASS 3	204,537	SY

COLD MILLING, CLASS 3
TYPE A

F03NTC09.TXT

117 STA

□

GROUP 9 BITUMINOUS

RUMBLE STRIPS, ASPHALT
ASPH PVMT SMOOTHNESS TESTING I/D

2,814 STA
LUMP LUMP

□