

NOTICE TO CONTRACTORS

CALL ORDER F07  
 FEDERAL PROJECT NO. EACSTPD-75-3(111)  
 LOCATION: ON US-75, SOUTH OF FT. CALHOUN.  
 COUNTIES: WASHINGTON

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on September 05, 2002 At that time the bids will be opened and read for GR CULV GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR:

BITUMINOUS

Length: 4.6 MILES  
 START DATE 07/28/03 WORKING DAYS 55  
 Price Range \$ 1,000,000 to \$ 3,000,000  
 THIS PROJECT CONTAINS A DBE GOAL OF 4.0 %.  
 Plans and specifications may be seen beginning August 13, 2002 at the Lincoln Central Office and August 19, 2002 at the District Engineer's Office at OMAHA

Additional letting information may be found at the Nebraska Department of Roads' Web Site at <http://www.dor.state.ne.us/letting/>

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

LIST OF PLANS

SHEET NO.	
1	TITLE PAGE
2T1-2T6	TYPICAL CROSS SECTIONS
2S1-2S3	SUMMARY OF QUANTITIES
2W1-2W5	WETLANDS
2N	GENERAL INFORMATION
3 - 7	PLAN SHEETS
8	TRAFFIC CONTROL PLAN
9	TEMPORARY PAVEMENT MARKING PLAN
10	DRAINAGE STRUCTURE CROSS SECTIONS
11 - 15	SPECIAL PLAN 1C GUARDRAIL PLAN
16 - 18	SPECIAL PLAN 2C CABLE GUARDRAIL
19 - 20	SPECIAL PLAN 3C MAILBOX SUPPORT POST

STANDARD PLANS

108-R1	SUPERELEVATION PLAN FOR CONCRETE AND BITUMINOUS SURFACING
410-R3	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
425-R3	COLLARS AND ELBOWS FOR CONCRETE PIPES
428-R2	CONCRETE PLUGS AND FIELD PIPE TAP DETAILS
501-R3	EROSION CONTROL
920-R5	(2 SHEETS) TRAFFIC CONTROL
921-R4	TRAFFIC CONTROL

PLANS (NOT INCLUDING STANDARDS)	34 SHEETS	\$ 6.80
STANDARD PLANS	9 SHEETS	1.80

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

EROSION CONTROL	5,490	SY
MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
ROADWAY GRADING	20	STA
ABANDON INLET	2	EACH
REMOVE CURB	551	LF
REMOVE GUARDRAIL	2,612	LF

GROUP 4 CULVERT

MOBILIZATION	LUMP	LUMP
FLOWABLE FILL CONCRETE	10	CY
TAPPING EXISTING STRUCTURE	1	EACH
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL	75	CY
PIPE LINER	72	LF
(54" METAL PIPE)		
36" REINFORCED CONCRETE PIPE	50	LF
36" REINF CONC PIPE CLASS IV	50	LF
36" CONCRETE FLARED-END SECTION	1	EACH
JACKING 36" RCP CLASS IV	50	LF

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
CULV MOUNTED GDRL POST	2	EACH
W-BEAM GUARDRAIL	1,031	LF
CABLE GUARDRAIL	1,296	LF
TERMINAL ANCHORAGE SECTIONS	6	EACH
GUARDRAIL END TREATMENT, TYPE II	8	EACH

GROUP 9 BITUMINOUS

SEEDING, TYPE B	14	ACRE
MULCH	32	TON
OVERLAY BROKEN LINES	647	STA
OVERLAY SOLID LINES	1,294	STA
MOBILIZATION	LUMP	LUMP
GRAVEL SURFACE COURSE	175	TON
MAILBOX POST	16	EACH
CONC PVMT REPAIR TYPE A FULL DEPTH	7	SY
CONC PVMT REPAIR TYPE B FULL DEPTH	187	SY
CONC PVMT REPAIR TYPE C FULL DEPTH	595	SY
BITUMINOUS PATCHING	53	TON
CONC PVMT, PR-3500	190	SY
JOINT REPAIR		
ASPH CONC FOR STATE MAINT PATCHING, TYPE SPS	100	TON

GROUP 9 BITUMINOUS

ASPH CONCRETE FOR PATCHING, TYPE	100	TON
----------------------------------	-----	-----

F07NTC09.TXT

SPS		
ASPH CONCRETE FOR PATCHING, TYPE SP4 (0.5)		100 TON
ASPH CONC, TYPE SPS		6,850 TON
ASPH CONC, TYPE SP4 (0.5)		14,270 TON
PLACE ASPH CONC FOR DRIVE & INTER		3,326 SY
PERF GRAD BIND (58-28) FOR ST MAINT PATCH		5 TON
PERF GRADED BINDER (58-28)		369 TON
PERF GRADED BINDER (70-28)		770 TON
TACK COAT		20,220 GAL
RENTAL OF LOADER, FULLY OPERATED		50 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED		50 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED		50 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED		50 HOUR
WATER		117 MGAL
EARTH SHOULDER CONSTRUCTION		467 STA
COLD MILLING, CLASS 3		157 STA
CONC SURF MILLING		3,490 SY
SURFACE UNDER GUARDRAIL		1,519 SY
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II		2,112 BDAY
BARRICADE, TYPE III		388 BDAY
TYPE B HIGH INTENSITY WARNING LIGHT		194 LDAY
TEMPORARY SIGN DAY		1,045 EACH
SIGN DAY		6,305 EACH
FLAGGING		110 DAY
FURNISHING AND OPERATING PILOT VEHICLE		40 DAY
FIELD OFFICE		1 EACH
MOBILIZATION	LUMP	LUMP

□