

NOTICE TO CONTRACTORS

CALL ORDER F11  
 FEDERAL PROJECT NO. EACNH-26-1(155)  
 LOCATION: ON US-26, SCOTTSBLUFF - MINATARE IRRIGATION STRUCTURES.  
 COUNTIES: SCOTTS BLUFF

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on September 05, 2002 At that time the bids will be opened and read for CULVERTS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR:

CULVERTS

START DATE 11/04/02 CALENDAR DAYS 146  
 Price Range \$ 100,000 to \$ 500,000  
 Plans and specifications may be seen beginning August 13, 2002 at the Lincoln Central Office and August 19, 2002 at the District Engineer's Office at BRIDGEPORT

Additional letting information may be found at the Nebraska Department of Roads' Web Site at <http://www.dor.state.ne.us/letting/>

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

LIST OF PLANS

SHEET NO.	TITLE PAGE
1	TITLE PAGE
2S	SUMMARY OF QUANTITIES
2H1-2H4	HORIZONTAL ALIGNMENT & CONTROL POINTS
2N1-2N2	GENERAL INFORMATION
3 - 20	PLAN & PROFILE SHEETS
21 - 27	DRAINAGE STRUCTURE CROSS SECTIONS
28	SPECIAL PLAN 1C PIPE SIPHON
29	SPECIAL PLAN 2C CONCRETE APRON
30 - 32	SPECIAL PLAN 3C 3700 MM X 1500 MM TWIN SPAN RC BOX CULVERT STA. 119+26.34
33 - 34	SPECIAL PLAN 4C 3600 MM X 1800 MM SINGLE SPAN RC BOX CULVERT STA. 162+36.19
35 - 37	SPECIAL PLAN 5C 3000 MM X 1300 MM SINGLE SPAN RC BOX CULVERT STA. 164+02.05
38 - 40	SPECIAL PLAN 6C 3000 MM X 1200 MM SINGLE SPAN RC BOX CULVERT STA. 3199+69.21
R1 - R10	RIGHT-OF-WAY SHEETS

STANDARD PLANS

M403-R1	(2 SHEETS) BENDS AND BREAKS FOR CONCRETE BOX CULVERTS
M410	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
M425	COLLARS AND ELBOWS FOR CONCRETE PIPES
M428-R1	CONCRETE PLUGS AND FIELD PIPE TAP DETAILS
M920	(2 SHEETS) TRAFFIC CONTROL

M921 TRAFFIC CONTROL  
M922 TRAFFIC CONTROL DEVICES

PLANS (NOT INCLUDING STANDARDS) 56 SHEETS \$11.20  
STANDARD PLANS 10 SHEETS 2.00

□

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 4 CULVERT

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EARTHWORK MEASURED IN EMBANKMENT		3,404 m3
REMOVE CONCRETE DITCH LINER		263 m2
CONCRETE DITCH LINING - 1.8 m		59 m
REMOVE HEADWALLS FROM CULV		12 EACH
PREPARATION OF STRUCTURE		1 EACH
AT STA. 162+36.19		
PREPARATION OF STRUCTURE		1 EACH
AT STA. 164+02.05		
PREPARATION OF STRUCTURE		1 EACH
AT STA. 3199+69.21		
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL		674 m3
EXCAVATION FOR BOX CULVERTS		587 m3
47B-20 OR AX-20 CONC FOR HDWL		12 m3
47B-20 OR AX-20 CONC FOR BOX CULV		201 m3
47B-20 OR AX-20 CONC FOR CONCRETE COLLAR		3 m3
47B-20 OR AX-20 CONC FOR PIPE PLUG		1 m3
RE-STEEL FOR HEADWALL		560 kg
RE-STEEL FOR BOX CULVERT		14,505 kg
RE-STEEL FOR COLLARS		159 kg
600 mm CORRUGATED METAL PIPE		31 m
600 mm REINFORCED CONCRETE PIPE		116 m
900 mm REINFORCED CONCRETE PIPE		76 m
1200 mm REINFORCED CONCRETE PIPE		26 m
1200 mm CONCRETE FLARED-END SECTION		1 EACH

GROUP 4A CULVERT AT STA. 119+26.34

MOBILIZATION	LUMP	LUMP
CULVERT CLEANOUT		1 EACH
AT STA. 119+26.34		
PREPARATION OF STRUCTURE		1 EACH
AT STA. 119+26.34		
EXCAVATION FOR BOX CULVERTS		148 m3
47B-20 OR AX-20 CONC FOR BOX CULV		132 m3
RE-STEEL FOR BOX CULVERT		8,751 kg

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE III		2,290 BDAY
TYPE B HIGH INTENSITY WARNING LIGHT		438 LDAY
SIGN DAY		4,734 EACH
FLAGGING		50 DAY
FIELD OFFICE		1 EACH
MOBILIZATION	LUMP	LUMP

□