

NOTICE TO CONTRACTORS

CALL ORDER F14  
FEDERAL PROJECT NO. EACSTPD-47-2(108)  
STPP-47-2(109)  
LOCATION: ON N-47, SOUTH OF GOTHENBURG.  
COUNTIES: DAWSON

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on September 05, 2002 At that time the bids will be opened and read for BRIDGE

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR:

BRIDGES

START DATE 06/09/03 WORKING DAYS 85  
Price Range \$ 100,000 to \$ 500,000  
Plans and specifications may be seen beginning  
August 13, 2002 at the Lincoln Central Office and  
August 19, 2002 at the District Engineer's Office  
at NORTH PLATTE

Additional letting information may be found at the Nebraska Department of Roads' Web Site at <http://www.dor.state.ne.us/letting/>

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

LIST OF PLANS

SHEET NO.  
PROJECT NO. EACSTPD-47-2(108)  
1 TITLE PAGE  
2T1-2T2 TYPICAL CROSS SECTIONS  
2S SUMMARY OF QUANTITIES  
2W WETLANDS  
2H HORIZONTAL ALIGNMENT & CONTROL POINTS  
2N GENERAL INFORMATION  
3 - 4 PLAN & PROFILE SHEETS  
5 TYPICAL YIELD CONTROL FOR LOW VOLUME,  
ONE LANE, TWO WAY OPERATION  
6 TRAFFIC CONTROL PLAN  
7 EARTHWORK DATA SHEET  
8 - 25 SPECIAL PLAN 1 ROLLED BEAM STEEL GIRDER BRIDGE  
WIDEN & REHAB  
STA. 1020+36.45  
26 - 31 SPECIAL PLAN 1C GUARDRAIL PLAN  
32 SPECIAL PLAN 2C SILT FENCE DETAILS  
X1 - X12 CROSS SECTIONS

STANDARD PLANS

501-R3 EROSION CONTROL  
920-R5 (2 SHEETS) TRAFFIC CONTROL  
921-R4 TRAFFIC CONTROL

PROJECT NO. STPP-47-2(109)

1 TITLE PAGE  
2T TYPICAL CROSS SECTIONS  
2S SUMMARY OF QUANTITIES  
2N GENERAL INFORMATION

- 3 PLAN SHEET
- 4 TYPICAL YIELD CONTROL FOR LOW VOLUME,  
ONE LANE, TWO WAY OPERATION
- 5 SPECIAL PLAN 1C REMODEL BRIDGE CURB  
REF. POST NO. 57+57
- 6 - 10 SPECIAL PLAN 2C GUARDRAIL PLAN

STANDARD PLANS

- 501-R3 EROSION CONTROL
- 920-R5 (2 SHEETS) TRAFFIC CONTROL
- 921-R4 TRAFFIC CONTROL

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	49 SHEETS	\$ 9.80
CROSS SECTIONS SHEETS X1 THRU X12 ON PROJECT NO. EACSTPD-47-2(108)	12 SHEETS	2.40
STANDARD PLANS	4 SHEETS	.80

□

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 6 BRIDGE AT STA. 1020+36.45

EROSION CONTROL, TYPE HV		2,188 SY
FABRIC SILT FENCE-LOW POROSITY		200 LF
BARRICADE, TYPE II		684 BDAY
BARRICADE, TYPE III		456 BDAY
TYPE B HIGH INTENSITY WARNING LIGHT		228 LDAY
SIGN DAY		3,876 EACH
PAVEMENT MARKING REMOVAL		155 LF
TEMP PVMT MARKING, TYPE II		2,000 LF
TEMP PVMT MARKING SURF PREP		1,000 LF
INSTALL CONC PROTECT BARRIER		470 LF
RELOCATE CONC PROTECTION BARRIER		470 LF
FIELD OFFICE		1 EACH
MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)		225 CY
WATER		12 MGAL
EARTHWORK MEASURED IN EMBANKMENT		517 CY
RIPRAP FILTER FABRIC		80 SY
REMOVE PAVEMENT		551 SY
CONC FOR PVMT APPROACHES CLASS 47BD-4000		191 CY
EPOXY COATED RE-STEEL FOR PVMT APPROACH		21,470 LB
ABUTMENT NO.1 EXCAVATION	LUMP	LUMP
ABUTMENT NO.2 EXCAVATION	LUMP	LUMP
PRECOMPRESSED POLY FOAM JOINT		107 LF
EXPANSION BEARING, TFE TYPE		6 EACH
FIXED BEARING		6 EACH
47B-3000 CONC FOR BRIDGE		54 CY
47BD-4000 CONC FOR BRIDGE		87 CY
PREP BRIDGE		1 EACH
AT STA. 1020+36.45		
STEEL SUPERSTRUCTURE	LUMP	LUMP
AT STA. 1020+36.45		
ROCK RIPRAP, TYPE A		25 TON
ROCK RIPRAP, TYPE B		205 TON
EPOXY COATED RE-STEEL		20,625 LB

F14NTC09.TXT

HP 10"X42# STEEL PILING	1,040	LF
TEMP BRIDGE SHORING	LUMP	LUMP
W-BEAM GUARDRAIL	100	LF
REMOVE GUARDRAIL	281	LF
BRIDGE APPROACH SECTIONS	4	EACH
GUARDRAIL END TREATMENT, TYPE II	4	EACH
4" YEL PREF PVMT MRKING T-4	200	LF
GRANULAR BACKFILL	85	CY
ASPH CONC, TYPE SP2(0.5)	180	TON
TEMPORARY SURFACING	51	SY
PERF GRADED BINDER (64-22)	9	TON
RENTAL OF LOADER, FULLY OPERATED	10	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	10	HOUR

□

GROUP 6 BRIDGE AT STA. 1020+36.45

RENTAL OF BACKHOE, FULLY OPERATED	10	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	10	HOUR
SURFACE UNDER GUARDRAIL	94	SY

GROUP 6A BRIDGE AT STA. 175+57

EROSION CONTROL	847	SY
BARRICADE, TYPE II	186	BDAY
BARRICADE, TYPE III	124	BDAY
TYPE B HIGH INTENSITY WARNING LIGHT	62	LDAY
SIGN DAY	1,054	EACH
PAVEMENT MARKING REMOVAL	2,000	LF
TEMPORARY PAVEMENT MARKING	1,250	LF
TEMP PVMT MARKING SURF PREP	750	LF
RELOCATE CONC PROTECTION BARRIER	800	LF
MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
ROADWAY GRADING	2	STA
REMOVE ASPHALT SURFACE	262	SY
47BD-4000 CONC FOR BRIDGE	23	CY
RE-STEEL FOR BRIDGE	2,515	LB
W-BEAM GUARDRAIL	68	LF
REMOVE GUARDRAIL	400	LF
BRIDGE APPROACH SECTIONS	4	EACH
GUARDRAIL END TREATMENT, TYPE II	4	EACH
SURFACE UNDER GUARDRAIL	241	SY

□