

STATE OF NEBRASKA  
DEPARTMENT OF ROADS

LETTING DATE: SEPTEMBER 5, 2002

ADDENDUM NO.	CALL NO.	PROJECT NO.	CONTROL NO.	LOCATION
5	N01	S-77-2(1038)	11801B	CERESCO - WAHOO
3	F05	EACNH-BH-30-7(115)	21794 1	BLAIR - KENNARD
2	F09	NH-81-3(134)	31663 1	COLUMBUS SOUTH
2	F13	EACIM-80-4(81)	60669	GOTHENBURG EAST
2	F14	EACSTPD-47-2(108) STPP-47-2(109)	61197 61292	GOTHENBURG SOUTH GOTHENBURG SOUTH
2	F21	BR-3680(6)	12587	TALMAGE SOUTHEAST

The following changes are made to Subsection 706.03 in the 1997 Standard Specifications, in both the English and Metric Editions:

1. Paragraph 2.b. is amended to read:

b. Bridge floor concrete shall not be placed when the ambient air or concrete temperature is above 90° F (32° C).

2. In **Table 706.01**, the "Air Temperature in the Shade" value of 86° F (30° C) is amended to read 90° F (32° C) and the "Maximum Wind Velocity" value of 9 mph (15 kmph) is amended to read 10 mph (16 kmph).

DEPARTMENT OF ROADS

Claude Oie  
Construction Engineer

Issued: August 29, 2002

CO:addensad309

NOTICE: Only the contractors issued bidding proposals receive this addendum and

responsibility for notifying any potential subcontractors or suppliers remains with the contractor.