

STATE OF NEBRASKA  
DEPARTMENT OF ROADS  
ADDENDUM NO. 2  
PROJECT NO. EACIM-80-8(102)  
CONTROL NO. 12564  
CALL ORDER F03  
I-80, MILFORD - LINCOLN  
LETTING DATE: SEPTEMBER 5, 2002

On page 74 of the Special Provisions, in the provision titled SUPERPAVE ASPHALTIC CONCRETE, the first sentence of the first paragraph is amended to read:

Asphaltic Concrete Type SP6 shall use the 0.375 inch gradation band for the top 1½ inch lift of the interstate mainline and mainline inside shoulder.

\* \* \* \* \*

On plan sheet 2-T1, in the INTERCHANGE RAMPS typical cross-section, the thickness and width dimensions are amended to read:

1. For the ramp mainline → 2" x 0' MIN. / 40' MAX.
2. For the ramp shoulder → 2" x 8' MIN.

\* \* \* \* \*

The plans will not be revised to reflect these changes to sheet 2-T1.

DEPARTMENT OF ROADS

Claude Oie  
Construction Engineer

Issued: August 19, 2002

CO:KM:F03AD209

NOTICE: Only the contractors issued bidding proposals receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the contractor.