

INFORMATIONAL PROPOSAL (For information only, not to be used for bidding)

NEBRASKA DEPARTMENT OF ROADS
LETTING DATE : November 14, 2002

CALL ORDER: N24 CONTRACT ID: 1579

CONTROL NO./SEQ. NO.: 12579 /000 PROJECT NO.: PEP-92-6(1010)

TENTATIVE START DATE: 06/16/03 CONTRACT TIME: 80 WORKING DAYS

LOCATION: N-92, IN RISING CITY AND EAST

IN COUNTY: BUTLER

BIDDER

GROUP 9 BITUMINOUS

SEE NOTICE TO BIDDERS SPECIAL PROVISION FOR COMBINED BID REQUIREMENT

NOTES

THE TOTAL AMOUNT OF WORK WHICH WILL BE ACCEPTED IN THIS LETTING IS
LIMITED TO \$_____.

THE NUMBER OF _____ CONTRACTS WHICH WILL BE ACCEPTED IN THIS
LETTING IS LIMITED TO ____.

NOTICE TO ALL BIDDERS

To report bid rigging activities, call: 1-800-424-9071

The U.S. Department of Transportation (DOT) operates the above toll-free "hotline" Monday through Friday, 8:00 a.m. to 5:00 p.m. eastern time. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the "hotline" to report such activities.

The "hotline" is part of the DOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

LETTING QUESTIONS

Prior to the letting, any questions pertaining to the Special Provisions or the plans for this project should be directed to Construction Division personnel at (402) 479-4568 or (402) 479-4529.

STATE OF NEBRASKA
DEPARTMENT OF ROADS

Required Provisions Supplemental to the
Standard Specifications for Highway Construction

I. Application

These contract provisions shall apply to all work performed on the contract by the contractor with his own organization and with the assistance of workmen under his immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.

The contractor shall insert in each of his subcontracts all of the stipulations contained in the Special Provisions and these Required Provisions.

A breach of any of the stipulations contained in these Required Provisions may be grounds for termination of the contract.

II. Equal Opportunity

1. **Selection of Labor**

During the performance of this contract, the contractor shall not discriminate against labor from any other state.

2. **Nebraska Fair Employment Practices Act**

The contractor shall not discriminate against any employee or applicant for employment, to be employed in the performance of this contract with respect to his hire, tenure, terms, conditions, or privileges of employment, because of his race, color, religion, sex or national origin. The contractor agrees to post in a conspicuous place or places a notice to be provided by the State Highway Department which sets forth excerpts of the Act.

3. **Nebraska Equal Pay Act**

The contractor shall not discriminate on the basis of sex by paying wages to employees of one sex at a lesser rate than the rate paid to employees of the opposite sex for comparable work on jobs which have comparable requirements. An abstract of the Act is included on the notice which is provided by the State Highway Department.

April 4, 1995

III. Employment of Labor

1. **General**

No person under the age of sixteen (16) years, and no one whose age or physical condition is such as to make his employment dangerous to his health or safety, or to the health and safety of others shall be employed on any project. This paragraph shall not be construed to deny the employment of older people or physically handicapped persons, otherwise employable, where such persons may be safely assigned to work which they can ably perform.

No person currently serving sentence to a penal or correction institution shall be employed on any project.

Except as specifically provided under this section, workers who are qualified by training or experience to be assigned to projects of this character shall not be discriminated against on any grounds whatsoever.

2. **Payrolls**

Payrolls and basic records relating thereto will be maintained during the course of the work and preserved for a period of three years thereafter for all laborers and mechanics working on the site of the work.

The contractor's and subcontractor's payroll records shall be available for inspection by authorized representatives of the State Highway Department and authorized representatives of Federal Agencies.

The wages of labor shall be paid in legal tender of the United States, except that this condition will be considered satisfied if payment is made by a negotiable check, on a solvent bank, which may be cashed readily by the employee in the local community for the full amount, without discount or collection charges of any kind. Where checks are used for payment the contractor shall make all necessary arrangements for them to be cashed and shall give information regarding such arrangements.

No fee of any kind shall be asked or accepted by the contractor or any of his agents from any person as a condition of employment on the project.

No laborers shall be charged for any tools used in performing their respective duties except for reasonably avoidable loss or damage thereto.

Every employee on the work covered by this contract shall be permitted to lodge, board and trade where and with whom he elects and neither the contractor nor his agents, nor his employees shall directly or indirectly require as a condition of employment that an employee shall lodge, board or trade at a particular place or with a particular person.

No charge shall be made for any transportation furnished by the contractor or his agents to any person employed on the work.

April 4, 1995

No individual shall be employed as a laborer on this contract except on a wage basis, but this shall not be construed to prohibit the rental of teams, trucks or other equipment from individuals. No such rental agreement, or any charges for feed, gasoline, supplies, or repairs on account of such agreement, shall cause any deduction from the wages accruing to any employee except as authorized by the regulations hereinbefore cited.

IV. Safety and Accident Prevention

In the performance of this contract, the contractor shall comply with all applicable Federal, State and local laws governing safety, health and sanitation. The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions, on his own responsibility or as the contracting officer may determine, reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.

V. Subletting or Assigning the Contract

The contractor shall perform with his own organization contract work amounting to not less than 30 percent of the total contract amount except that any items designated in the contract as "Specialty Items" may be performed by subcontract and the amount of any such "Specialty Items" so performed may be deducted from the total contract amount before computing the amount of work required to be performed by the contractor with his own organization.

Any items that have been selected as "Specialty Items" for the contract are listed as such in the Special Provisions found elsewhere in the contract.

No portion of the contract shall be sublet, assigned, or otherwise disposed of except with the written consent of the contracting officer or his authorized representative. Requests for permission to sublet assign or otherwise dispose of any portion of the contract shall be in writing and accompanied by a showing that the organization which will perform the work is particularly experienced and equipped for such work. The contractor shall give assurance that the minimum wage for labor as stated in his proposal shall apply to labor performed on all work sublet, assigned or otherwise disposed of in any way. Consent to sublet, assign or otherwise dispose of any portion of the contract shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract.

April 4, 1995

**SPECIAL PROVISIONS
FOR
STATE
PROJECT NO. PEP-92-6(1010)**

GENERAL CONDITIONS

Sealed bids for the work contemplated in this proposal form will be received at the office of the Nebraska Department of Roads in Room 104 of the Central Office Building at 1500 Highway 2 at Lincoln, Nebraska, on November 14, 2002, until 1:30 P.M.

Bids submitted by mail should be addressed to the Nebraska Department of Roads, c/o Contract Lettings Section, P.O. Box 94759, Lincoln, NE 68509-4759.

The 1997 English Edition of the Standard Specifications for Highway Construction, including all amendments and additions thereto effective at the date of the contract, are made a part of these Special Provisions, through reference.

The Supplemental Specifications to the 1997 English Edition of the Standard Specifications for Highway Construction dated July 12, 2001, including all amendments and additions thereto effective at the date of the contract, are made part of these Special Provisions, through reference.

The Required Provisions dated April 4, 1995, are attached to and are a part of this proposal form.

The attention of bidders is directed to the Required Provisions covering subletting or assigning the contract.

The proposal contains a statement that the contractor is complying with, and will continue to comply with, fair labor standards in the pursuit of his business and in the execution of the work contemplated in this proposal.

Fair labor standards shall be construed to mean such a scale of wages and conditions of employment as are paid and maintained by at least fifty per cent of the contractors in the same business or field of endeavor as the contractor filing this proposal.

NOTICE TO BIDDERS

To be eligible for the award of this contract, bidders shall submit a completed bidding proposal for Call Order No. N04 [Project No. S-S80C(1007)], Call Order No. N23 [Project No. RD-15-2(1019)], and Call Order No. N24 [Project No. PEP-92-6(1010)].

Award of Contract, if awarded, will be made on the combined bid for all contracts.

Separate contracts will be awarded for each Call Order Number.

Paragraph 1.a.(2) of Subsection 108.01 in the 1997 Standard Specifications is void and superseded by the following:

With the Engineer's consent, the Contractor may sublet up to 70 percent of the work for the combined contracts.

STATUS OF UTILITIES

No utilities have been or will be required to relocate within the limits of this project.

Underground utilities may exist within the limits of this project. The Contractor shall determine to his satisfaction the extent of occupancy of any underground utilities located within the respective construction areas and the extent of conflict with the proposed work under this contract.

Any utility adjustments or interruption of service for the convenience of the Contractor shall be the sole responsibility of the Contractor.

To arrange for utilities to locate and flag their underground facilities, contact The Diggers Hotline of Nebraska at 1-800-331-5666.

STATUS OF RIGHT-OF-WAY (S1-16-0801)

According to the best information available, all necessary right-of-way has been acquired.

SUBCONTRACTOR BIDDERS LIST INFORMATION (S1-43-0801)

All bidders must complete and submit with the bidding proposal, the "Subcontractor Bidders List" form provided by the NDR Contracts office.

Bidders must identify all firms who bid or quote subcontracts on all projects. If no bids or subcontractor quotations are received, the "Subcontractor Bidders List" must be submitted with the bidding documents and the bidder must indicate on the face of the "Subcontractor Bidders List" that no bids or subcontractor quotations were received.

**CONTROL OF WORK
(S1-43-0901)**

Subsection 105.08 in the 1997 Standard Specifications is void and replaced by the following:

105.08 - Authority and Duty of the Inspector

Department inspectors are authorized to inspect all work performed and all materials furnished. Such inspection may extend to the preparation, fabrication, or manufacture of the materials. The inspector has the authority to reject work or materials until any issues can be decided, including the right to suspend work. The inspector is not authorized to alter or waive the provisions of the contract or act as a supervisor for the Contractor.

105.13 – Tentative Acceptance of Portions of the Project

Paragraph 3.a. of Subsection 105.13 is amended by deleting the word “normal”.

**LEGAL RELATIONS AND RESPONSIBILITY TO THE PUBLIC
(S1-43-1001)**

107.14 – Opening of Sections of the Project to Traffic

Subsection 107.14 Paragraphs 2.b.(1) and (2) are void and replaced by the following:

2.b. (1) Whenever the Department permits the public use of a highway undergoing construction, repair, or maintenance in lieu of a detour route, the Contractor shall not be held responsible for damages to those portions of the project upon which the Department permitted public use, when such damages are the result of no proximate act or failure to act on the part of the Contractor.

(2) If the traveling public should cause damage to the roadway, the Contractor shall assist the State in identifying the responsible party and the Contractor shall as a minimum if present at the time of the damage record pertinent information regarding the accident. (Who caused the damage; when the damage occurred; and how the damage occurred.)

107.15 – Contractor’s Responsibility for Work

Subsection 107.15 is amended by adding Paragraph 1.b.(3) as follows:

(3) The Contractor shall not be held responsible for damage caused by the traveling public on those portions of the project where the Department has permitted public use of the road in lieu of using a detour route and the damage as not the result of any proximate act or failure to act on the part of the Contractor.

**MEASUREMENT AND PAYMENT
(S1-43-0901)**

109.08 – Acceptance, Final Payment, and Termination of Contractor's Responsibility

Subsection 109.08 Paragraph c. amended by deleting the word "normal".

Subsection 109.08 Paragraph d. is void and replaced by the following:

d. If the traveling public should cause damage to the roadway the Contractor shall assist the State in identifying the responsible party and the Contractor shall as a minimum if present at the time of the damage record pertinent information regarding the accident. (Who caused the damage; when the damage occurred; and how the damage occurred.)

**SPECIAL PROSECUTION AND PROGRESS
(Milling/Overlay)**

The contractor will be required to begin the overlay portion of the project no later than 21 calendar days after the start of the milling portion of the project.

Should the overlay operation begin later than 21 calendar days after the start of the milling operation, any pavement deterioration which, in the opinion of the engineer, occurs after this 21 calendar day period, will be repaired by the contractor at no cost to the state.

Exceptions to this requirement will be considered only when the delaying circumstances are, in the opinion of the engineer, beyond the control of the contractor.

THE BURLINGTON NORTHERN AND SANTA FE RAILWAY COMPANY

**WORK TO BE PERFORMED BY THE
RAILROAD COMPANY**

The Burlington Northern and Santa Fe Railway Company will perform, or cause to be performed, such temporary and permanent alterations of telegraph, telephone, signal wires and signals, tracks or other facilities on its right of way as are required. According to the best information available at this time it may be necessary for the Railroad Company to perform work within the limits of the project concurrently with the highway construction work. The company agrees to furnish to the State a drawing showing the location of the existing facilities and their relocation.

The Railroad Company shall provide an inspector or inspectors for any direct labor work undertaken by the Railroad Company on or in connection with the project.

**RAILROAD SAFETY TRAINING
(S1-22A-0801)**

The railroad company requires that anyone working within the railroad right-of-way attend a "Rail Safety Training" class. The Contractor, or their representative, will not be allowed on railroad right-of-way until they have successfully completed the mandatory safety training. The railroad will present a certification card to everyone who completes their safety training, and construction crews will be required to have their safety training certification cards in their possession at all times when they are working on railroad right-of-way.

The contractor will be responsible for all costs associated with attending this training class.

FLAGGING PROTECTION

When, for any reason, the Manager Public Projects or other duly authorized representative of The Burlington Northern and Santa Fe Railway Company shall deem it necessary to employ flagmen for the protection of train operations, such flagmen shall be furnished by the Railroad Company and all costs for such flagmen shall be borne by the contractor.

Prospective bidders shall familiarize themselves fully with the Railroad Company's requirements for flagging protection before bidding on the work.

**REIMBURSEMENT TO RAILROAD COMPANY
FOR FLAGGING COSTS
(S1-24-0801)**

At all times while performing such work, flagmen shall be deemed to be employees of the Railroad Company.

The contractor shall reimburse the Railroad Company directly for this flagging protection and shall make a showing that the Railroad Company has been reimbursed for all necessary flagging required by his operations before final payment for the work contemplated in the contract is made by the State.

Direct payment for flagging protection as required in these special provisions will not be made but it shall be considered that this work is subsidiary to any or all of the items for which the contract provides that direct payment shall be made.

**FLAGGING CONDITIONS
(S1-25-0801)**

Flagging and other protective services and devices will be provided by the Company to protect its facilities, property and movements of its trains or engine.

In general, the Company will furnish such flagging or other protective services and devices:

- (a) For any excavation below elevation of track subgrade, if, in the opinion of the Company's representative, track or other railroad facilities may be subject to settlement or movement.
- (b) During any clearing, grubbing, grading or blasting in proximity to the railroad, which, in the opinion of the Company's representative, may endanger or interfere with the railroad's facilities or operations.
- (c) When any of the Contractor's operations are carried on or within the Railroad Company's right of way and in the opinion of the Company's representative could endanger Company's facilities or create a hazard to the Company's operations.

PROTECTION OF UTILITIES (S1-26-0801)

Before the contractor begins his operations on the railroad right-of-way he shall confer with the official representatives of the State and the Railroad Company with regard to any underground or overhead utilities which may be on or in close proximity to the site of the work. The contractor shall take such measures as the State or Railroad Company may direct in protecting those utilities properly throughout the period his construction operations are in progress. The party or parties owning or operating overhead or underground utilities shall perform the actual work of moving, repairing, reconditioning or revising those utilities, except as otherwise provided in the contract. Whenever and wherever such operations are undertaken by owners of utilities, the contractor shall cooperate to the extent that ample protection of their work will be provided so that the entire work that is contemplated in the contract may be expedited to the best interests of all concerned, as judged by the engineer for the State.

The contractor shall be responsible for any and all damages to utilities that are permitted to remain in place, or to reconstructed utilities in the vicinity, which may be due either directly or indirectly to his operations, and shall repair promptly any such damaged property to the satisfaction of the engineer and the owner of the property, or shall make payment to such owners for repairs as may become necessary on account of damages that are due to his operations.

Direct payment for this work will not be made but it shall be considered that the protection of the utilities is subsidiary to any or all of the items for which the contract provides that direct payment shall be made.

RAILROAD SPECIAL PROVISIONS

Before the contractor begins his operations on railroad right of way, he will contact the railroad at least 10 days in advance by telephone at 1-800-533-2891 (a 24-hour number) to determine if fiber optic cable is buried anywhere on the railroad property to be used by the contractor.

The railroad will advise the contractor if fiber optic cable exists at the location(s) being occupied and will dispatch a representative to locate, mark and protect each cable in the vicinity of the work to be performed by the contractor.

The railroad will need the Railroad Mile Post involved which is 49.02 on this project.

The contractor, for his own protection, should obtain and record the "Trouble Log Number" from the railroad for verification of the call made.

WRITTEN NOTICE TO RAILROAD COMPANY

The contractor shall give written notice to the Manager Public Projects or to his authorized representative, at least ten days in advance of the date on which he expects to begin any work under or adjacent to any of the tracks of the Railroad Company or he expects to begin any construction work on the right of way of the Railroad Company. The contractor shall also give written notice to the Manager Public Projects no later than ten days after completion of all work on the railroad company's right of way.

BRIDGE REMOVAL PLANS (S1-28A-0801)

The Contractor shall submit a complete Bridge Removal Plan to the Railroad by certified mail. The Bridge Removal Plan shall include details, procedures and the sequence of staged removal of the bridge, including all steps necessary to remove the bridge in a safe and controlled manner.

The Contractor shall submit to the Railroad: three (3) complete sets of the Contractor's Bridge Removal Plan for review and comments. The Plan shall be sealed by a Civil or Structural Engineer registered in the State of Nebraska. A minimum of three (3) weeks shall be allowed for the Railroad's review after the complete submittal is received. No removal operations will be permitted over the Railroad right-of-way until the submitted material has been reviewed and comments provided.

PROTECTION OF PROPERTY (S1-29-0801)

The contractor shall use the utmost care to guard against accidents or cause the least possible interference with the operation of trains of the Railroad Company and the telephone, telegraph or signal lines of the Railroad Company or of any tenant of the Railroad Company's right-of-way. The contractor shall use the utmost care in guarding against injury to underground and overhead public utilities and services at or near the site of the work.

All work to be done under this contract shall be handled by the contractor so as to interfere as little as is reasonably possible with the use of tracks, wires, signals and property of the Railroad Company or its tenants, and the underground or overhead services of public and private utilities, and the contractor shall be responsible for any damages which may be sustained by the Railroad Company, its tenants, employees, passengers or freight in its care, or by the owners of any public or private overhead or underground services caused by such interferences which could have been avoided by the proper handling of said work. The

contractor shall discontinue immediately, upon request of the engineer, any practices or actions which, in the opinion of the engineer, are unsafe or cause damage to underground or overhead services of public or private utilities, or which might result in delays to trains, engines or cars, or damage to tracks, roadbed, telephone, telegraph or signal wires.

The contractor shall take all precautions for the purposes of protecting the embankment of all railroad tracks as may be determined necessary by the authorized representative of the Railroad Company. The contractor agrees to affix the seal of a registered professional engineer licensed to practice in the State of Nebraska on all plans and calculations pertaining to details for sheeting or otherwise protecting excavations next to or adjacent to railroad tracks if necessary and noted on the State's plans. The contractor also shall take all precautions for the protection of underground and overhead services either public or private, as may be determined by the engineer.

PROTECTION OF PROPERTY

The contractor shall not place or permit to be placed, or remain, piles of material or other temporary obstructions closer than 12 feet (3.7 meters) to the nearest rail of any track or closer than 23 feet (7 meters) above the top of any rail except that the construction forms and scaffolding may be placed no closer than 12 feet (3.7 meters) from the centerline of any such track.

Any changes necessary in the clearance set forth above shall be made only by special arrangements with the Manager Public Projects of the Company or his authorized representative.

The contractor agrees to affix the seal of a registered professional engineer licensed to practice in the State of Nebraska on all plans and calculations pertaining to details for sheeting or otherwise protecting excavations next to or adjacent to railroad tracks if necessary and noted on the State's plans.

RAILROAD CROSSINGS (S1-31-1201)

The Contractor shall use only public roadways or special crossings that are specifically shown on the plans to cross railroad tracks. If the Contractor should desire a temporary crossing for construction purposes at a location other than an existing public crossing, provisions for such crossing shall be negotiated with the railroad by the Contractor, and all costs for such crossing shall be borne by the Contractor.

Prospective bidders should familiarize themselves with railroad temporary crossing and insurance requirements before bidding on the work.

**INSPECTION
(S1-32-0801)**

Subsection 105.09 in the Standard Specifications is amended to provide also that the work shall be subject to the inspection of the properly authorized representatives of the railroad and that such inspection shall in no sense make the railroad a party to this contract and will in no way interfere with the rights of either party hereunder.

**INSURANCE
(S1-33-1201)**

The State shall require its Contractor or any of his subcontractors to carry regular Contractor's Public Liability and Property Damage Insurance as specified in Federal-Aid Policy Guide 23 CFR 646A providing for a limit of not less than Two Million Dollars (\$2,000,000) for all damages arising out of bodily injuries to or death of one person, and subject to that limit for each person, a total limit of not less than Four Million Dollars (\$4,000,000) for all damages arising out of bodily injuries to or death of two or more persons in any one accident and providing for a limit of not less than Two Million Dollars (\$2,000,000) for all damages to or destruction of property in any one accident and subject to that limit a total (or aggregate) limit of not less than Four Million Dollars (\$4,000,000) for all damages to or destruction of property during the policy period. A certified copy of the policy providing said Contractor's Public Liability and Property Damage Insurance executed by a corporation qualified to write the same in the State in which the work is to be performed, in form and substance satisfactory to the Railroad, shall be delivered to and approved by the Railroad prior to the entry upon or use of the Railroad's property by the Contractor.

In addition to any other forms of insurance or bonds required under the terms of the contract and the specifications, the Contractor shall furnish to the Railroad a Railroad Protective Policy in the form provided by Federal-Aid Policy Guide 23 CFR 646A. The combined single limit of said policy shall not be less than Two Million Dollars (\$2,000,000) for all damages arising out of bodily injuries to or death of any person or persons and for all damages arising out of loss or destruction of or injury or damage to property in any one occurrence during the policy period; and subject to that limit, a total (or aggregate) limit of not less than Six Million Dollars (\$6,000,000) for all damages arising out of bodily injuries to or death of any person or persons and for all damages arising out of or loss or destruction of or injury or damage to property during the policy period. Said insurance policy executed by a corporation qualified to write the same in the State in which the work is to be performed shall be in form and substance satisfactory to the Railroad and shall be delivered to and approved by the Railroad prior to the entry upon or use of its property by the Contractor.

The above mentioned insurance shall be written in accordance with the Federal-Aid Policy Guide 23 CFR 646A issued by the Federal Highway Administration, which is hereby, through reference, made a part of these provisions.

The State shall require its Contractor or any of its subcontractors to carry a Business Automobile Insurance Policy or equivalent policy with minimum limits of one million dollars (\$1,000,000) for bodily injury and property damage per occurrence on all vehicles which the Contractor or subcontractors, their agents or employees may use at any time in connection with the performance of the work on this project. A certified copy of the policy providing said Business Automobile Insurance executed by a corporation qualified to write the same in the state in which the work is to be performed, in form and substance satisfactory to the companies,

shall be delivered to and approved by the companies prior to the entry upon or use of the companies property by the Contractor.

The insurance as hereinbefore specified shall be carried by the Contractor and the Railroad covering all work performed on this project within the limits of the rights-of-way of the Railroad. Said insurance shall be carried until all work required under the terms of the contract is satisfactorily completed, as evidenced by formal acceptance by the State.

The State's Contractor shall cause triplicate originals of the policy or policies covering the Railroad Protective Liability Insurance specified above to be delivered to the State for delivery to the Railroad. The Contractor shall not enter upon or perform any work upon the property or the rights-of-way of the Railroad until the specified originals of the policy or policies have been delivered to and approved by the Railroad. The Contractor shall deliver one original policy of the above described Contractor's Property Damage Liability Insurance and one copy of the Business Automobile Insurance Policy to the State prior to the beginning of any work on the Railroad's right-of-way.

In addition to the above, the Contractor shall indemnify and hold the railroad(s) harmless against and from all cost, liability, and expense whatsoever (including the railroad attorney's fees and court costs and expenses) actually incurred arising out of or in any way contributed to by any negligent act or omission of the Contractor and its employees, for any damage to or destruction of any telecommunications system by the Contractor and its employees on the railroad's property.

RIGHT OF WAY (S1-34-0801)

The right of way and property which the public has, or will have, by ownership or easement, for the permanent construction and the prosecution of the construction operations, is indicated in the plans or will be defined upon request. Any additional ground, or working or storage space that the contractor may require for his operations, shall be provided by the contractor at his own expense.

RESTORATION OF RAILROAD COMPANY'S PROPERTY (S1-35-0801)

In the event the contractor shall in any manner move or disturb other property of the Railroad Company, in connection with the use of the said property, then, and in that event, the contractor shall, as soon as possible and at its sole expense, restore such property to the same condition as it was in before such property was moved or disturbed, and the contractor shall indemnify and save harmless the Railroad Company against and from any and all liability, loss, damages, claims, demands, costs and expenses of whatsoever nature, including court costs and attorneys' fees, which may result from injury to or death of persons whomsoever, or damage to or loss or destruction of property whatsoever, when such injury, death, damage, loss or destruction grows out of or arises from the taking down of any fence, or the moving or disturbance of any other property, of the Railroad Company.

**FINAL CLEANING UP
(S1-36-0801)**

Subsection 104.08 in the Standard Specifications is amended to provide also that upon the completion of the work contemplated in this contract, the contractor shall remove all machinery, equipment, surplus materials, falsework, rubbish, ditches, and temporary building, furnished or erected by him from within the limits of the right of way of the Railroad Company and shall leave the said right of way in a neat condition satisfactory to the Chief Engineer of the Railroad Company, or his authorized representative.

PERCENTAGE OF COST OF WORK WITHIN RAILROAD RIGHT-OF-WAY

The following information is furnished to aid in the determination of a proper premium for the Railroad Protective Liability Insurance required elsewhere in these special provisions.

RAILROAD PROTECTIVE POLICY DATA SHEET

Railroad: The Burlington Northern and Santa Fe Railway Co.

Railroad Contact: Robert Carter

Title: Manager Public Projects

Address: 201 North 7th, Lincoln, NE 68510

Telephone Number: (402) 458-7515

Project Number: PEP-92-6(1010)

Project Location: In Rising City & East

Type of Project: Maintenance/Resurfacing

No. of trains/day: Total: 1

Freight or Coal: 1 Speed: 25 mph Passenger 0 Speed mph

No. of Tracks: Mainline 1 Branchline 0

Project Over RR: No X Yes Project Under Railroad: No X Yes

Railroad Shoo-fly Required: No X Yes

Project Parallel to RR: No X Yes If Yes, Number of Miles

Crossings on State Highway or City Street System: No Yes X at DOT 074749V

If Yes, Number of Crossings 1

Pavement or Overlay up to Crossing on County or City Road:

No X Yes If Yes, Number of Crossings

Work to be done by Railroad Railroad will install a new 50' concrete crossing surface at DOT No. 074749V.

It shall be the contractor's responsibility to contact the railroad for additional information needed to purchase the Railroad Protective Policy.

The percentage of work within railroad right of way that is within 50 feet (15.25 meters) of any railroad track shall be covered by railroad protective insurance. The railroad's ownership of right of way that extends beyond 50 feet (15.25 meters) from the closest track shall be covered under regular Contractor's Public liability and Property Damage Insurance in the amounts specified in this contract.

<u>Group</u>	<u>Approximate Percent of Work Within 50 feet (15.25 meters) of Nearest Track</u>	<u>Approximate Percent of Work on RR/ROW Not Within 50 feet (15.25 meters) of Nearest Track</u>	<u>Description of Work</u>
<u>All</u>	<u>0.1 %</u>	<u>0.0 %</u>	<u>--</u>

NEBRASKA CENTRAL RAILROAD COMPANY

WORK TO BE PERFORMED BY THE RAILROAD COMPANY

The Nebraska Central Railroad Company will perform, or cause to be performed, such temporary and permanent alterations of telegraph, telephone, signal wires and signals, tracks or other facilities on its right of way as are required. According to the best information available at this time it may be necessary for the Railroad Company to perform work within the limits of the project concurrently with the highway construction work. The company agrees to furnish to the State a drawing showing the location of the existing facilities and their relocation.

The Railroad Company shall provide an inspector or inspectors for any direct labor work undertaken by the Railroad Company on or in connection with the project.

RAILROAD SAFETY TRAINING (S1-22A-0801)

The railroad company requires that anyone working within the railroad right-of-way attend a "Rail Safety Training" class. The Contractor, or their representative, will not be allowed on railroad right-of-way until they have successfully completed the mandatory safety training. The railroad will present a certification card to everyone who completes their safety training, and construction crews will be required to have their safety training certification cards in their possession at all times when they are working on railroad right-of-way.

The contractor will be responsible for all costs associated with attending this training class.

FLAGGING PROTECTION

When, for any reason, the Manager Track & Structures or other duly authorized representative of the Nebraska Central Railroad Company shall deem it necessary to employ flagmen for the protection of train operations, such flagmen shall be furnished by the Railroad Company and all costs for such flagmen shall be borne by the contractor.

Prospective bidders shall familiarize themselves fully with the Railroad Company's requirements for flagging protection before bidding on the work.

**REIMBURSEMENT TO RAILROAD COMPANY
FOR FLAGGING COSTS
(S1-24-0801)**

At all times while performing such work, flagmen shall be deemed to be employees of the Railroad Company.

The contractor shall reimburse the Railroad Company directly for this flagging protection and shall make a showing that the Railroad Company has been reimbursed for all necessary flagging required by his operations before final payment for the work contemplated in the contract is made by the State.

Direct payment for flagging protection as required in these special provisions will not be made but it shall be considered that this work is subsidiary to any or all of the items for which the contract provides that direct payment shall be made.

**FLAGGING CONDITIONS
(S1-25-0801)**

Flagging and other protective services and devices will be provided by the Company to protect its facilities, property and movements of its trains or engine.

In general, the Company will furnish such flagging or other protective services and devices:

- (a) For any excavation below elevation of track subgrade, if, in the opinion of the Company's representative, track or other railroad facilities may be subject to settlement or movement.
- (b) During any clearing, grubbing, grading or blasting in proximity to the railroad, which, in the opinion of the Company's representative, may endanger or interfere with the railroad's facilities or operations.
- (c) When any of the Contractor's operations are carried on or within the Railroad Company's right of way and in the opinion of the Company's representative could endanger Company's facilities or create a hazard to the Company's operations.

PROTECTION OF UTILITIES (S1-26-0801)

Before the contractor begins his operations on the railroad right-of-way he shall confer with the official representatives of the State and the Railroad Company with regard to any underground or overhead utilities which may be on or in close proximity to the site of the work. The contractor shall take such measures as the State or Railroad Company may direct in protecting those utilities properly throughout the period his construction operations are in progress. The party or parties owning or operating overhead or underground utilities shall perform the actual work of moving, repairing, reconditioning or revising those utilities, except as otherwise provided in the contract. Whenever and wherever such operations are undertaken by owners of utilities, the contractor shall cooperate to the extent that ample protection of their work will be provided so that the entire work that is contemplated in the contract may be expedited to the best interests of all concerned, as judged by the engineer for the State.

The contractor shall be responsible for any and all damages to utilities that are permitted to remain in place, or to reconstructed utilities in the vicinity, which may be due either directly or indirectly to his operations, and shall repair promptly any such damaged property to the satisfaction of the engineer and the owner of the property, or shall make payment to such owners for repairs as may become necessary on account of damages that are due to his operations.

Direct payment for this work will not be made but it shall be considered that the protection of the utilities is subsidiary to any or all of the items for which the contract provides that direct payment shall be made.

RAILROAD SPECIAL PROVISIONS

Before the contractor begins his operations on railroad right of way, he will contact the railroad at least 10 days in advance by telephone at 1-800-336-9193 (a 24-hour number) to determine if fiber optic cable is buried anywhere on the railroad property to be used by the contractor.

The railroad will advise the contractor if fiber optic cable exists at the location(s) being occupied and will dispatch a representative to locate, mark and protect each cable in the vicinity of the work to be performed by the contractor.

The railroad will need the Railroad Mile Post involved which is 15.06 on this project.

The contractor, for his own protection, should obtain and record the "Trouble Log Number" from the railroad for verification of the call made.

WRITTEN NOTICE TO RAILROAD COMPANY

The contractor shall give written notice to the Manager Track & Structures or to his authorized representative, at least ten days in advance of the date on which he expects to begin any work under or adjacent to any of the tracks of the Railroad Company or he expects to begin any construction work on the right of way of the Railroad Company. The contractor shall also give written notice to the Manager Track & Structures no later than ten days after completion of all work on the railroad company's right of way.

**BRIDGE REMOVAL PLANS
(S1-28A-0801)**

The Contractor shall submit a complete Bridge Removal Plan to the Railroad by certified mail. The Bridge Removal Plan shall include details, procedures and the sequence of staged removal of the bridge, including all steps necessary to remove the bridge in a safe and controlled manner.

The Contractor shall submit to the Railroad: three (3) complete sets of the Contractor's Bridge Removal Plan for review and comments. The Plan shall be sealed by a Civil or Structural Engineer registered in the State of Nebraska. A minimum of three (3) weeks shall be allowed for the Railroad's review after the complete submittal is received. No removal operations will be permitted over the Railroad right-of-way until the submitted material has been reviewed and comments provided.

**PROTECTION OF PROPERTY
(S1-29-0801)**

The contractor shall use the utmost care to guard against accidents or cause the least possible interference with the operation of trains of the Railroad Company and the telephone, telegraph or signal lines of the Railroad Company or of any tenant of the Railroad Company's right-of-way. The contractor shall use the utmost care in guarding against injury to underground and overhead public utilities and services at or near the site of the work.

All work to be done under this contract shall be handled by the contractor so as to interfere as little as is reasonably possible with the use of tracks, wires, signals and property of the Railroad Company or its tenants, and the underground or overhead services of public and private utilities, and the contractor shall be responsible for any damages which may be sustained by the Railroad Company, its tenants, employees, passengers or freight in its care, or by the owners of any public or private overhead or underground services caused by such interferences which could have been avoided by the proper handling of said work. The contractor shall discontinue immediately, upon request of the engineer, any practices or actions which, in the opinion of the engineer, are unsafe or cause damage to underground or overhead services of public or private utilities, or which might result in delays to trains, engines or cars, or damage to tracks, roadbed, telephone, telegraph or signal wires.

The contractor shall take all precautions for the purposes of protecting the embankment of all railroad tracks as may be determined necessary by the authorized representative of the Railroad Company. The contractor agrees to affix the seal of a registered professional engineer licensed to practice in the State of Nebraska on all plans and calculations pertaining to details for sheeting or otherwise protecting excavations next to or adjacent to railroad tracks if necessary and noted on the State's plans. The contractor also shall take all precautions for the protection of underground and overhead services either public or private, as may be determined by the engineer.

PROTECTION OF PROPERTY

The contractor shall not place or permit to be placed, or remain, piles of material or other temporary obstructions closer than 12 feet (3.7 meters) to the nearest rail of any track or closer than 23 feet (7 meters) above the top of any rail except that the construction forms and scaffolding may be placed no closer than 12 feet (3.7 meters) from the centerline of any such track.

Any changes necessary in the clearance set forth above shall be made only by special arrangements with the Manager Track & Structures of the Company or his authorized representative.

The contractor agrees to affix the seal of a registered professional engineer licensed to practice in the State of Nebraska on all plans and calculations pertaining to details for sheeting or otherwise protecting excavations next to or adjacent to railroad tracks if necessary and noted on the State's plans.

RAILROAD CROSSINGS (S1-31-1201)

The Contractor shall use only public roadways or special crossings that are specifically shown on the plans to cross railroad tracks. If the Contractor should desire a temporary crossing for construction purposes at a location other than an existing public crossing, provisions for such crossing shall be negotiated with the railroad by the Contractor, and all costs for such crossing shall be borne by the Contractor.

Prospective bidders should familiarize themselves with railroad temporary crossing and insurance requirements before bidding on the work.

INSPECTION (S1-32-0801)

Subsection 105.09 in the Standard Specifications is amended to provide also that the work shall be subject to the inspection of the properly authorized representatives of the railroad and that such inspection shall in no sense make the railroad a party to this contract and will in no way interfere with the rights of either party hereunder.

**INSURANCE
(S1-33-1201)**

The State shall require its Contractor or any of his subcontractors to carry regular Contractor's Public Liability and Property Damage Insurance as specified in Federal-Aid Policy Guide 23 CFR 646A providing for a limit of not less than Two Million Dollars (\$2,000,000) for all damages arising out of bodily injuries to or death of one person, and subject to that limit for each person, a total limit of not less than Four Million Dollars (\$4,000,000) for all damages arising out of bodily injuries to or death of two or more persons in any one accident and providing for a limit of not less than Two Million Dollars (\$2,000,000) for all damages to or destruction of property in any one accident and subject to that limit a total (or aggregate) limit of not less than Four Million Dollars (\$4,000,000) for all damages to or destruction of property during the policy period. A certified copy of the policy providing said Contractor's Public Liability and Property Damage Insurance executed by a corporation qualified to write the same in the State in which the work is to be performed, in form and substance satisfactory to the Railroad, shall be delivered to and approved by the Railroad prior to the entry upon or use of the Railroad's property by the Contractor.

In addition to any other forms of insurance or bonds required under the terms of the contract and the specifications, the Contractor shall furnish to the Railroad a Railroad Protective Policy in the form provided by Federal-Aid Policy Guide 23 CFR 646A. The combined single limit of said policy shall not be less than Two Million Dollars (\$2,000,000) for all damages arising out of bodily injuries to or death of any person or persons and for all damages arising out of loss or destruction of or injury or damage to property in any one occurrence during the policy period; and subject to that limit, a total (or aggregate) limit of not less than Six Million Dollars (\$6,000,000) for all damages arising out of bodily injuries to or death of any person or persons and for all damages arising out of or loss or destruction of or injury or damage to property during the policy period. Said insurance policy executed by a corporation qualified to write the same in the State in which the work is to be performed shall be in form and substance satisfactory to the Railroad and shall be delivered to and approved by the Railroad prior to the entry upon or use of its property by the Contractor.

The above mentioned insurance shall be written in accordance with the Federal-Aid Policy Guide 23 CFR 646A issued by the Federal Highway Administration, which is hereby, through reference, made a part of these provisions.

The State shall require its Contractor or any of its subcontractors to carry a Business Automobile Insurance Policy or equivalent policy with minimum limits of one million dollars (\$1,000,000) for bodily injury and property damage per occurrence on all vehicles which the Contractor or subcontractors, their agents or employees may use at any time in connection with the performance of the work on this project. A certified copy of the policy providing said Business Automobile Insurance executed by a corporation qualified to write the same in the state in which the work is to be performed, in form and substance satisfactory to the companies, shall be delivered to and approved by the companies prior to the entry upon or use of the companies property by the Contractor.

The insurance as hereinbefore specified shall be carried by the Contractor and the Railroad covering all work performed on this project within the limits of the rights-of-way of the Railroad. Said insurance shall be carried until all work required under the terms of the contract is satisfactorily completed, as evidenced by formal acceptance by the State.

The State's Contractor shall cause triplicate originals of the policy or policies covering the Railroad Protective Liability Insurance specified above to be delivered to the State for delivery to the Railroad. The Contractor shall not enter upon or perform any work upon the property or the rights-of-way of the Railroad until the specified originals of the policy or policies have been delivered to and approved by the Railroad. The Contractor shall deliver one original policy of the above described Contractor's Property Damage Liability Insurance and one copy of the Business Automobile Insurance Policy to the State prior to the beginning of any work on the Railroad's right-of-way.

In addition to the above, the Contractor shall indemnify and hold the railroad(s) harmless against and from all cost, liability, and expense whatsoever (including the railroad attorney's fees and court costs and expenses) actually incurred arising out of or in any way contributed to by any negligent act or omission of the Contractor and its employees, for any damage to or destruction of any telecommunications system by the Contractor and its employees on the railroad's property.

RIGHT OF WAY (S1-34-0801)

The right of way and property which the public has, or will have, by ownership or easement, for the permanent construction and the prosecution of the construction operations, is indicated in the plans or will be defined upon request. Any additional ground, or working or storage space that the contractor may require for his operations, shall be provided by the contractor at his own expense.

RESTORATION OF RAILROAD COMPANY'S PROPERTY (S1-35-0801)

In the event the contractor shall in any manner move or disturb other property of the Railroad Company, in connection with the use of the said property, then, and in that event, the contractor shall, as soon as possible and at its sole expense, restore such property to the same condition as it was in before such property was moved or disturbed, and the contractor shall indemnify and save harmless the Railroad Company against and from any and all liability, loss, damages, claims, demands, costs and expenses of whatsoever nature, including court costs and attorneys' fees, which may result from injury to or death of persons whomsoever, or damage to or loss or destruction of property whatsoever, when such injury, death, damage, loss or destruction grows out of or arises from the taking down of any fence, or the moving or disturbance of any other property, of the Railroad Company.

FINAL CLEANING UP (S1-36-0801)

Subsection 104.08 in the Standard Specifications is amended to provide also that upon the completion of the work contemplated in this contract, the contractor shall remove all machinery, equipment, surplus materials, falsework, rubbish, ditches, and temporary building, furnished or erected by him from within the limits of the right of way of the Railroad Company and shall leave the said right of way in a neat condition satisfactory to the Chief Engineer of the Railroad Company, or his authorized representative.

PERCENTAGE OF COST OF WORK WITHIN RAILROAD RIGHT-OF-WAY

The following information is furnished to aid in the determination of a proper premium for the Railroad Protective Liability Insurance required elsewhere in these special provisions.

RAILROAD PROTECTIVE POLICY DATA SHEET

Railroad: Nebraska Central Railroad Company

Railroad Contact: Ken Sidlinger

Title: Vice President General Manager

Address: 400 Braasch Avenue, Suite B, Norfolk, NE 68701

Telephone Number: (402) 371-9015

Project Number: PEP-92-6(1010)

Project Location: In Rising City and East

Type of Project: Maintenance and Resurfacing

No. of trains/day: Total: 2

Freight or Coal: 2 Speed: 30 mph Passenger 0 Speed mph

No. of Tracks: Mainline 1 Branchline 0

Project Over RR: No X Yes Project Under Railroad: No X Yes

Railroad Shoo-fly Required: No X Yes

Project Parallel to RR: No X Yes If Yes, Number of Miles

Crossings on State Highway or City Street System: No Yes X

If Yes, Number of Crossings 1 at DOT 818092D

Pavement or Overlay up to Crossing on County or City Road:

No X Yes If Yes, Number of Crossings

Work to be done by Railroad Install 50' concrete crossing at DOT 818092D

It shall be the contractor's responsibility to contact the railroad for additional information needed to purchase the Railroad Protective Policy.

The percentage of work within railroad right of way that is within 50 feet (15.25 meters) of any railroad track shall be covered by railroad protective insurance. The railroad's ownership of right of way that extends beyond 50 feet (15.25 meters) from the closest track shall be covered under regular Contractor's Public liability and Property Damage Insurance in the amounts specified in this contract.

<u>Group</u>	<u>Approximate Percent of Work Within 50 feet (15.25 meters) of Nearest Track</u>	<u>Approximate Percent of Work on RR/ROW Not Within 50 feet (15.25 meters) of Nearest Track</u>	<u>Description of Work</u>
<u>All</u>	<u>0.1 %</u>	<u>0.1 %</u>	<u>--</u>

CONSTRUCTION DETAILS

**TEMPORARY TRAFFIC CONTROL DEVICES
(S4-9-1201)**

Paragraphs 2.a. of Subsection 422.05 in the Standard Specifications is void and superseded by the following:

2.a. If signs are not returned or are returned damaged, and the damage is beyond reasonable "wear and tear" and the damage was caused by the Contractor, then the Contractor shall be charged the value of the missing or damaged items. These charges shall be deducted from monies due the Contractor upon final payment.

**TYPE B HIGH INTENSITY WARNING LIGHTS
(S4-9-1002)**

All references in the plans to Type B High Intensity Warning Lights shall be considered void. The plans will not be revised to reflect this change.

**LOCAL MATERIAL SOURCES
(S5-1-0801)**

Information regarding possible sources of local materials is available at the Materials and Research Division of the Department of Roads, Lincoln, Nebraska.

**ASPHALTIC CONCRETE
(S5-5-0801)**

Paragraph 5. of Subsection 503.02 in the Standard Specifications is void.

**ASPHALTIC CONCRETE
(S5-7-0902)**

Paragraph 11.a. in Subsection 503.04 of the 2001 Supplemental Specifications is void.

Paragraph 4. in Subsection 503.05 of the 1997 Standard Specifications is void.

The pay item "Asphalt Pavement Smoothness Testing" in Subsection 503.06 of the 1997 Standard Specifications is void.

**ASPHALTIC CONCRETE PAVEMENT SMOOTHNESS
(S5-7-0902)**

Section 502 in the 1997 Standard Specifications for Highway Construction and the 2001 Supplemental Specifications is void and superseded by the following:

502.01 – General

1. This specification establishes a standard for asphaltic concrete pavement smoothness, and defines defective pavement smoothness. The intent of the specification is to produce a finished asphaltic concrete pavement driving surface with a Profile Index no greater than 12 inches per mile. Pavement smoothness will be evaluated as prescribed in this section.
2. When the pay item "Asphalt Pavement Smoothness Testing I/D" is included in the contract, all the requirements of the following sections including the incentive/disincentive provisions shall apply.
3. When the pay item "Asphalt Pavement Smoothness Testing" is included in the contract, the incentive/disincentive provisions of this section do not apply, but the smoothness testing shall be performed as prescribed. The asphaltic concrete pavement shall be evaluated in accordance with Paragraph 11. b. of Subsection 503.04 in the 2001 Supplemental Specifications.
4. When the contract contains no item for smoothness testing, the asphaltic concrete pavement shall be evaluated in accordance with Paragraph 11. b. of Subsection 503.04 in the 2001 Supplemental Specifications.

502.02 – Equipment

1. The Contractor shall furnish a 25-ft California profilograph approved by the Nebraska Department of Roads.
2. The profilograph shall have multiple, non-uniformly spaced, articulated support wheels arranged such that no two wheels pass the same location on the pavement surface at the same time (ASTM Designation: E 1274, Paragraph 5.1.2)
3. The profilograph shall be equipped with a computerized system that will record, analyze, and print the test data.

4. The profilograph shall produce a printed pavement profile trace (profilogram) with a vertical scale of 1:1, and a horizontal scale of 1:300 (1" paper = 25' pavement). The profilogram shall include the following information:
 - a. Project number
 - b. Test date
 - c. Traffic lane
 - d. Test direction
 - e. Test path
 - f. Pass number (1 for initial test; 2, 3, etc. for repeat runs)
 - g. Operator's name
 - h. Project stations
 - i. Data filter values
 - j. Blanking (Null) band width
 - k. Profile counts for each test section
 - l. Profile Index for each test section
 - m. Bump locations for each test section

502.03 – Certification and Independent Assurance Testing

1. The Department shall calibrate and certify the Contractor's profilograph annually at a test site established by the Department.
 - a. The profilograph shall be inspected for compliance with general equipment requirements, including wheel configuration, effective length, data analysis system, guidance system, and overall condition.
 - b. The profilograph shall be calibrated for distance measurement by moving it over the prescribed path of a premeasured test distance at walking speed, and determining its distance calibration factor.
 - c. The profilograph shall be checked for vertical measurement accuracy by placing a 1-inch and 2-inch calibration block, measured to the nearest 0.01 inch, under the sensing wheel while the profilograph is stationary. The vertical measurement indicated by the profilograph shall be within 4.0% tolerance of the actual premeasured block height.
 - d. The profilograph shall be checked for overall performance by moving it over the prescribed path of a pre-measured pavement test section at walking speed.
 - e. Distance measurement indicated by the profilograph shall be within 0.2% tolerance of the actual premeasured test section distance. To ensure accurate distance measurement during test runs, the air pressure of the distance measurement tire must always be maintained at the same level used for calibration.
 - f. The Profile Index reported by the profilograph for the test section shall be within 10.0% tolerance of the Profile Index reported by a Nebraska Department of Roads profilograph for the same test section.
 - g. A dated and signed decal will be placed on the profilograph to certify its acceptability for use on Nebraska Department of Roads pavement construction projects.

2. The Department shall certify the Contractor's profilograph operator at least every 5 years. The operator may be certified by presenting certification from another State Highway Agency or by completing certification training conducted by the Nebraska Department of Roads.
3. The Department shall schedule and perform Independent Assurance tests for the Contractor's profilographs and operators at least once per construction season. Independent Assurance testing shall be conducted at a randomly selected time on an active construction project. The criteria for the test will be similar to those used for certification.

502.04 – Profilograph Test Procedures

1. The Contractor shall perform all pavement smoothness specification tests except the 10-foot straight edge testing as shown in Paragraph 16. below:
2. The Engineer shall furnish a report form to the Contractor identifying all required test sections.
 - a. The pavement surface shall be divided into lane-width segments that end at a bridge, railroad crossing, or other designated termini.
 - b. The lane-width segments shall be further divided into individual 528 feet (0.10 mile) long test sections in the direction of project stationing. The last test section in a segment is usually shorter than 528 feet.
 - c. If a test section is less than 300 feet long, it shall be combined with the preceding 528 feet long test section for analysis.
3. The Contractor's certified profilograph operator shall perform smoothness specification tests in the Engineer's presence. Smoothness testing shall be performed during normal daylight working hours unless otherwise approved by the Engineer. If the Contractor notifies the Engineer of a proposed test and the Engineer elects not to be present, then the Contractor may proceed unaccompanied.
4. The Contractor shall report test results to the Engineer within 2 NDR workdays after initial asphaltic concrete placement or surface corrective work. The Contractor shall report additional test results to the Engineer as soon as possible, but not later than 7 calendar days after completion of the mainline pavement.
5. The asphaltic concrete pavement surface temperature shall be 150 degrees F. or lower when smoothness tests are performed.
6. The profilograph operator shall perform pavement smoothness measurements in the right-hand or left-hand wheel path of all driving lanes, as directed by the Engineer, including climbing and fly-by lanes. In urban areas, where inlet block-outs or manholes are in the right or left-hand wheel path, the pavement smoothness measurements shall be made in a location determined by the Engineer. All wheels of the profilograph shall be on the new pavement for which the Contractor is responsible.
7. The Contractor shall remove all objects and foreign material from the pavement surface before testing.

8. The profilograph operator shall guide the profilograph along the specified wheel path of each traffic lane at walking speed. Propulsion may be by personnel pushing manually, or by a suitable propulsion unit that does not exceed a speed of 4 miles per hour. Excessive speed can produce erratic test results.
9. A lateral location indicator shall be used to keep the profilograph in the required test path during testing. Pavement edges, longitudinal joints, or longitudinal pavement markings may be used as reference lines. An additional person may be required to hold the back end of the profilograph on the required path on horizontal curves.
10. Before testing, the profilograph operator shall lower the profilograph's recording wheel to the pavement surface and move the profilograph forward to the beginning location of a test section to stabilize the measurement system. To ensure consistent distance measurement, the profilograph operator shall also check and adjust the recording wheel tire pressure several times a day.
11. All station references on the profilograms and report forms shall be actual project stations. Stations shall be accurately noted on the profilogram at least every 200 feet.
12. The profilograph operator and the Engineer shall sign the profilograms immediately after completion of the tests. If the Engineer was not present at the time of the tests, then the absence shall be noted on the profilograms.
13. The Engineer shall perform or schedule verification tests on at least 10 percent of the pavement surface, using a profilograph owned by the Department.
14. If the verification test, Independent Assurance tests, or other observations indicate that the Contractor's procedures and/or results are not acceptable or accurate, the Engineer may do any of the following:
 - a. require the Contractor to calibrate the profilograph and re-run the tests.
 - b. disqualify the Contractor's equipment and/or operator.
 - c. perform the tests for part, or all, of the project with a profilograph owned by the Department, and charge the Contractor \$500.00 per lane mile for all testing done by the Department.
15. The following areas of pavement shall be excluded from the Profile Index, unless otherwise specified in the Special Provisions.
 - a. Pavement on horizontal curves having a centerline radius of curvature of less than 1,000 feet, and pavement within the superelevation transition of such curves.
 - b. Pavement within 50 feet of a transverse joint that separates the pavement from an approach slab to a bridge deck or existing pavement not constructed under the contract.
 - c. Pavement for truck weigh stations or rest areas, acceleration/deceleration lanes, and interchange ramps and loops.

- d. Pavement within 50 feet of railroad crossings and associated transitions.
 - e. Pavement with a posted speed limit of 45 miles per hour or less.
 - f. Pavement where the Engineer requires the contractor to open an area prematurely to cross traffic at intersections and driveways.
 - g. Additional exceptions shown on the summary sheet in the plans.
16. Excluded pavement sections shall be measured for bumps with either a profilograph or a 10-foot straight edge. If the profilograph is used, the deviation shall not exceed 0.40 inch. The deviation of the surface shall not exceed 1/8 inch, if a 10-foot straightedge is used.

502.05 – Evaluation

1. The Contractor shall determine a Profile Index and number of correctable bumps and dips for each test section, record the information on the report form, and provide a copy of the report, along with the corresponding profilograms, to the Engineer.
 - a. The Profile Index shall be calculated by adding the absolute value of the vertical deviations (inches) outside of a 0.1 inch blanking band and dividing the sum by the length of the test section (miles). The resulting Profile Index is in units of inches per mile.
 - b. Correctable bumps shall be separately identified on the profilograms. They appear as high points on the profilogram and correspond to high points on the pavement surface. Correctable bumps are vertical deviations on the pavement surface that exceed 0.40 inch in height above a base line span of 25 feet.
 - c. Correctable dips shall be separately identified on the profilograms. They appear as low points on the profilogram and correspond to low points on the pavement surface. Correctable dips are vertical deviations on the pavement surface that exceed 0.40 inch in depth below a base line span of 25 feet.

502.06 – Pavement Surface Correction

1. The Contractor shall locate and perform all required pavement surface corrective work, with the approval of and in the presence of, the Engineer.
2. Corrective work may be required for any bump, dip, or a combination of bumps and dips or other roughness that, in the opinion of the Engineer, produces an objectionable ride. Corrective work shall be accomplished at no cost to the Department.
 - a. When the initial Profile Index of a test section is 21 in/mi or less, bump and dip correction is the only corrective work allowed for that section.
 - b. When the Profile Index of a test section exceeds 21 in/mi, corrective work shall be performed.
 - c. The Contractor shall retest all corrected test sections with the profilograph.

3. All bumps, as defined in Subsection 502.05, Paragraph 1.b., and all test sections with a Profile Index exceeding 21 in/mi shall be corrected by diamond grinding.
 - a. Bumps shall be considered corrected when they are at or below the 0.40 inch maximum height.
 - b. Sections with a Profile Index exceeding 21 in/mi shall be considered corrected when the Profile Index for that section has been reduced to a value of 21 in/mi or less.
4. All dips, as defined in Subsection 502.05, Paragraph 1.c., shall be corrected until they are at or below the 0.40 inch maximum depth. The Contractor shall have the following options:
 - a. diamond grind on either or both sides of the dip,
 - b. with the approval of the Engineer, remove and replace a sufficient length of the surface layer to correct the deficiency, under the following conditions:
 - (1) The Contractor shall furnish replacement material that meets the original specifications for the material removed.
 - (2) Removal and replacement shall be for the full lane width.
 - c. a combination of the grinding and removal and replacement methods, or
 - d. with the approval of the Engineer, elect to leave an uncorrected or partially corrected dip in place for a monetary deduction.
5. Diamond grinding equipment used for surface correction shall be power driven, self-propelled units specifically designed to grind and texture pavements. The cutting head shall be at least 36 inches wide and consist of many diamond blades with spacers. The Engineer may approve equipment with a narrower width for irregular and confined areas, which will not accommodate larger equipment, and for bumps of limited number and area.

502.07 - Traffic Control

The Contractor shall provide all traffic control for smoothness testing and corrective work at no cost to the Department.

502.08 - Method of Measurement

1. "Asphalt Pavement Smoothness Testing I/D" and "Asphalt Pavement Smoothness Testing" shall be measured on a lump sum basis.
2. a. When the pay item "Asphalt Pavement Smoothness Testing I/D" is included in the contract, the unit price of the accepted quantity of asphaltic concrete pavement and performance graded binder in the surface layer of each profilograph test section shall be adjusted according to the schedule in Table 502.01, subject to the limitations in Paragraphs 3 and 4 of this Subsection. Pavement sections excluded from this smoothness specification shall not qualify for incentive pay.

- b. When the pay item "Asphalt Pavement Smoothness Testing " is included in the contract, the incentive/disincentive provisions of this Subsection do not apply.

Table 502.01

Payment Adjustment Schedule	
Profile Index Inches Per Lane Mile	Percent of Contract Prices
0 to 2	107
Greater than 2 to 4	105
Greater than 4 to 6	103
Greater than 6 to 8	102
Greater than 8 to 12	100
Greater than 12 to 14	98
Greater than 14 to 16	96
Greater than 16 to 18	94
Greater than 18 to 20	92
Greater than 20 to 21	90
Greater than 21	Corrective Work Required

3. When the initial Profile Index of a test section is 21 in/mi or less, that value shall determine the percent of incentive pay for the section unless bump and dip correction performed in that section increases the percent of pay.
4. When the initial Profile Index of a test section is greater than 21 in/mi, corrective work performed in that section may increase the percent of pay up to the level indicated in Table 502.01.

502.09 – Basis of Payment

1. When the pay item "Asphalt Pavement Smoothness Testing I/D" is included in the contract, the overall pay factor for the accepted quantity of asphaltic concrete and performance graded binder in the surface layer of all profilograph test sections shall be determined according to the formula in Table 502.02.

Table 502.02

Pay Factor Formula	
$PF = \frac{A(1.07) + B(1.05) + C(1.03) + D(1.02) + E(1.00) + F(0.98) + G(0.96) + H(0.94) + I(0.92) + J(0.90)}{A + B + C + D + E + F + G + H + I + J}$	
Where:	
A	= Length of pavement with a Profile Index of 0 to 2 inches per mile.
B	= Length of pavement with a Profile Index greater than 2 to 4 inches per mile.
C	= Length of pavement with a Profile Index greater than 4 to 6 inches per mile.
D	= Length of pavement with a Profile Index greater than 6 to 8 inches per mile.
E	= Length of pavement with a Profile Index greater than 8 to 12 inches per mile.
F	= Length of pavement with a Profile Index greater than 12 to 14 inches per mile.
G	= Length of pavement with a Profile Index greater than 14 to 16 inches per mile.
H	= Length of pavement with a Profile Index greater than 16 to 18 inches per mile.
I	= Length of pavement with a Profile Index greater than 18 to 20 inches per mile.
J	= Length of pavement with a Profile Index greater than 20 to 21 inches per mile.

2. The Contractor shall be assessed \$500 each for all uncorrected or partially corrected dips left in place.
3. The work of Asphalt pavement Smoothness Testing I/D” and “Asphalt Pavement Smoothness Testing” shall be paid at the lump sum contract unit price. This price shall be full compensation for all smoothness testing as set forth in this specification.

COLD MILLING CLASS 3 COLD MILLING CLASS 3, TYPE A

Under no circumstance shall the Contractor mill a greater depth from the roadway than what is shown in the plans.

Void Paragraph 9.a. of Subsection 510.04 in the 1997 English Edition of the Standard Specifications and replace it with the following:

Bituminous material produced from the cold milling operation shall become the property of the Contractor and removed from the project.

CONCRETE PAVEMENT REPAIR

Paragraph 6. of Subsection 605.01 is amended to include the following:

When performing this operation on multi-lane highways, the Contractor will be permitted to have one lane closed at night. Where the pavement has been removed, the Contractor will be required to have the excavated area filled with either (1) the appropriate patching concrete material for curing overnight, or (2) a commercially available cold-mix bituminous mixture or other suitable temporary patch material with a durable surface, as directed by the Engineer. The next day, the Contractor will then be required to remove any “temporary patches”,

thoroughly clean the repair area and complete the required permanent patch so that the lane can be opened to traffic by the end of the second day. The material, installation, removal and disposal of these temporary patches will not be measured and paid for directly, but shall be considered subsidiary to the concrete pavement repair work being performed.

Subsection 605.01 is amended to include the following:

7. The asphalt surfacing on the concrete may be milled prior to or after performing the pavement repair work. The Contractor has the option to pour the repair to the top of the existing asphalt surfacing before or after milling. On single lift projects, if the Contractor elects to pour the concrete to the top of the asphalt surfacing, the Contractor will be required to place an asphalt wedge over the repair immediately prior to placing the asphalt surfacing. The asphalt wedge shall be approximately 1 inch (25 mm) thick over the repair tapered to 0 inches (0 mm) in 10 feet (3 m) on each side of the repair parallel to the centerline. The depth of the existing asphalt is approximately 6 1/2 inches. If the Contractor elects to pour the concrete to the top of the existing asphalt surfacing, and the existing asphalt is greater than 1 inch (25 mm) deeper than is shown here, then the Contractor shall be paid the invoice price per cubic yard (cubic meter) for the extra concrete needed. If the Contractor elects to pour concrete to the top of the existing concrete and use asphaltic concrete to finish filling the repair area, it shall be either Asphaltic Concrete for Patching as shown in the plans or temporary asphaltic concrete. Temporary asphaltic concrete shall be any asphaltic concrete approved by the Engineer. The material installation, maintenance, removal and disposal of temporary asphaltic concrete will not be measured and paid for, but shall be considered subsidiary to the item "Concrete Pavement Repair, Type A, B or C, Full Depth". Asphaltic concrete used to finish filling the repair area shall be the Asphaltic Concrete For Patching as shown on the plans and shall be paid for at the contract unit price per ton (mg).

The last sentence of Paragraph 2. of Subsection 605.04 is void.

Paragraph 10. of Subsection 605.04 is void.

Paragraph 16. of Subsection 605.04 is void and superseded by the following:

The minimum concrete placement shall be as shown in the plans or as directed by the engineer. Interior transverse joints shall be sawed to a minimum of one-third the actual thickness of the slab at the spacing designated in the plans.

Paragraphs 17. and 18. of Subsection 605.04 are void.

Paragraph 19.a. of Subsection 605.04 is amended to include the following:

When pavement repairs are overlaid with asphaltic concrete, the curing method shall be with tack coat, RC-70, or an approved asphalt emulsion.

Paragraph 21. of Subsection 605.04 is amended to include the following:

- b. Class PR1 Concrete may be used for concrete repair if the repaired area is to remain closed to traffic for at least 24 hours.

- c. Class PR3 Concrete shall be used for all concrete repair if the repaired areas must be opened to traffic within 24 hours.
- d. Strength measurements for opening the PR1 and PR3 Concrete may be performed using the maturity meter method.

Paragraphs 24. a. and b. of Subsection 605.04 are void.

Paragraphs 25. b. (1) and 25. b. (2) of Subsection 605.04 are void and superseded by the following:

A full depth diamond blade saw cut shall be made and dowel bars and/or tie bars anchored into the faces of the existing concrete as designated in the plans. A full depth cut approximately 4 inches (100 mm) wide may be made with a wheel cutter through the repair section if the repair will be overlaid. The wheel-type cutter shall be operated to produce minimum disturbance of the foundation course material, with no encroachment of the cut into the concrete of the adjoining lane.

Dowel bars shall be placed on the transverse joint on the longer side of the panel to minimize the panel length. A minimum of 2 tie bars shall be placed on each side of a full depth pavement repair as designated in the plans.

Dowel bars or tie bars shall be anchored into the faces of the existing concrete as designated in the plans. Dowel bars shall be installed parallel to the pavement surface and parallel to the pavement centerline. To provide proper alignment, a three-bit gang drill shall be used to install the dowel bars. The gang drill shall be capable of drilling simultaneously 3-holes in the same plane at the spacing shown in the plans. The tie bars can be drilled independently. The drilled holes shall be thoroughly cleaned with compressed air to remove all dust, dirt, loose material, and moisture.

After cleaning and prior to dowel or tie bar insertion, an application of grout shall be made at the back of the hole. The grout shall be from the Approved Products List. Twist the dowel or tie bar one full turn during insertion to completely surround it with the grout. Grout retention disks shall be placed on the bars as designated in the plans. The furnishing and installation of dowel and tie bars will not be paid for directly but shall be considered subsidiary to the concrete pavement or joint repair work being performed.

Paragraph 25. c. of Subsection 605.04 is amended to include the following:

Any loosened foundation course material shall be removed and replaced with concrete.

Paragraph 25. d. of Subsection 605.04 is void.

Subsection 605.05 in the 1997 Standard Specifications is amended to provide that adjoining full depth repair areas of varying widths in the same traffic lane, which are situated such the removals of the areas may be accomplished concurrently, shall be considered as a single repair. The total area of the adjoining areas shall be combined to determine the repair type as shown in Table 605.01.

CONCRETE PAVEMENT JOINT REPAIR

Section 605 in the Standard Specifications and Supplemental Specifications is amended to include the following:

Approximately 156 lane joints will require the full depth joint repair.

Paragraph 6. of Subsection 605.01 is amended to include the following:

When performing this operation on multi-lane highways, the Contractor will be permitted to have one lane closed at night. Where the pavement has been removed, the Contractor will be required to have the excavated area filled with either (1) the appropriate patching concrete material for curing overnight, or (2) a commercially available cold-mix bituminous mixture or other suitable temporary patch material with a durable surface, as directed by the Engineer. The next day, the Contractor will then be required to remove any "temporary patches", thoroughly clean the repair area and complete the required permanent patch so that the lane can be opened to traffic by the end of the second day. The material, installation, removal and disposal of these temporary patches will not be measured and paid for directly, but shall be considered subsidiary to the concrete pavement repair work being performed.

Subsection 605.01 is amended to include the following:

7. The asphalt surfacing on the concrete may be milled prior to or after performing the joint repair work. The Contractor has the option to pour the repair to the top of the existing asphalt surfacing before or after milling. On single lift projects, if the Contractor elects to pour the concrete to the top of the asphalt surfacing, the Contractor will be required to place an asphalt wedge over the repair immediately prior to placing the asphalt surfacing. The asphalt wedge shall be approximately 1 inch (25 mm) thick over the repair tapered to 0 inches (0 mm) in 10 feet (3 m) on each side of the repair parallel to the centerline. The depth of the existing asphalt is approximately 6 1/2 inches. If the Contractor elects to pour the concrete to the top of the existing asphalt surfacing, and the existing asphalt is greater than 1 inch (25 mm) deeper than is shown here, then the Contractor shall be paid the invoice price per cubic yard (cubic meter) for the extra concrete needed. If the Contractor elects to pour concrete to the top of the existing concrete and use asphaltic concrete to finish filling the repair area, it shall be either Asphaltic Concrete for Patching as shown in the plans or temporary asphaltic concrete. Temporary asphaltic concrete shall be any asphaltic concrete approved by the Engineer. The material installation, maintenance, removal and disposal of temporary asphaltic concrete will not be measured and paid for, but shall be considered subsidiary to the item "Concrete Pavement, Class "PR" Joint Repair". Asphaltic concrete used to finish filling the repair area shall be the Asphaltic Concrete For Patching as shown on the plans and shall be paid for at the contract unit price per ton (mg).

The last sentence of Paragraph 2. of Subsection 605.04 is void.

Paragraphs 16. and 17. of Subsection 605.04 are void.

Paragraph 19.a. of Subsection 605.04 is amended to include the following:

When joint repairs are overlaid with asphaltic concrete, the curing method shall be with tack coat, RC-70, or an approved asphalt emulsion.

Paragraph 21. of Subsection 605.04 is amended to include the following:

- b. Class PR1 Concrete may be used for concrete repair if the repaired area is to remain closed to traffic for at least 24 hours.
- c. Class PR3 Concrete shall be used for all concrete repair if the repaired areas must be opened to traffic within 24 hours.
- d. Strength measurements for opening the PR1 and PR3 Concrete may be performed using the maturity meter method.

Paragraphs 24. a. and 24. b. of Subsection 605.04 are void.

Paragraphs 25. b. (1) and 25. b. (2) of Subsection 605.04 are void and superseded by the following:

A full depth diamond blade saw cut shall be made and dowel bars and/or tie bars anchored into the faces of the existing concrete as designated in the plans. A full depth cut approximately 4 inches(100 mm) wide may be made with a wheel cutter through the repair section if the repair will be overlaid. The wheel-type cutter shall be operated to produce minimum disturbance of the foundation course material, with no encroachment of the cut into the concrete of the adjoining lane.

Dowel bars or tie bars shall be anchored into the faces of the existing concrete as designated in the plans. Dowel bars shall be installed parallel to the pavement surface and parallel to the pavement centerline. To provide proper alignment, a three-bit gang drill shall be used to install the dowel bars. The gang drill shall be capable of drilling simultaneously 3-holes in the same plane at the spacing shown in the plans. The tie bars can be drilled independently. The drilled holes shall be thoroughly cleaned with compressed air to remove all dust, dirt, loose material, and moisture.

After cleaning and prior to dowel or tie bar insertion, an application of grout shall be made at the back of the hole. The grout shall be from the Approved Products List. Twist the dowel or tie bar one full turn during insertion to completely surround it with the grout. Grout retention disks shall be placed on the bars as designated in the plans. The furnishing and installation of dowel and tie bars will not be paid for directly but shall be considered subsidiary to the concrete pavement or joint repair work being performed.

Paragraph 25. c. of Subsection 605.04 is amended to include the following:

Any loosened foundation course material shall be removed and replaced with concrete.

The last sentence of Paragraph 25. d. of Subsection 605.04 is void.

Paragraph 1. of Subsection 605.06 is amended to include the following:

Pay Item	Pay Unit
Concrete Pavement, _____ Joint Repair	Square Yard (SY) Square Meter (m ²)

**FLY ASH
(S10-5-0801)**

Subsection 1008.01 in the Standard Specifications is void and superseded by the following:

Fly ash shall be Class C or F meeting the requirements of ASTM C 618.

**STRUCTURAL STEEL
(S10-5-0801)**

Section 1045 of the Standard Specifications is amended to include the following:

1045.03 -- Steel Plate Substitution

The Contractor may use either English or Metric steel plates in accordance with Table 1045.01.

Table 1045.01			
English-Metric Steel Plate Substitution Table			
Metric (millimeters)	English (inches)	Metric (millimeters)	English (inches)
9	3/8	32	1 1/4
10	3/8	35	1 3/8
11	7/16	38	1 1/2
12	1/2	40	1 5/8
14	9/16	45	1 3/4
16	11/16	50	2
18	3/4	55	2 1/4
20	13/16	60	2 3/8
22	7/8	70	2 3/4
25	1	80	3 1/4
28	1 1/8	90	3 1/2
30	1 1/4		

**REPAIR OF DAMAGED METALLIC COATINGS
(S10-5-0801)**

Paragraph 2. of Subsection 1061.01 in the Standard Specifications is void and superseded by the following:

2. The material used for repair shall provide a minimum coating thickness of at least 50 µm with one application.

**DOWEL BARS
(S10-5-0801)**

Subsection 1022.02 in the Standard Specifications is amended to include the following:

In addition to these certificates, two 1.8 meter samples of the coated bar (for tension testing and bend testing) of each size bar and each heat number shall be sent to the NDR Materials and Research Laboratory, Lincoln, Nebraska. These bars will be properly identified with tags showing the size and heat number.

**CORRUGATED METAL PIPE
(S10-5-0801)**

Table 1035.01 in Section 1035 of the Supplemental Specifications is amended by deleting the title "Steel and Aluminum Culvert Thickness".

**METAL FLARED-END SECTIONS
(S10-5-0801)**

Table 1036.01 in Section 1036 of the Supplemental Specifications is amended by deleting the title "Steel and Aluminum Flared-End Thickness".

**REINFORCED CONCRETE PIPE, MANHOLE RISERS,
AND FLARED-END SECTIONS
(S10-5-0801)**

Paragraph 3.a. of Subsection 1037.02 in the Supplemental Specifications is void and superseded by the following:

3.a. Round reinforced concrete pipe shall conform to the requirements of AASHTO M 170-95 with the exception of the minimum circumferential reinforcing (in²/ft. (mm²/m) of pipe wall) for 15, 21, and 24 inch (380, 460, 600 mm) Class III pipe, as shown below:

Paragraph 3.b. of Subsection 1037.02 is void and superseded by the following:

b. AASHTO M 170-95 Specifications are modified as follows:

Paragraph 4. of Subsection 1037.02 is void and superseded by the following:

4. Reinforced concrete arch pipe shall conform to the requirements of AASHTO M 206-95.

Paragraph 5. of Subsection 1037.02 is void and superseded by the following:

5. Reinforced concrete elliptical pipe shall conform to the requirements of AASHTO M 207-95.

Paragraph 7. of Subsection 1037.02 is void and superseded by the following:

7. Concrete flared-end sections shall be of the design shown in the plans and in conformance with the applicable requirements of AASHTO M 170-95, Class II pipe, AASHTO M 206-95, Class A-II pipe, or AASHTO M 207-95, Class HE-II pipe for the diameter of pipe which it is to be installed.

HIGH TENSILE BOLTS, NUTS, AND WASHERS (S10-5-1001)

Subsection 1058.02 in the Supplemental Specifications is void.

Paragraph 4.b.(5) in the Standard Specifications is void and superseded by the following:

- (5) The bolt, nut, and washer assembly shall be assembled in a Skidmore-Wilhelm calibrator or an acceptable equivalent device. For bolts that are too short to be assembled in the calibrator, see Subsection 1058.03, Paragraph 4.b.(9).

ELASTOMERIC BEARINGS AND LAMINATED BEARING PADS (S10-5-0202)

Paragraph 2. of Subsection 1068.02 in the Standard Specifications is void and superseded by the following:

2. Certification shall be furnished in accordance with NDR's *Materials Sampling Guide*.

Paragraph 3. of Subsection 1068.02 is void.

STEEL BARS FOR CONCRETE REINFORCEMENT (S10-5-1201)

Section 1020 in the Standard Specifications is void and superseded by the following:

1020.01 - Description

Steel tie bars for longitudinal joint reinforcement in concrete pavements shall be epoxy coated and deformed Grade 40 or 60 billet steel as shown in the plans, specifications or Special Provisions.

1020.02 - Material Characteristics

1. Billet-steel bars shall conform to the requirements of ASTM A 615/A 615M.
2. Epoxy coatings shall conform to the requirements in Section 1021 of the Standard Specifications and Supplemental Specifications.

1020.03 - Acceptance Requirements

Acceptance shall be based on sampling, testing, and certification requirements in accordance with the NDR *Materials Sampling Guide*.

PERFORMANCE GRADED BINDER

Section 503 in the Standard Specifications and Supplemental Specifications is amended to include Performance Graded Binders.

I. Description:

The performance graded binder to be used on this project shall be PG Binder 64-28 for Asphaltic Concrete Type SP4, and P.G. Binder 58-28 for Asphaltic Concrete Type SPS, supplied by a Certified Supplier.

Certified Supplier

A supplier must be certified by the Nebraska Department of Roads to be allowed to supply Performance Graded Binder in Nebraska. A certified supplier must be a participant in one or more of the following PG Binder groups.

1. AASHTO Materials Reference Laboratory (AMRL)
2. Western Cooperative Testing Group
3. Combined States Binder Group

The supplier must maintain and follow the requirements of the group or groups in which they participate in to maintain certification by the Nebraska Department of Roads. In addition, active participation is required to maintain certification by the Department. Active participation will include submitting of round robin samples results, along with meeting other requirements of the group or groups. Failure to do so will result in loss of certification by the Department.

A certified supplier may be asked to supply to the Department, past round robin results, laboratory inspection reports, reasons for and investigative reports on out lying results, quality control testing, and/or technician training and proficiency testing reports.

Supplier Certification

A supplier may request certification by contacting the Nebraska Department of Roads, Materials and Research Division, Flexible Pavement Engineer at (402) 479-4675. A temporary certification may be issued for a period of up to one year. Split sample testing will be required prior to receiving a temporary certification. Split sample testing will be done on all grades of binder that the supplier intends to supply during the temporary certification. The supplier will have up to one year to become certified by participating in and following the requirements of one or more of the approved binder groups.

A supplier may become certified through active participation in other binder certification/round robin groups that are approved by the Department. The Department may request from the supplier prior to approval, past or current round robin results, quality control testing, laboratory inspection reports, and/or technician training and proficiency testing reports.

II. Binder Sampling and Testing:

1. Lots. Each 3750 tons (3400 Mg) of HMA produced will be a binder lot.
2. A binder lot will include only one PG Binder grade or a blend as allowed in paragraph 6.e.
3. A Binder lot will only include one supplier of the PG Binder or a blend as allowed in paragraph 6.e.
4. Blending of different binder grades and binders from different suppliers will be allowed with restrictions as noted in paragraph 6.e. The Engineer must be notified of the intent to blend prior to actual blending.
5. All binders shall be sampled at the rate of one sample per lot with a minimum of three samples per project.
 - a. The sample shall consist of two one-quart (liter) cans and shall be taken by the Contractor's Certified Sampling Technician, with assistance from or under supervision of NDR personnel. The sample shall be taken at the plant from the line between the storage tank and the mixer or from the tank supplying material to the line, at a location at which material sampled is representative of the material in the line to the mixer. One can will be tested for compliance with MP1 specifications and the other can portion will be saved for dispute resolution, if needed. The sampling process shall follow procedures of the NDR Materials Sampling Guide and NDR T 40.
 - b. Testing. When the tested PG Binder is in compliance, the binder lot will be accepted and both cans of the sample can be discarded. If the tested PG Binder does not comply, then the price of the PG Binder lot represented by the sample shall be adjusted according to Table 1. Overall project average testing requirements and price adjustments will also apply, as stated in Table 2.
6. Material Requirements:
 - a. Performance graded binder, as specified in the contract items shall be in accordance with AASHTO Designation MP1 and meet all minimum and maximum requirements.
 - b. Substitution of a PG Binder, which exceeds the upper and lower grade designations from the specified, requires advance notification of the Engineer, and be documented by a no cost change order. The bill of lading or delivery ticket shall state the binder grade and specific gravity.
 - c. Material Certification - A Material Certification shall be submitted prior to construction stating, the type of modifier being used, and the recommended mixing and compaction temperatures for the Hot Mix Asphalt.
 - d. The Contractor shall receive from the supplier, instructions on the proper storage and handling of each grade and shipment of PG Binder.

- e. Blending of PG Binders at the hot mix plant site will be allowed only when transitioning to an asphalt mixture requiring a different grade of binder and with the following restrictions:
- (1) The resultant blend will meet MP-1 specifications when tested as $\pm 3^\circ$ of the specified PG binder. The sample of the blended material will 1) be considered as a lot sample, 2) will be taken during initial production following the blending of the binders, and 3) deductions when not meeting MP-1, will apply. On the blended sample's identification form will be a note explaining the blending conditions and a statement that the sample is a blend of materials. The next lot sample, following the sample representing the blend, will be tested as the specified binder grade for the asphalt mixture being produced and shall meet MP-1 specifications.
 - (2) Modified Binders - When a type of modification is used and stated in the Material Certification as required in paragraph 6.c., it will not be allowed to be blended with a binder containing a different type of modification. Blending of the same type of modifiers will be allowed.

TABLE 1

SINGLE SAMPLE TOLERANCE AND PRICE REDUCTION TABLE		
	Price Reduction¹ Pay Factor of 0.75	Determined by Engineer² Pay Factor of 0.50 or Removal
<u>Tests on Original Binder</u> Dynamic Shear, $G^*/\sin \delta$, kPa	0.86-0.92	< 0.86
<u>Tests on Rolling Thin Film Oven Residue</u> Dynamic Shear, $G^*/\sin \delta$, kPa	1.76-1.97	< 1.76
<u>Tests Pressure Aging Vessel Residue</u> Dynamic Shear, $G^*\sin \delta$, kPa	5601-6200	> 6200
<u>Creep Stiffness</u> S, Mpa	325-348	> 348
m-value	0.270-0.284	< 0.270

NOTE: If more than one test fails to meet requirements, the largest individual price reduction (pay factor of 0.75 or 0.50) will be used to calculate price reduction for the asphalt binder.

¹Price Reduction will be based on contract unit price of asphalt binder.

²The Engineer will determine if the non-compliant material will be removed. If the non-compliant material is accepted, a price reduction of 50% will be applied. The price reduction shall be based on the contract unit price of asphalt binder.

The pay factor will be applied to the quantity of material that the sample represents.

Overall Project Average - Price Reduction Based on Complete MP-1 Testing

Out of specification material will be determined by the specifications outlined in AASHTO MP-1, excluding Direct Tension.

The Nebraska Department of Roads, Materials and Research, Bituminous Laboratory will do complete testing, per MP-1 specifications, on a minimum of three samples or 20% of the total samples from the project, whichever is the greatest. The Department will randomly select one sample for complete MP-1 testing out of every five samples received. When any test result shows sample not meeting MP-1 specifications, the previous and following sample received will be tested for complete MP-1 compliance. Testing will continue in this manner until tested samples meet all of MP-1 specifications.

Original Dynamic Shear Rheometer testing will be completed on all samples. When a sample being tested for only Original Dynamic Shear Rheometer compliance falls out of MP-1 specification, it will then be tested for complete MP-1 specification compliance. Adjacent samples will be tested when results, other than the Original Dynamic Shear Rheometer result, do not meet specification. This additional complete testing for MP-1 compliance is in addition to the minimum number of samples that will be tested for complete MP-1 compliance.

At the completion of testing, all complete MP-1 test results will be averaged. For averages that do not meet MP-1 specifications, the largest reduction shown in Table 2 will be applied to all the Performance Graded Binder used on the project.

Table 2

OVERALL PROJECT AVERAGE - PRICE REDUCTION TABLE		
	Range of Average	Pay Factor Applied
<u>Tests on Original Binder</u> Dynamic Shear, $G^*/\sin \delta$, kPa Min. 1.00 kPa	< 1.00 - 0.98	0.98
	< 0.98 - 0.96	0.95
	< 0.96 - 0.94	0.92
	< 0.94	0.85
<u>Tests on Rolling Thin Film</u> <u>Oven Residue</u> Dynamic Shear, $G^*/\sin \delta$, kPa Min. 2.20 kPa	< 2.20 - 2.156	0.98
	< 2.156 - 2.09	0.95
	< 2.09 - 2.024	0.92
	< 2.024	0.85
<u>Tests Pressure Aging Vessel</u> <u>Residue</u> Dynamic Shear, $G^*\sin \delta$, kPa Max. 5000 kPa	< 5000 - 5100	0.98
	< 5100 - 5250	0.95
	< 5250 - 5400	0.92
	< 5400	0.85
m-Value Min. 0.300	< 0.300 - 0.298	0.98
	< 0.298 - 0.293	0.95
	< 0.293 - 0.290	0.92
	< 0.290	0.85
<u>Creep Stiffness</u> S, MPa Max. 300 MPa	< 300 - 306	0.98
	< 306 - 315	0.95
	< 315 - 324	0.92
	< 324	0.85

Single Sample Reduction and Overall Project Average Reduction

A sample representing a lot, not meeting MP-1 Specification, will have a reduction for the material that the sample represents. Only the largest reduction from Table 1, will apply when more than one result of a single sample does not meet MP-1 specifications. Only the largest overall project average reduction from Table 2, will apply when more than one test average falls out of MP-1 specifications. Pay Factors based on both Table 1 and Table 2 test results are separate from each other and both will be applied.

Investigation of Verification Lot Samples That Do Not Meet Specifications

When the lot sample shows test results out of specification limits, the process of resolving the sample failure will include the following actions as appropriate:

1. The Bituminous Lab may conduct retesting of the remaining portion of the original can sample as determined necessary to confirm or disaffirm the original test result(s).
2. The Flexible Pavement Engineer will notify the Contractor who will arrange to investigate all aspects of the testing, loading, handling and delivery of the material in question. The Contractor shall report findings to the Central Laboratory, Flexible Pavement Engineer.

3. The Department will collect and compile all information and prepare a report. A copy of the report will be distributed to the District and the Contractor.
4. The Bituminous Laboratory will issue the standard report of tests for all samples tested, to include any resulting pay factor deductions. A copy of the report of tests will be distributed to the District, Construction Division, and Contractor.

Dispute Resolution

After testing and investigations have been completed on the one can of the sample and there is still a dispute, the Department will select an independent laboratory for referee testing to take place on the second can of the sample. If the independent lab's tests indicate failing results and pay deductions equal to or great than the Department's, the Contractor will reimburse the Department for the cost of testing. If the independent lab's tests indicate that the material meets specification or is at a pay deduction less than the Department's, the Department will assume the cost of testing. When the independent lab's tests indicate a pay deduction, the lesser of the Department's and the independent lab's deductions will be applied.

Basis of Measurement

PG Binder shall be measured in accordance with Subsection 503.05 in the Standard Specifications and Supplemental Specifications.

Basis of Payment:

Subsection 503.06 in the Standard Specifications and Supplemental Specifications is amended to provide that PG Binder, accepted by the Engineer for use in asphaltic concrete, will be paid for at the contract unit price per ton (Megagram) for the item "Performance Graded Binder _____", less any deductions as prescribed in the tolerance and price reduction tables.

SUPERPAVE ASPHALTIC CONCRETE

Asphaltic Concrete Type SP4 shall use the 0.5 gradation band.

Paragraph 2.b. of Subsection 503.06 of the Supplemental Specifications is amended to include Asphaltic Concrete Type SP6.

Section 1028 is amended to include Asphaltic Concrete Type SP6.

Paragraph 2. a. of Subsection 1028.01 is void and superseded by the following:

Before production of asphaltic concrete, the Contractor shall submit, in writing, a tentative job mix formula on the NDOR Mix Design Submittal Form for approval to the NDR Flexible Pavement Engineer at the Lincoln, Nebraska Central Laboratory.

Paragraph 2. b. of Subsection 1028.01 is void and superseded by the following:

The job mix formula shall identify the virgin mineral aggregates, RAP, if used, and mineral filler, if needed, with the value of the percent passing each specified sieve for the individual and blended materials.

Paragraph 2. c. (1) of Subsection 1028.01 is void and superseded by the following:

The Contractor shall submit six – 95 mm and two – 75 mm gyratory pucks compacted to 7% ± 1% air voids for testing and 3 proportioned 22 lb. (10,000-gram) samples of the blended mineral aggregates to be used in the mixture to the NDR Materials and Research Central Laboratory at least 15 NDR working days before production of asphaltic concrete. These samples will be used to validate the Contractor’s Superpave mix design test results and mix properties.

Paragraph 2. c. (3) of Subsection 1028.01 is amended to include the following:

- (ix) Dust to Binder Ratio

Paragraph 2. c. (3) (i) of Subsection 1028.01 is void and superseded by the following:

The bulk specific gravity of the blended aggregate. Whenever RAP is used it shall be processed through an ignition oven and then combined proportionally with the virgin aggregate. The bulk specific gravity shall be determined for the blend from an unwashed sample of the - #4 and a washed sample of + #4 material in accordance with AASHTO T 84 and AASHTO T 85 respectively.

Table 1028.01 is amended to include the following:

Table 1028.01

Asphaltic Concrete Type	Percent, Maximum RAP
SP6	15

Paragraph 4. f, (2), (i) of Subsection 1028.01 is void and superseded by the following:

The quality control technicians shall report directly to the Program Administrator and shall perform all sampling and quality control tests as required by the contract.

Paragraph 4. h. (3) of Subsection 1028.01 is void and superseded by the following:

All QC test results shall be documented on NDR Forms by the Contractor with a copy provided to the Engineer within 1 week after the tests are complete. Daily review by the Engineer will be allowed if requested.

Paragraph 4. i. (3) (ii) of Subsection 1028.01 is amended to include the following:

- (VII) Dust to Binder Ratio

Paragraph 4. i. (3) (iii) of Subsection 1028.01 is amended to include the following:

- (IV) Tearing
- (V) Irregular surface due to mix tenderness

Paragraph 2.e. of Subsection 1028.02 is void and superseded by the following:

e. Crushed rock (Limestone) and Dolomite shall conform to the requirements of Subsection 1033.02 of the Standard Specifications, Paragraph 4.a. (4), (5) and (6). Sampling size and frequency shall adhere to the current NDR Materials Sampling Guide. (Some aggregate can be adversely affected by ignition ovens resulting in erroneous reading for asphalt content and gradation unless corrected for.)

Paragraph 2.h. of Subsection 1028.02 of the Supplemental Specifications is void and superseded by the following:

The coarse aggregate angularity value of the blended aggregate material shall meet or exceed the minimum values for the appropriate asphaltic concrete type as shown in Table 1028.02.

Table 1028.02 is void and superseded by the following:

**Table 1028.02
Coarse Aggregate Angularity
(ASTM D 5821)**

Asphaltic Concrete Type	Course Aggregate Angularity
SPS	35
SP0	55
SP1	55
SP2	65
SP3	75
SP4	85/80*
SP5	95/90*
SP6	95/90*

* Denotes two faced crushed requirements

Paragraph 2.h.(1) of Subsection 1028.02 is void.

Paragraph 2.i. of Subsection 1028.02 is void and superseded by the following:

The fine aggregate angularity value of the blended aggregate material shall meet or exceed the minimum values for the appropriate asphaltic concrete type as shown in Table 1028.03.

Note: The specific gravity for calculation of the Fine Aggregate Angularity (FAA) shall be based on material passing the No. 8 (2.36 mm) sieve and retained on the No. 100 (150 µm) sieve.

Table 1028.03 is void and superseded by the following:

**Table 1028.03
Fine Aggregate Angularity
(AASHTO T304 Method A)**

Asphaltic Concrete Type	Fine Aggregate Angularity
SPS	--
SP0	--
SP1	40.0
SP2	43.0
SP3	43.0
SP4	45.0
SP5	45.0
SP6	45.0

Paragraph 2.i.(1) of Subsection 1028.02 is void.

Table 1028.04 is amended to include the following:

**Table 1028.04
Flat And Elongated Particles
(ASTM D 4791)**

Asphaltic Concrete Type	Percent, Maximum
SP6	10

Table 1028.05 is amended to include the following:

**Table 1028.05
Clay Content
(AASHTO T 176)**

Asphaltic Concrete Type	Sand Equivalent, Minimum
SP6	50

Paragraph 2.i (1). of Subsection 1028.02 is void and superseded by the following:

It is recommended that the selected blended aggregate gradation does not pass through the restricted zones as specified in the following control points for nominal size. The plot of the blended aggregate gradation of Superpave mix designs with FAA values of less than 43.0 will not enter the limits of the restricted zone. The plot of the blended aggregate gradation of Superpave mix designs with FAA values of 43.0 to less than 45.0 passing through the restricted zone must intersect both the upper and lower limits of the restricted zone between 1) any two consecutive sieves used to define the restricted zone limits, or 2) two vertical lines plotted between the #8 and #50 sieve a distance apart no greater than 1/3 the horizontal distance between the #8 (2.36-mm) and #50 (300- μ m) sieves. Superpave mix designs with FAA values of 45.0 or greater will not be restricted from passing through the restricted zone.

The note following table 1028.08 is void and superseded by the following:

- * Dust to binder ratio is the ratio of the percentage by weight of aggregate finer than the No. 200 (75 µm) sieve to the asphalt content expressed as a percent by weight of total mix. The dust to binder ratio shall be between 0.60 and 1.20. This shall be verified during mix design approval.

Table 1028.09 is amended to include the following:

- * see note following Table 1028.08

Paragraph 3. b. (3). of Subsection 1028.02 is void and superseded by the following:

Rice equipment specified in AASHTO T 209, procedure 9.5.1, Weighing in Water. The thermometer being used to measure water temperature will be as specified in T 209.

Paragraph 3. b. (11). of Subsection 1028.02 is void and superseded by the following:

Personal Computer capable of running NDR software and Color Printer.

Paragraph 1. a. of Subsection 1028.03 is void and superseded by the following:

The job mix formula shall be determined from a mix design for each mixture. A volumetric mixture design in accordance with AASHTO PP 28 as modified within this special provision, will be required. However, the mixture for the Superpave specimens and maximum specific gravity mixture shall be short-term aged for two hours.

Paragraph 1. c. of Subsection 1028.03 is void and superseded by the following:

The Contractor shall inform the Engineer when changes in the types or sources of aggregates or PG Binders are made. These changes may require a new job mix formula, mix design and moisture susceptibility test. The new proposed job mix formula shall be in accordance with the requirements as stated above and submitted 5 working days prior to use for verification.

Paragraph 1. d. of Subsection 1028.03 is void and superseded by the following:

Each Superpave mixture shall be tested for moisture susceptibility in accordance with AASHTO T 283. The loose mixture shall be short-term aged for two hours in accordance with AASHTO PP 2. The 6-inch (152-mm) specimens shall be compacted in accordance with AASHTO T 312 to seven percent air voids at 95-mm in height and evaluated to determine if the minimum Tensile Strength Ratio (TSR) of 80 percent has been met. If the mixture has not met the minimum TSR value, an anti-stripping additive shall be added at a dosage rate, such that the mix will meet the minimum TSR of 80 percent. All data shall be submitted with the mix design verification request. For mixtures containing an anti-stripping additive; during production of Lot #1, the Contractor shall provide to the NDR Central laboratory properly prepared gyratory samples for AASHTO T 283 testing. A TSR test result of less than 80 percent will require mixture modification(s) and a sample from subsequent lots will be tested until a TSR value of at least 80 percent is achieved. Moisture susceptibility testing is not required for Asphaltic Concrete Type SPS.

Paragraph 1. d. (1) of Subsection 1028.03 is void and superseded by the following:

When tests indicate the need for an anti-stripping additive the Contractor shall be compensated for the cost of the anti-strip additive needed at the invoice price of the additive. If the Contractor elects to use a liquid anti-strip additive it shall be added to the PG Binder by the PG Binder Supplier.

Table 1028.11 is amended to include the following:

**Table 1028.11
Gyratory Compaction Effort
(Average Design High Air Temperature = < 39 degrees C)**

Asphaltic Concrete Type	Nini	Ndes	Nmax
SP6	9	126	204

Table 1028.12 is void and superseded by the following:

Table 1028.12

Mix Criteria	SPS,SP0,SP1	SP2	SP3,SP4,SP5,SP6
Voids In Mineral Aggregate	See Table 13		
Voids Filled with Asphalt	See Table 14		
%Gmm at Nini	91.5*	90.5	89.0
%Gmm at Nmax	98.0*	98.0	98.0

* No specification requirement for SPS, only %Gmm at Ndes = 95 to 98.5

Table 1028.14 is amended to include the following:

**Table 1028.14
Voids Filled With Asphalt
Criteria at Ndes**

Asphaltic Concrete Type	Design VFA, Percent
SP6	65 – 75

Paragraph 3. c. of Subsection 1028.03 is void and superseded by the following:

c. The adjustment values in Table 1028.15 will be the tolerances allowed for adjustments from the NDR verified mix design “Combined Gradation” target values which resulted from production or mix design adjustments, but cannot deviate from Superpave gradation criteria, or violate restricted zone criteria specified in paragraph 2. I. (1) of Subsection 1028.02. Mix adjustments for individual aggregates, including RAP, greater than 25% of the original verified mix design proportion may require the Contractor to submit a new mix design, as determined by the Engineer

Paragraph 4.c.(4) of Subsection 1028.03 is void and superseded by the following:

At the project start-up and when a substantial aggregate proportion or other major mix change has been made, at least 1 sample shall be taken between the first 110 tons (100 Mg) and 300 tons (270 Mg) of production. This sample, when other than at start-up, will be in lieu of the next scheduled random sample location.

Paragraph 4.c. (5) of Subsection 1028.03 is amended to include the following:

When both ignition oven and cold feed cold feed samples are being tested the taking of the samples shall be timed such that each sample represents, as close as possible, the same aggregate being fed into the plant.

Paragraph 4. c. (6) of Subsection 1028.03 is void and superseded by the following:

For projects using RAP material the FAA and CAA shall be established as follows:

A RAP sample will be processed through an ignition oven and then combined with the proportioned amount of virgin aggregate defined by the mix design and then proceeding with FAA and CAA testing.

Paragraph 4. f. (1) (i) of Subsection 1028.03 is void and superseded by the following:

Bulk Specific Gravity (Gmb) shall be determined for each specimen in accordance with AASHTO T 166- Bulk Specific Gravity of Compacted Bituminous Mixtures Using Saturated Surface Dry Specimens.

Paragraph 4.f. (1) (iv) of Subsection 1028.03 in the Supplemental Specifications is void and superseded by the following:

At the Contractor's request, upon evidence that the 3 Bulk Specific Gravity specimens are exhibiting consistency in their results, The Materials and Research Central Laboratory or Branch Manager may reduce the number of specimens to 2.

Paragraph 4. f. (3) (i) of Subsection 1028.03 is void and superseded by the following:

The Blended Aggregate Bulk Specific Gravity (Gsb) shall be determined from a combined aggregate blend, including any RAP following ignition burn-off, on the + #4 and - #4 material.

Paragraph 4. f. (5) of Subsection 1028.03 is void and superseded by the following:

5. (i) The percent of PG Binder shall be determined for each QC test. The percent of PG Binder will be computed by ignition oven results.
5. (ii) The gradations shall be determined for each QC test using AASHTO T 30.

Paragraph 4.g.(1) of Subsection 1028.03 is void and superseded by the following:

All test results and calculations shall be recorded and documented on data sheets using the latest version of NDOR provided "Superpave" software. A copy containing complete project documentation will be provided to the Materials and Research Division at the completion of the project.

Paragraph 4. h. (3) of Subsection 1028.03 is amended to include the following:

- (x) Dust to Binder ratio to the nearest 0.01

The table of paragraph 4. i. (3) (i) of Subsection 1028.03 is void and superseded by the following:

Test	Tolerance
Asphalt Content by Ignition Oven	0.5%
Gyratory Density	0.020
Maximum Specific Gravity	0.015
Bulk Dry Specific Gravity (Gsb)	0.020
FAA	0.5%
CAA	10.0%
Field Core Density	0.020

Paragraph 5.b. of Subsection 1028.03 is void and superseded by the following:

Two consecutive test results (single test) outside the Specification limits or a (50% or reject) shall be cause to cease operations.

Paragraph 5.e. of Subsection 1028.03 is void and superseded by the following:

Failure to cease operations after two consecutive test results fall outside the Specification limits shall subject all subsequent material to be rejected.

Paragraph 7.b. of Subsection 1028.03 is amended to include SP6.

Paragraph 9. a. of Subsection 1028.03 is void and superseded by the following:

Density tests will be performed by the Contractor under direct observation of NDR personnel. The Contractor will establish the method of testing in the preconstruction conference and shall be tested in accordance with the AASHTO T 166 or NDR T 587. The Contractor will insure that the proper adjustment bias and/or correction factors are used and accessible to NDR personnel along with all other inputs when NDR T 587 is selected. All correlation factors and test results shall be generated and reported on the NDOR Density spreadsheet. All disputed values determined using NDR T 587 shall be resolved using AASHTO T 166.

The “**Note**” in paragraph 9.b. of Subsection 1028.03 is void and superseded by the following:

Note: The individual QC test value of the Maximum Mix Specific Gravity (Rice) will be used to calculate the density of each corresponding core.

Paragraph 9. h. 3 (i) of Subsection 1028.03 is void and superseded by the following:

If requested by the Contractor, check tests for all density tests in the original set, taken no later than the working day following placement will be allowed in lots with a density pay factor of less than 1.00. Locations for checks tests will be determined by a new random sampling schedule provided by the Engineer. The average density obtained by the check tests shall be used to establish the density pay factor for the lot.

Subsection 1028.03 is amended to include Paragraph 10 as follows:

10. PG Binder Sampling
 - a. At least one sample (2-1 quart cans) (2-1 liter cans) of PG Binder will be sampled by the Contractor's QC Technician for every Lot (3750 tons) (3400 Mg) of asphalt concrete mixture produced.
 - b. Samples will be taken in accordance with NDR Standard Method T 40.
 - c. The QC Technician will include on the Sample Identification form all information required by the contract.

ASPHALTIC CONCRETE, TYPE SPS

Table 1028.09 in the Supplemental Specifications is void and superseded by the following:

**Table 1028.09
Gradation Control Points for Type SPS**

English Sieve (Metric)	Control Points (percent passing)	
	Minimum	Maximum
1 inch (25 mm)		
¾ inch (19 mm)	100	
½ inch (12.5 mm)	90	100
No. 8 (2.36 mm)	42	81
No. 16 (1.18 mm)	29	43
No 30 (600 µm)	19	34
No. 50 (300 µm)	11	20
*No. 200 (75 µm)	2	8

**PROPOSAL GUARANTY
(S1-38-0801)**

As an evidence of good faith in submitting a proposal for this work or for any portion thereof as provided in the proposal form, the bidder must file with his proposal a bid bond, which must be executed on the Department of Roads' Bid Bond form, in the amount of 5 percent of the amount bid for any group of items or collection of groups for which the bid is submitted. Any alterations, conditions or limitations added to the Department of Roads' Bid Bond form will be unacceptable and cause the bid not to be opened and read.

* * * * *

N24INFNOV02

ASPHALTIC CONCRETE..... 26, 27
 ASPHALTIC CONCRETE PAVEMENT SMOOTHNESS..... 27
 ASPHALTIC CONCRETE, TYPE SPS 56

COLD MILLING CLASS 3 COLD MILLING CLASS 3, TYPE A..... 34
 CONCRETE PAVEMENT JOINT REPAIR 37
 CONCRETE PAVEMENT REPAIR..... 34
 CONSTRUCTION DETAILS 26
 CONTROL OF WORK..... 8
 CORRUGATED METAL PIPE 41

DOWEL BARS..... 41

ELASTOMERIC BEARINGS AND LAMINATED BEARING PADS..... 42

FINAL CLEANING UP..... 16, 24
 FLAGGING CONDITIONS..... 10, 19
 FLAGGING PROTECTION..... 10, 18
 FLY ASH..... 39

GENERAL CONDITIONS..... 6

HIGH TENSILE BOLTS, NUTS, AND WASHERS..... 42

INSPECTION..... 14, 22
 INSURANCE..... 14, 23

LEGAL RELATIONS AND RESPONSIBILITY TO THE PUBLIC 8
 LOCAL MATERIAL SOURCES..... 26

MEASUREMENT AND PAYMENT..... 9
 METAL FLARED-END SECTIONS 41

NEBRASKA CENTRAL RAILROAD COMPANY 18
 NOTICE TO BIDDERS..... 6

PERCENTAGE OF COST OF WORK WITHIN RAILROAD RIGHT-OF-WAY 17, 25
 PERFORMANCE GRADED BINDER..... 43
 PROPOSAL GUARANTY 56
 PROTECTION OF PROPERTY 12, 13, 21, 22
 PROTECTION OF UTILITIES..... 11, 20

RAILROAD CROSSINGS..... 13, 22
 RAILROAD SAFETY TRAINING..... 10, 18
 RAILROAD SPECIAL PROVISIONS 11, 20
 REIMBURSEMENT TO RAILROAD COMPANY FOR FLAGGING COSTS..... 10, 19
 REINFORCED CONCRETE PIPE, MANHOLE RISERS, AND FLARED-END SECTIONS..... 41
 REPAIR OF DAMAGED METALLIC COATINGS..... 40
 RESTORATION OF RAILROAD COMPANY'S PROPERTY..... 15, 24
 RIGHT OF WAY 15, 24

SPECIAL PROSECUTION AND PROGRESS

(Milling/Overlay) 9

STATUS OF RIGHT-OF-WAY 7

STATUS OF UTILITIES 7

STEEL BARS FOR CONCRETE REINFORCEMENT 42

STRUCTURAL STEEL 40

SUBCONTRACTOR BIDDERS LIST INFORMATION 7

SUPERPAVE ASPHALTIC CONCRETE 48

TEMPORARY TRAFFIC CONTROL DEVICES 26

THE BURLINGTON NORTHERN AND SANTA FE RAILWAY COMPANY 9

TYPE B HIGH INTENSITY WARNING LIGHTS 26

WORK TO BE PERFORMED BY THE RAILROAD COMPANY 9, 18

WRITTEN NOTICE TO RAILROAD COMPANY 12, 20