

NOTICE TO CONTRACTORS

CALL ORDER F40
FEDERAL PROJECT NO. BR-1970(2)
LOCATION: ON A COUNTY ROAD NORTHWEST OF CHAMBERS - TWO SITES
COUNTIES: HOLT

The Nebraska Department of Roads will receive sealed bids for
HOLT COUNTY in Room 104 of the Central Office Building at
1500 Hwy 2 at Lincoln, until 1:30 P.M. on December 19, 2002 .
At that time the bids will be opened and read for
GRAD BR GDRL

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR
WHO IS QUALIFIED FOR: BRIDGES

Length: 0.4 MILES
START DATE 06/23/2003 WORKING DAYS 90
Price Range \$ 100,000 to \$ 500,000

Plans and specifications may be seen beginning November 26, 2002 at the Lincoln
Central Office and December 02, 2002 at the District Engineer's Office at AINSWORTH

Additional letting information may be found at the Nebraska Department of Roads
Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal
requirements will apply.

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	32 SHEETS	\$ 6.40
CROSS SECTIONS (SHEETS X1 THRU X5)	5 SHEETS	\$ 1.00
STANDARD PLANS	6 SHEETS	\$ 1.20

SHEET NO.

1	TITLE PAGE
2T	TYPICAL CROSS SECTIONS OF IMPROVEMENT
2S	SUMMARY OF QUANTITIES
2N	GENERAL INFORMATION
3	PLAN & PROFILE SHEET
4 - 12	SPECIAL PLAN 1 PRESTRESSED DOUBLE TEE BRIDGE STA. 10+20.00
13 - 22	SPECIAL PLAN 2 PRESTRESSED DOUBLE TEE BRIDGE STA. 15+35.00
23 - 29	SPECIAL PLAN 1C GUARDRAIL PROTECTION
R1	RIGHT-OF-WAY DATA
X1 - X5	CROSS SECTIONS
STANDARD PLANS	
617-R3	(2 SHEETS) CONCRETE PILING
920-R5	(2 SHEETS) TRAFFIC CONTROL
921-R4	TRAFFIC CONTROL
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and
should not be used for bidding purposes. The Department
reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
LARGE TREE REMOVAL		1 EACH
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		21 MGAL
EARTHWORK MEASURED IN EMBANKMENT		6,869 CY
24" DRIVEWAY CULVERT PIPE		36 LF
GRAVEL SURFACE COURSE		223 CY
CLAY SURFACE COURSE		795 CY
COVER CROP SEEDING		2 ACRE

GROUP 6 BRIDGE AT STA. 10+20

MOBILIZATION	LUMP	LUMP
ABUTMENT NO.1 EXCAVATION	LUMP	LUMP
ABUTMENT NO.2 EXCAVATION	LUMP	LUMP
47B-3000 CONC FOR BRIDGE		69 CY
47BD-4000 CONC FOR BRIDGE		47 CY
PRECAST/PRESTRESSED CONC SUPERSTR	LUMP	LUMP
AT STA. 10+20		
RE-STEEL FOR BRIDGE		11,795 LB
REMOVE STRUCTURE		1 EACH
AT STA. 10+20		
STRUC STEEL FOR SUBSTRUCTURE		2,490 LB
CONCRETE PILING		660 LF
STEEL SHEET PILING		4,125 SF

GROUP 6A BRIDGE AT STA. 15+35

MOBILIZATION	LUMP	LUMP
ABUTMENT NO.1 EXCAVATION	LUMP	LUMP
ABUTMENT NO.2 EXCAVATION	LUMP	LUMP
47B-3000 CONC FOR BRIDGE		52 CY
47BD-4000 CONC FOR BRIDGE		69 CY
PRECAST/PRESTRESSED CONC SUPERSTR	LUMP	LUMP
AT STA. 15+35		
RE-STEEL FOR BRIDGE		16,910 LB
REMOVE STRUCTURE		1 EACH
AT STA. 15+35		
STRUC STEEL FOR SUBSTRUCTURE		1,020 LB
CONCRETE PILING		1,060 LF
STEEL SHEET PILING		2,417 SF

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
BRIDGE APPROACH SECTIONS		8 EACH
MELT		8 EACH

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE III		1,920 BDAY
SIGN DAY		2,240 EACH
CONTRACTOR FURNISHED SIGN		960 EACH
FIELD OFFICE		1 EACH
MOBILIZATION	LUMP	LUMP