

NOTICE TO CONTRACTORS

CALL ORDER F07
 FEDERAL PROJECT NO. BRO-7026(13)
 LOCATION: ON A COUNTY ROAD WEST OF WATERBURY.
 COUNTIES: DIXON

The Nebraska Department of Roads will receive sealed bids for
 DIXON COUNTY in Room 104 of the Central Office Building at
 1500 Hwy 2 at Lincoln, until 1:30 P.M. on March 13, 2003 .
 At that time the bids will be opened and read for
 BRIDGE

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR
 WHO IS QUALIFIED FOR: BRIDGES
 START DATE 08/11/2003 WORKING DAYS 60
 Price Range \$ 100,000 to \$ 500,000

Plans and specifications may be seen beginning February 18, 2003 at the Lincoln
 Central Office and February 24, 2003 at the District Engineer's Office at NORFOLK
 Additional letting information may be found at the Nebraska Department of Roads
 Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal
 requirements will apply.

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	13 SHEETS	\$ 2.60
CROSS SECTIONS (SHEETS X1 THRU X5)	5 SHEETS	\$ 1.00
STANDARD PLANS	6 SHEETS	\$ 1.20

SHEET NO.

1	TITLE PAGE
2T	TYPICAL CROSS SECTION & SUMMARY OF QUANTITIES
3	PLAN & PROFILE SHEET
4	CONSTRUCTION DETAILS
5	DRAINAGE STRUCTURE CROSS SECTIONS
6 - 12	SPECIAL PLAN 1 WELDED PLATE GIRDER BRIDGE STA. 16+95.00
R1	RIGHT-OF-WAY SHEET
X1 - X5	CROSS SECTIONS

STANDARD PLANS

410-R3	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
920-R5	(2 SHEETS) TRAFFIC CONTROL
921-R4	TRAFFIC CONTROL
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and
 should not be used for bidding purposes. The Department
 reserves the right to change these quantities without notice.

GROUP 6 BRIDGE AT STA. 16+95

BARRICADE, TYPE III	1,332 BDAY
SIGN DAY	1,332 EACH
CONTRACTOR FURNISHED SIGN DAY	666 EACH
MOBILIZATION	LUMP LUMP
LARGE TREE REMOVAL	1 EACH
GENERAL CLEARING AND GRUBBING	LUMP LUMP
WATER	14 MGAL
EARTHWORK MEASURED IN EMBANKMENT	1,410 CY
18" DRIVEWAY CULVERT PIPE	40 LF
24" DRIVEWAY CULVERT PIPE	42 LF
REMOVE CULVERT PIPE	22 LF
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL	34 CY
24" CORRUGATED METAL PIPE	36 LF
24" METAL FLARED-END SECTION	2 EACH

GROUP 6 BRIDGE AT STA. 16+95

6" PERF CORR POLY PIPE UNDERDRAIN		100 LF
ABUTMENT NO.1 EXCAVATION	LUMP	LUMP
ABUTMENT NO.2 EXCAVATION	LUMP	LUMP
EXPANSION BEARING, TFE TYPE		4 EACH
FIXED BEARING		4 EACH
47B-3000 CONC FOR BRIDGE		18 CY
47BD-4000 CONC FOR BRIDGE		108 CY
RE-STEEL FOR BRIDGE		23,590 LB
REMOVE STRUCTURE		1 EACH
AT STA. 17+05 RT.		
REMOVE CAISSON		4 EACH
STEEL SUPERSTRUCTURE	LUMP	LUMP
AT STA. 16+95		
STRUC STEEL FOR SUBSTRUCTURE		2,520 LB
ROCK RIPRAP, TYPE B		390 TON
PIPE PILING		1,280 LF
STEEL SHEET PILING		3,033 SF
COVER CROP SEEDING		1 ACRE