

STATE OF NEBRASKA
DEPARTMENT OF ROADS
ADDENDUM NO. 2
PROJECT NO. RD-80-9(1139)
CONTROL NO. 12682
CALL ORDER N04
I-80, LINCOLN TO PLATTE RIVER BRIDGE
LETTING DATE: MARCH 13, 2003

On page 11 of the Special Provisions, in the provision titled CRACK SEALING BITUMINOUS SURFACING, section "519.02 – Material Requirements" is amended to include the following:

- h. Material having a bond specification will be tested on concrete blocks that will be constructed by the Department's Concrete laboratory. The materials used for the concrete blocks will be constructed to a commonly used design, which meets Nebraska concrete paving specifications. The design used is a 47-B mixture. The design can be found on the Department Web Site at:

<http://www.nebraskatransportation.org/ref-man/specbooke/1000/1000-e20.pdf>

The design is amended so that no fly ash is used in the mixture. All other specifications for Portland cement concrete apply.

If a Department approved independent laboratory will be used for testing purposes, the Department must be notified so that concrete blocks for bond testing can be sent to the approved independent laboratory.

DEPARTMENT OF ROADS

Claude Oie
Construction Engineer

Issued: March 4, 2003

CO:CC:N04AD203

NOTICE: Only the contractors issued bidding proposals receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the contractor.