

NOTICE TO CONTRACTORS

CALL ORDER N03

STATE PROJECT NO. RD-2-6(1024)

LOCATION: N-2 AT 148TH STREET, LINCOLN.

COUNTIES: LANCASTER

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on April 17, 2003 . At that time the bids will be opened and read for GRAD,CONC PAVE

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: CONCRETE PAVEMENT

START DATE 07/14/2003 WORKING DAYS 15

Price Range \$ 100,000 to \$ 500,000

Plans and specifications may be seen beginning March 25, 2003 at the Lincoln Central Office and March 31, 2003 at the District Engineer's Office at LINCOLN

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	20 SHEETS	\$ 4.00
CROSS SECTIONS (SHEETS X1 THRU X5)	5 SHEETS	\$ 1.00
STANDARD PLANS	14 SHEETS	\$ 2.80

SHEET NO.

1	TITLE PAGE
2T	TYPICAL CROSS SECTIONS
2S1-2S2	SUMMARY OF QUANTITIES & DETOUR LOCATION MAP
2N1-2N2	GENERAL INFORMATION
2L1	GEOMETRICS, GRADES, & JOINT DETAIL
2L2	CONSTRUCTION & REMOVAL
3	PLAN & PROFILE SHEET
4	TRAFFIC CONTROL PLAN--LANE CLOSURE
5	PAVEMENT MARKING PLAN
6 - 9	ROADWAY LIGHTING PLANS
10 - 11	DRAINAGE STRUCTURE CROSS SECTIONS
12	SPECIAL PLAN 1C EROSION CONTROL, TYPES "A" & "AA"
13	SPECIAL PLAN 2C EROSION CHECKS (ALL TYPES) AND FABRIC SILT CHECKS
R1	RIGHT-OF-WAY SHEET
X1 - X5	CROSS SECTIONS

STANDARD PLANS

301-R8	(3 SHEETS) PAVEMENT DETAILS
329-R4	(4 SHEETS) 6 TO 16 INCH CONCRETE PAVEMENT
425-R3	COLLARS AND ELBOWS FOR CONCRETE PIPES
501-R3	EROSION CONTROL
804	PRECAST CONCRETE R.O.W. MARKER
914-R3	PULL BOX DETAIL
920-R5	(2 SHEETS) TRAFFIC CONTROL
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)	1,490	CY
WATER	7	MGAL
RIGHT-OF-WAY MARKERS	2	EACH
REMOVE & RESET DELINEATORS	4	EACH
REMOVE & SALVAGE FES	2	EACH
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL	16	CY

47B-3000 OR AX-3000 CONC FOR CONCRETE CO	1 CY
RE-STEEL FOR COLLARS	38 LB
INSTALL 36" METAL F.E.S.	1 EACH
INSTALL 18" CONC FES	1 EACH
EROSION CONTROL, TYPE A	200 SY
EROSION CONTROL, TYPE HV	996 SY
EROSION CHECKS, TYPE HV	36 BALE
18" CULV PIPE 2	22 LF
36" CULV PIPE 3,4,5	28 LF

GROUP 3 CONCRETE PAVEMENT

MOBILIZATION	LUMP	LUMP
REMOVE		2 EACH
UNDERDRAIN HEADWALL		
TIE BARS		246 EACH
CONC 47B-3000 MEDIAN SURFACING		8 SY
10" DOWELED CONC PVMT, 47B-3500		3,228 SY
UNDERDRAIN HEADWALL		2 EACH
4" NONPERF PIPE UNDERDRAIN		92 LF
4" WHITE PREF PVMT MRKNG T-4 GROOVED		1,300 LF
12" WHT PREF PVMT MRKING T-4 GROOVED		500 LF
BIT FOUNDATION COURSE 4"		3,228 SY
GRANULAR SUBDRAIN		5 EACH
WATER		13 MGAL
EARTH SHOULDER CONSTRUCTION		13 STA
SUBGRADE PREPARATION		3,228 SY
COLD MILLING, CLASS 4		1,419 SY
ST LIGHT UNIT SL-BT-40-12-0.25		2 EACH
1 1/2" CONDUIT IN TRENCH		590 LF
STREET LIGHT CABLE, NO. 6 BARE		710 LF
STREET LIGHT CABLE, NO. 6 USE		1,420 LF
RELOCATE STREET LIGHTING UNIT		2 EACH
SEEDING, TYPE B		1 ACRE
MULCH		2 TON

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II		525 BDAY
BARRICADE, TYPE III		295 BDAY
TEMPORARY SIGN DAY		180 EACH
SIGN DAY		600 EACH
CONTRACTOR FURNISHED SIGN DAY		100 EACH
FLASHING ARROW PANEL		15 DAY
MOBILIZATION	LUMP	LUMP