

# NOTICE TO CONTRACTORS

CALL ORDER N03  
STATE PROJECT NO. STR-57-4(1004)  
LOCATION: ON N-57, HARTINGTON NORTH.  
COUNTIES: CEDAR

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on May 22, 2003 . At that time the bids will be opened and read for CULVERTS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: CULVERTS  
START DATE 09/15/2003 WORKING DAYS 40  
Price Range \$ 100,000 to \$ 500,000

Plans and specifications may be seen beginning April 29, 2003 at the Lincoln Central Office and May 05, 2003 at the District Engineer's Office at NORFOLK  
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	21 SHEETS	\$ 4.20
CROSS SECTIONS (SHEETS X1 THRU X9)	9 SHEETS	\$ 1.80
STANDARD PLANS	5 SHEETS	\$ 1.00

SHEET NO.	
1	TITLE PAGE
2T	TYPICAL CROSS SECTIONS
2S	SUMMARY OF QUANTITIES
2A1-2A3	PHOTO MAPS
2N1-2N2	GENERAL INFORMATION
3 - 5	PLAN SHEETS
6	DRAINAGE STRUCTURE CROSS SECTIONS
7 - 8	SPECIAL PLAN 1C 12' X 8' TWIN SPAN RC BOX CULVERT STA. 277+63.00
9 - 10	SPECIAL PLAN 2C 12' X 8' TWIN SPAN RC BOX CULVERT STA. 300+92.60
11 - 12	SPECIAL PLAN 3C 10' X 6' TWIN SPAN RC BOX CULVERT STA. 903+13.20
R1 - R3	RIGHT-OF-WAY SHEETS
X1 - X9	CROSS SECTIONS

## STANDARD PLANS

501-R3	EROSION CONTROL
920-R5	(2 SHEETS) TRAFFIC CONTROL
921-R4	TRAFFIC CONTROL
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

## GROUP 4 CONCRETE BOX CULVERT AT STA. 277+63 RT.

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EARTHWORK MEASURED IN EMBANKMENT		167 CY
EXCAVATION FOR BOX CULVERTS		170 CY
47B-3000 OR AX-3000 CONC FOR BOX CULV		102 CY
RE-STEEL FOR BOX CULVERT		10,371 LB
REMOVE STRUCTURE		1 EACH
AT STA. 277+63 RT.		
EROSION CONTROL		166 SY

GROUP 4A CONCRETE BOX CULVERT AT STA. 300+92.6 RT.

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)		210 CY
EARTHWORK MEASURED IN EMBANKMENT		388 CY
GRAVEL SURFACE COURSE		32 CY
GRAVEL EMBEDMENT		1 STA
EXCAVATION FOR BOX CULVERTS		276 CY
47B-3000 OR AX-3000 CONC FOR BOX CULV		102 CY
RE-STEEL FOR BOX CULVERT	10,371	LB
54" CORRUGATED METAL PIPE		86 LF
REMOVE STRUCTURE		1 EACH
AT STA. 300+92.6		
SURFACING 6"		96 SY
EROSION CONTROL		564 SY

GROUP 4B CONCRETE BOX CULVERT AT STA. 903+13.2 RT.

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EARTHWORK MEASURED IN EMBANKMENT		46 CY
EXCAVATION FOR BOX CULVERTS		207 CY
47B-3000 OR AX-3000 CONC FOR BOX CULV		73 CY
RE-STEEL FOR BOX CULVERT	7,187	LB
REMOVE STRUCTURE		1 EACH
AT STA. 903+13.2 RT		
EROSION CONTROL		156 SY

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE III		807 BDAY
SIGN DAY		304 EACH
CONTRACTOR FURNISHED SIGN DAY		262 EACH
FLAGGING		30 DAY
MOBILIZATION	LUMP	LUMP