

STATE OF NEBRASKA  
DEPARTMENT OF ROADS  
ADDENDUM NO. 3  
PROJECT NO. S-75-2(1025)  
CONTROL NO. 10800A  
CALL ORDER N01  
ON US-75 NORTH & SOUTH OF JULIAN  
LETTING DATE: JUNE 26, 2003

The Special Provisions are amended to include the following:

EXISTING CONCRETE PAVEMENT

Plan sheet 2T4 depicts a "Removal Typical" detail that indicates the underlying concrete pavement to be 200 mm in depth. District maintenance and Material & Research records indicate the following:

1. The existing concrete pavement was constructed in the 1920s as 6 m wide (20 ft), 225-175-225 mm (9"-7"-9") deep concrete pavement with steel mesh and reinforcing bars on centerline.
2. The pavement was widened in the mid-late 1950s with 200 mm x 0.6 m (8" x 2ft) concrete pavement. The plans do not indicate dowel bars as part of the widening.

DEPARTMENT OF ROADS

Claude Oie  
Construction Engineer

Issued: June 19, 2003

CO:N01AD306

NOTICE: Only the contractors issued bidding proposals receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the contractor.