

STATE OF NEBRASKA
DEPARTMENT OF ROADS
ADDENDUM NO. 1
PROJECT NO. BRO-7020(16)
CONTROL NO. 31449
CALL ORDER F07
ON A COUNTY ROAD NORTHWEST OF BANCROFT
LETTING DATE: OCTOBER 9, 2003

On page 34 of the Special Provisions, the provision titled CRUSHED ROCK EMBEDMENT is void and superseded by the following:

CRUSHED ROCK EMBEDMENT

This work shall consist of spreading a 50 mm layer of crushed rock for surfacing over the surface of the roadbed as shown in the plans, scarifying to uniformly blend the crushed rock into the upper 100 mm of the subgrade soil and compacting the area with a sheepsfoot roller until firm and stable as determined by the engineer.

Water shall be added as necessary to facilitate compaction.

Crushed rock for embedment shall conform to the requirements of Crushed rock for Surfacing in Paragraph 7. of Subsection 1033.02 in the 1997 Metric Edition of the Standard Specifications.

After the crushed rock embedment is completed, the Contractor shall place and spread approximately 50 mm of gravel on the roadway. Additional gravel shall be placed and spread during the life of the project if requested by the engineer.

Gravel for embedment shall conform to the requirements of Gravel Surfacing in Paragraph 7. of Subsection 1033.02 of the Standard Specifications.

Water will not be measured and paid for, but shall be considered subsidiary to the Crushed Rock Embedment.

Crushed Rock Embedment shall be measured by the Station, measured horizontally along the project centerline of completed and accepted work.

The work of scarifying and compacting the roadbed, measured as provided herein, will be paid for at the contract unit price per Station for the item "Crushed Rock Embedment." This price shall be full compensation for scarifying, smoothing and compacting the subgrade and for all labor, equipment, tools and incidentals necessary to complete the work.

Crushed rock used in the work will be measured and paid for in accordance with Section 310 of the Standard Specifications.

Gravel used in the work of Crushed Rock Embedment will be measured and paid for in accordance with Section 310 of the Standard Specifications.

DEPARTMENT OF ROADS



Claude Oie
Construction Engineer

Issued: September 23, 2003

CO:F07AD110

NOTICE: Only the contractors issued bidding proposals receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the contractor.