

NOTICE TO CONTRACTORS

CALL ORDER N06

STATE PROJECT NO. RD-8-7(1010)

LOCATION: ON N-8, LIBERTY SPUR EAST.

COUNTIES: GAGE

PAWNEE

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on October 09, 2003 . At that time the bids will be opened and read for GR CULV SEED BR GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 7 MILES

START DATE 06/07/2004 WORKING DAYS 85

Price Range \$ 1,000,000 to \$ 3,000,000

Plans and specifications may be seen beginning September 16, 2003 at the Lincoln Central Office and September 22, 2003 at the District Engineer's Office at LINCOLN

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

NOTICE TO BIDDERS

To be eligible for the award of this contract, bidders shall submit a completed bidding proposal for Call Order No. F04, {Project No. STPD-8-6(113)}, Call Order No. N05, {Project No. PEP-112-1(1003)} and Call Order No. N06, {Project No. RD-8-7(1010)}.

Award of Contract, if awarded, will be made on the combined bid for all contracts.

Separate contracts will be awarded for each Call Order Number.

Please order plans and proposals accordingly.

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	71 SHEETS	\$ 14.20
CROSS SECTIONS (SHEETS X1 THRU X46)	46 SHEETS	\$ 9.20
STANDARD PLANS	11 SHEETS	\$ 2.20

SHEET NO.

1	TITLE PAGE
2T1-2T5	TYPICAL CROSS SECTIONS
2S1-2S3	SUMMARY OF QUANTITIES
2W1-2W14	WETLANDS
2N1-2N2	GENERAL INFORMATION
3 - 9	PLAN SHEETS
10	TRAFFIC CONTROL PLAN
11	TYPICAL YIELD CONTROL FOR LOW VOLUME, ONE LANE, TWO WAY OPERATION
12	TYPICAL PAVEMENT MARKING PLAN
13	TEMPORARY PAVEMENT MARKING PLAN
14 - 16	DRAINAGE STRUCTURE CROSS SECTIONS
17	SPECIAL PLAN 1C REMODEL BRIDGE CURB STA. 490+25.00
18 - 24	SPECIAL PLAN 2C GUARDRAIL PLAN
25 - 26	SPECIAL PLAN 3C CONCRETE PROTECTION BARRIER
27	SPECIAL PLAN 4C SILT FENCE DETAILS
28	SPECIAL PLAN 5C MAILBOX TURNOUT
29 - 30	SPECIAL PLAN 6C MAILBOX SUPPORT POST
31 - 34	SPECIAL PLAN 7C 7' X 7' SINGLE SPAN 7' X 11' SINGLE SPAN RC BOX CULVERT STA. 476+98.00
35	SPECIAL PLAN 8C MODIFIED CONCRETE APRON STA. 476+98.00
36	SPECIAL PLAN 9C CONCRETE BOX CULVERT DROP WALL STA. 476+98.00

37 - 43 SPECIAL PLAN 10C 10' X 8' QUADRUPLE SPAN CONCRETE
 BOX CULVERT WITH MODIFIED PAVED
 CONCRETE INLET & OUTLET
 STA. 729+76.40

R1 - R5 RIGHT-OF-WAY SHEETS
 X1 - X46 CROSS SECTIONS

STANDARD PLANS

329-R5 (4 SHEETS) 6 TO 16 INCH CONCRETE PAVEMENT
 501-R3 EROSION CONTROL
 804 PRECAST CONCRETE R.O.W. MARKER
 920-R5 (2 SHEETS) TRAFFIC CONTROL
 921-R4 TRAFFIC CONTROL
 1108 (2 SHEETS) REINFORCED CONCRETE BOX CULVERTS
 SINGLE SPAN WITH 8-FOOT RISE

Quantities shown herein are FOR INFORMATION ONLY and
 should not be used for bidding purposes. The Department
 reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION		LUMP	LUMP
GENERAL CLEARING AND GRUBBING		LUMP	LUMP
WATER	21		MGAL
RIGHT-OF-WAY MARKERS	11		EACH
EARTHWORK MEASURED IN EMBANKMENT	2,800		CY
REMOVE PAVEMENT	239		SY
REMOVE GUARDRAIL	3,498		LF
EROSION CONTROL	4,760		SY
FABRIC SILT FENCE-LOW POROSITY	1,510		LF

GROUP 4 CULVERTS

MOBILIZATION		LUMP	LUMP
PREPARATION OF STRUCTURE	1		EACH
AT STA. 476+98			
PREPARATION OF STRUCTURE	1		EACH
AT STA. 565+34			
EXCAVATION FOR BOX CULVERTS	283		CY
47B-3000 OR AX-3000 CONC FOR BOX CULV	131		CY
RE-STEEL FOR BOX CULVERT	13,228		LB

GROUP 4A CULVERT AT STA. 729+76.4

MOBILIZATION		LUMP	LUMP
REMOVE STRUCTURE	1		EACH
AT STA. 729+80			
EXCAVATION FOR BOX CULVERTS	2,250		CY
TEMPORARY SHORING		LUMP	LUMP
AT STA. 729+76.4			
47B-3000 OR AX-3000 CONC FOR BOX CULV	391		CY
RE-STEEL FOR BOX CULVERT	40,675		LB

GROUP 5 SEEDING

MOBILIZATION		LUMP	LUMP
SEEDING, TYPE B	20		ACRE
MULCH	46		TON

GROUP 6 BRIDGE AT STA. 490+25

MOBILIZATION		LUMP	LUMP
47BD-4000 CONC FOR BRIDGE	29		CY
RE-STEEL FOR BRIDGE	2,845		LB
PREP BRIDGE	1		EACH
AT STA. 490+25			

GROUP 7 GUARDRAIL

MOBILIZATION		LUMP	LUMP
W-BEAM GUARDRAIL	75		LF
BRIDGE APPROACH SECTIONS	4		EACH
GUARDRAIL END TREATMENT, TYPE II	4		EACH

GROUP 9 BITUMINOUS

CONCRETE PROTECTION BARRIER	775		LF
RELOCATE CONC PROTECTION BARRIER	775		LF
MOBILIZATION		LUMP	LUMP
CRUSHED ROCK SURFACE COURSE	110		TON
SPEC SURF CRSE FOR MAILBOX TURNOUTS	235		SY
MAILBOX POST	7		EACH
TIE BARS	12		EACH
6" CONCRETE BASE COURSE	239		SY
CONC PVMT REPAIR TYPE A FULL DEPTH	11		SY
CONC PVMT REPAIR TYPE B FULL DEPTH	133		SY
CONC PVMT REPAIR TYPE C FULL DEPTH	446		SY
CONC PVMT, PR-3500	3		SY
JOINT REPAIR			
4" YELLOW THERMOPLASTIC	19,600		LF
4" WHITE THERMOPLASTIC	74,600		LF
4" WHITE PREF PVMT MRKNG T-4 GROOVED	400		LF
4" YEL PREF PVMT MRKNG, T-4, GROOVED	40		LF
ASPH CONC FOR STATE MAINT PATCHING, TYPE SP4 SPECIAL (0.5)	200		TON
ASPH CONCRETE FOR PATCHING, TYPE SP4 SPECIAL(0.5)	50		TON
ASPH CONC, TYPE SP4 SPECIAL(0.5)	21,920		TON
PLACE ASPH CONC FOR DRIVE & INTER	2,783		SY
TEMPORARY SURFACING	475		SY
PERF GRAD BIND (64-22)FOR ST MAINT PATCH	10		TON
PERF GRADED BINDER (64-22)	1,186		TON
TACK COAT	20,320		GAL
WATER	189		MGAL
JOINT SEALING - ASPHALT TO CONCRETE	6		STA
EARTH SHOULDER CONSTRUCTION	738		STA
SUBGRADE PREPARATION	767		SY
MILLING CONC FOR INLAYS	2		EACH
SURFACE UNDER GUARDRAIL	330		SY
ASPH PVMT SMOOTHNESS TESTING I/D		LUMP	LUMP

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	12,080		BDAY
BARRICADE, TYPE III	1,036		BDAY
TEMPORARY SIGN DAY	700		EACH
SIGN DAY	15,102		EACH
PAVEMENT MARKING REMOVAL	1,900		LF
TEMP PVMT MARKING, TYPE II	5,800		LF
TEMP PVMT MARKING SURF PREP	3,000		LF
OVERLAY BROKEN LINES	733		STA
OVERLAY SOLID LINES	1,467		STA
FLAGGING	120		DAY
FURNISHING AND OPERATING PILOT VEHICLE	30		DAY
FIELD OFFICE	1		EACH
MOBILIZATION		LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED	25		HOURL
RENTAL OF MOTOR GRADER, FULLY OPERATED	10		HOURL
RENTAL OF DUMP TRUCK, FULLY OPERATED	25		HOURL
RENTAL OF BACKHOE, FULLY OPERATED	15		HOURL
RENTAL OF SKID LOADER, FULLY OPERATED	25		HOURL