

NOTICE TO CONTRACTORS

CALL ORDER F02
FEDERAL PROJECT NO. BRO-7049(18)
LOCATION: ON A COUNTY ROAD SOUTHEAST OF COOK
COUNTIES: JOHNSON

The Nebraska Department of Roads will receive sealed bids for
JOHNSON COUNTY in Room of the Central Office Building at
1500 Hwy 2 at Lincoln, until 1:30 P.M. on November 13, 2003 .
At that time the bids will be opened and read for
GRAD,BR,GDRL

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR
WHO IS QUALIFIED FOR: BRIDGES

Length: 0.4 MILES
START DATE 07/12/2004 WORKING DAYS 80
Price Range \$ 100,000 to \$ 500,000
THIS PROJECT CONTAINS A DBE GOAL OF 3.0 %

Plans and specifications may be seen beginning October 21, 2003 at the Lincoln
Central Office and October 27, 2003 at the District Engineer's Office at LINCOLN
Additional letting information may be found at the Nebraska Department of Roads
Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal
requirements will apply.

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	25 SHEETS	\$ 5.00
CROSS SECTIONS (SHEETS X1 THRU X8)	8 SHEETS	\$ 1.60
STANDARD PLANS	7 SHEETS	\$ 1.40

SHEET NO.

1	TITLE PAGE
2T	TYPICAL CROSS SECTIONS OF IMPROVEMENT
2S	SUMMARY OF QUANTITIES
2N	GENERAL INFORMATION
3	PLAN & PROFILE SHEET
4 - 5	DRAINAGE STRUCTURE CROSS SECTIONS
6 - 15	SPECIAL PLAN 1 PRESTRESSED DOUBLE TEE BRIDGE STA. 17+82.50
16 - 22	SPECIAL PLAN 1C GUARDRAIL PROTECTION
R1	RIGHT-OF-WAY DATA
X1 - X8	CROSS SECTIONS

STANDARD PLANS

410-R3	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
425-R3	COLLARS AND ELBOWS FOR CONCRETE PIPES
920-R5	(2 SHEETS) TRAFFIC CONTROL
921-R4	TRAFFIC CONTROL
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and
should not be used for bidding purposes. The Department
reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
LARGE TREE REMOVAL		10 EACH
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)		9,347 CY
WATER		47 MGAL

GROUP 1 GRADING

24" RD EQUIV DRIVEWAY CULVERT PIPE	50 LF
CRUSHED ROCK EMBEDMENT	19 STA
CRUSHED ROCK SURFACE COURSE	752 TON
REMOVE CULVERT PIPE	40 LF
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL	413 CY
24" CULVERT PIPE	344 LF
24" FLARED-END SECTION	6 EACH
COVER CROP SEEDING	2 ACRE

GROUP 6 BRIDGE AT STA. 17+82.5

MOBILIZATION	LUMP	LUMP
RIPRAP FILTER FABRIC	913 SY	
ABUTMENT NO.1 EXCAVATION	LUMP	LUMP
ABUTMENT NO.2 EXCAVATION	LUMP	LUMP
BENT NO.1 EXCAVATION	LUMP	LUMP
BENT NO.2 EXCAVATION	LUMP	LUMP
47B-3000 CONC FOR BRIDGE	194 CY	
47BD-4000 CONC FOR BRIDGE	104 CY	
PRECAST/PRESTRESSED CONC SUPERSTR	LUMP	LUMP
AT STA. 17+82.5		
RE-STEEL FOR BRIDGE	27,425 LB	
REMOVE STRUCTURE	1 EACH	
AT STA. 17+86 RT.		
STRUC STEEL FOR SUBSTRUCTURE	1,885 LB	
ROCK RIPRAP, TYPE B	792 TON	
HP 10"X42# STEEL PILING	240 LF	
HP 12"X53# STEEL PILING	300 LF	
ROCK SOCKET	99 LF	
28"		
DRILLED SHAFT	54 LF	
34"		

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
BRIDGE APPROACH SECTIONS	4 EACH	
MELT	4 EACH	

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE III	1,656 BDAY
SIGN DAY	2,070 EACH
CONTRACTOR FURNISHED SIGN DAY	552 EACH
MOBILIZATION	LUMP LUMP