

NOTICE TO CONTRACTORS

CALL ORDER F03
FEDERAL PROJECT NO. BRO-7013(9)
LOCATION: ON A COUNTY ROAD NORTHEAST OF GREENWOOD
COUNTIES: CASS

The Nebraska Department of Roads will receive sealed bids for
CASS COUNTY in Room of the Central Office Building at
1500 Hwy 2 at Lincoln, until 1:30 P.M. on November 13, 2003 .
At that time the bids will be opened and read for
BRIDGE

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR
WHO IS QUALIFIED FOR: BRIDGES

START DATE 08/02/2004 WORKING DAYS 65
Price Range \$ 100,000 to \$ 500,000
THIS PROJECT CONTAINS A DBE GOAL OF 4.0 %

Plans and specifications may be seen beginning October 21, 2003 at the Lincoln
Central Office and October 27, 2003 at the District Engineer's Office at LINCOLN
Additional letting information may be found at the Nebraska Department of Roads
Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal
requirements will apply.

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	21	SHEETS	\$ 4.20
CROSS SECTIONS (SHEETS X1 THRU X9)	9	SHEETS	\$ 1.80
STANDARD PLANS	6	SHEETS	\$ 1.20

SHEET NO.

1	TITLE PAGE
2T	TYPICAL CROSS SECTION OF IMPROVEMENT
2S	SUMMARY OF QUANTITIES
3	ROADWAY PLAN & PROFILE SHEET
4 - 5	DRAINAGE STRUCTURE CROSS SECTIONS
6 - 12	SPECIAL PLAN 1 CONCRETE SLAB BRIDGE STA. 39+10.00
13 - 19	SPECIAL PLAN 1C GUARDRAIL PROTECTION
R1	RIGHT-OF-WAY DATA
X1 - X6	CROSS SECTIONS OF ROADWAY
X7 - X9	CROSS SECTIONS OF CHANNEL

STANDARD PLANS

410-R3	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
920-R5	(2 SHEETS) TRAFFIC CONTROL
921-R4	TRAFFIC CONTROL
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and
should not be used for bidding purposes. The Department
reserves the right to change these quantities without notice.

GROUP 6 BRIDGE AT STA. 39+10

BARRICADE, TYPE III	1,416	BDAY
SIGN DAY	2,124	EACH
CONTRACTOR FURNISHED SIGN DAY	236	EACH
MOBILIZATION	LUMP	LUMP
LARGE TREE REMOVAL	1	EACH
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)	3,182	CY
WATER	25	MGAL
18" CMP FOR DRIVEWAY CULVERT PIPE	134	LF
GRAVEL SURFACE COURSE	82	TON
CRUSHED ROCK EMBEDMENT	9	STA

GROUP 6 BRIDGE AT STA. 39+10

CRUSHED ROCK SURFACE COURSE	152 TON
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL	281 CY
18" CORRUGATED METAL PIPE	68 LF
24" CORRUGATED METAL PIPE	212 LF
18" METAL FLARED-END SECTION	1 EACH
24" METAL FLARED-END SECTION	3 EACH
ABUTMENT NO.1 EXCAVATION	LUMP LUMP
ABUTMENT NO.2 EXCAVATION	LUMP LUMP
BENT NO.1 EXCAVATION	LUMP LUMP
BENT NO.2 EXCAVATION	LUMP LUMP
47B-3000 CONC FOR BRIDGE	144 CY
47BD-4000 CONC FOR BRIDGE	214 CY
RE-STEEL FOR BRIDGE	49,972 LB
REMOVE STRUCTURE	1 EACH
AT STA. 39+11	
STRUC STEEL FOR SUBSTRUCTURE	5,141 LB
ROCK RIPRAP, TYPE B	500 TON
HP 10"X42# STEEL PILING	1,910 LF
STEEL SHEET PILING	3,232 SF
BRIDGE APPROACH SECTIONS	4 EACH
MELT	4 EACH
SEEDING, TYPE A	1 ACRE
COVER CROP SEEDING	1 ACRE
MULCH	2 TON