

NOTICE TO CONTRACTORS

CALL ORDER F09

FEDERAL PROJECT NO. BRO-7054(10)

LOCATION: ON A COUNTY ROAD SOUTHWEST OF VERDIGRE.

COUNTIES: KNOX

The Nebraska Department of Roads will receive sealed bids for  
KNOX COUNTY in Room of the Central Office Building at  
1500 Hwy 2 at Lincoln, until 1:30 P.M. on November 13, 2003 .  
At that time the bids will be opened and read for  
GR BR GDRL

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR  
WHO IS QUALIFIED FOR: BRIDGES

Length: 0.4 MILES

START DATE 07/06/2004 WORKING DAYS 85

Price Range \$ 100,000 to \$ 500,000

Plans and specifications may be seen beginning October 21, 2003 at the Lincoln  
Central Office and October 27, 2003 at the District Engineer's Office at NORFOLK

Additional letting information may be found at the Nebraska Department of Roads  
Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal  
requirements will apply.

PLANS (NOT INCLUDING STANDARDS)	28 SHEETS	\$ 3.60
STANDARD PLANS	4 SHEETS	\$ .80

SHEET NO.

1	TITLE PAGE
2T	TYPICAL CROSS SECTIONS OF IMPROVEMENT
2S	SUMMARY OF QUANTITIES
3	PLAN & PROFILE SHEET
4 - 10	CROSS SECTIONS
11 - 19	SPECIAL PLAN 1 CONCRETE SLAB BRIDGE STA. 13+02.00
20 - 26	SPECIAL PLAN 1C GUARDRAIL PROTECTION
R1	RIGHT-OF-WAY DATA

STANDARD PLANS

920-R5	(2 SHEETS) TRAFFIC CONTROL
921-R4	TRAFFIC CONTROL
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and  
should not be used for bidding purposes. The Department  
reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
LARGE TREE REMOVAL		8 EACH
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)	11,783	CY
WATER	79	MGAL
18" DRIVEWAY CULVERT PIPE	146	LF
36" DRIVEWAY CULVERT PIPE	108	LF
48" RD EQUIV DRIVEWAY CULVERT PIPE	132	LF
GRAVEL SURFACE COURSE	295	CY
18" AUTO. FLOOD CONTROL GATE	1	EACH
36" AUTO. FLOOD CONTROL GATE	3	EACH
COVER CROP SEEDING	3	ACRE

GROUP 6 BRIDGE AT STA. 13+02.00

MOBILIZATION	LUMP	LUMP
RIPRAP FILTER FABRIC		267 SY
ABUTMENT NO.1 EXCAVATION	LUMP	LUMP
ABUTMENT NO.2 EXCAVATION	LUMP	LUMP
BENT NO.1 EXCAVATION	LUMP	LUMP
BENT NO.2 EXCAVATION	LUMP	LUMP
BENT NO.3 EXCAVATION	LUMP	LUMP
47B-3000 CONC FOR BRIDGE		139 CY
47BD-4000 CONC FOR BRIDGE		410 CY
RE-STEEL FOR BRIDGE		78,230 LB
REMOVE STRUCTURE		1 EACH
AT STA. 12+99		
STRUC STEEL FOR SUBSTRUCTURE		1,535 LB
ROCK RIPRAP, TYPE B		236 TON
HP 10"X42# STEEL PILING		1,885 LF

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
BRIDGE APPROACH SECTIONS		4 EACH
MELT		4 EACH

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE III		1,740 BDAY
SIGN DAY		2,175 EACH
CONTRACTOR FURNISHED SIGN DAY		580 EACH
MOBILIZATION	LUMP	LUMP