

NOTICE TO CONTRACTORS

CALL ORDER F12
FEDERAL PROJECT NO. EACSTPD-32-7(105)
LOCATION: N-32, WEST POINT - OAKLAND.
COUNTIES: BURT
CUMING

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on November 13, 2003 . At that time the bids will be opened and read for GR BR GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BRIDGES BITUMINOUS
START DATE 03/01/2004 WORKING DAYS 125
Price Range \$ 1,000,000 to \$ 3,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 1.50 %

Plans and specifications may be seen beginning October 21, 2003 at the Lincoln Central Office and October 27, 2003 at the District Engineer's Office at NORFOLK
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

NOTICE TO BIDDERS

To be eligible for the award of this contract, bidders shall submit a completed bidding proposal for both Call Order No. F12, {Project No. EACSTPD-32-7(105)} and Call Order No. F11, {Project No. EACSTPD-32-7(104)}.

Award of Contract, if awarded, will be made on the combined bid for both contracts.

Separate contracts will be awarded for each Call Order Number.

Please order plans and proposals accordingly.

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	81	SHEETS	\$ 16.20
CROSS SECTIONS (SHEETS X1 THRU X12)	12	SHEETS	\$ 2.40
STANDARD PLANS	3	SHEETS	\$.60

SHEET NO.

1	TITLE PAGE
2T	TYPICAL CROSS SECTIONS
2S1-2S2	SUMMARY OF QUANTITIES
2W1-2W3	WETLANDS
2H	HORIZONTAL ALIGNMENT & CONTROL POINTS
2N	GENERAL INFORMATION
3 - 5	PLAN & PROFILE SHEETS
6	TRAFFIC CONTROL PLAN
7	TYPICAL TRAFFIC SIGNAL CONTROL PLAN FOR ONE LANE, TWO WAY OPERATION
8	TEMPORARY TRAFFIC SIGNAL
9	TYPICAL PAVEMENT MARKING PLAN
10	TEMPORARY PAVEMENT MARKING PLAN
11	DRAINAGE STRUCTURE CROSS SECTIONS
12 - 28	SPECIAL PLAN 1 PRESTRESSED INVERTED T-400 BRIDGE STA. 168+91.00
29 - 45	SPECIAL PLAN 2 PRESTRESSED INVERTED T-500 BRIDGE STA. 318+94.00
46 - 62	SPECIAL PLAN 3 ROLLED GIRDER BRIDGE WIDEN & REHAB STA. 628+79.00
63 - 71	SPECIAL PLAN 1C GUARDRAIL PLAN
72	SPECIAL PLAN 2C SILT FENCE DETAILS
73 - 74	SPECIAL PLAN 3C CONCRETE PROTECTION BARRIER
X1 - X12	CROSS SECTIONS

STANDARD PLANS

501-R3	EROSION CONTROL
920-R5	(2 SHEETS) TRAFFIC CONTROL

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION		LUMP	LUMP
GENERAL CLEARING AND GRUBBING		LUMP	LUMP
WATER	75		MGAL
EARTHWORK MEASURED IN EMBANKMENT	7,561		CY
REMOVE PAVEMENT	803		SY
REMOVE SPLASH BASIN	1		EACH
REMOVE INLET	6		EACH
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL	81		CY
REMOVE GUARDRAIL	1,064		LF
EROSION CONTROL	8,907		SY
FABRIC SILT FENCE-LOW POROSITY	631		LF

GROUP 6 BRIDGE AT STA. 168+91

MOBILIZATION		LUMP	LUMP
EARTHWORK MEASURED IN EMBANKMENT	360		CY
RIPRAP FILTER FABRIC	70		SY
CONC FOR PVMT APPROACHES CLASS 47BD-4000	190		CY
EPOXY COATED RE-STEEL FOR PVMT APPROACH	20,790		LB
ABUTMENT NO.1 EXCAVATION		LUMP	LUMP
ABUTMENT NO.2 EXCAVATION		LUMP	LUMP
BENT NO.1 EXCAVATION		LUMP	LUMP
BENT NO.2 EXCAVATION		LUMP	LUMP
PRECOMPRESSED POLY FOAM JOINT	92		LF
47B-3000 CONC FOR BRIDGE	199		CY
47BD-5000 CONC FOR BRIDGE	114		CY
PRECAST/PRESTRESSED CONC SUPERSTR		LUMP	LUMP
AT STA. 168+91			
REMOVE STRUCTURE	1		EACH
AT STA. 168+91			
STRUC STEEL FOR SUBSTRUCTURE	720		LB
BROKEN CONCRETE RIPRAP	185		TON
ROCK RIPRAP, TYPE B	50		TON
EPOXY COATED RE-STEEL	48,595		LB
SUBSURFACE DRAINAGE MATTING	37		SY
PIPE PILING	4,000		LF
STEEL SHEET PILING	2,933		SF
TEMP BRIDGE SHORING		LUMP	LUMP
GRANULAR BACKFILL	130		CY

GROUP 6A BRIDGE AT STA. 318+94

MOBILIZATION		LUMP	LUMP
EARTHWORK MEASURED IN EMBANKMENT	1,550		CY
RIPRAP FILTER FABRIC	62		SY
CONC FOR PVMT APPROACHES CLASS 47BD-4000	190		CY
EPOXY COATED RE-STEEL FOR PVMT APPROACH	20,680		LB
ABUTMENT NO.1 EXCAVATION		LUMP	LUMP
ABUTMENT NO.2 EXCAVATION		LUMP	LUMP
BENT NO.1 EXCAVATION		LUMP	LUMP
BENT NO.2 EXCAVATION		LUMP	LUMP
PRECOMPRESSED POLY FOAM JOINT	92		LF
47B-3000 CONC FOR BRIDGE	215		CY
47BD-5000 CONC FOR BRIDGE	170		CY
PRECAST/PRESTRESSED CONC SUPERSTR		LUMP	LUMP
AT STA. 318+94			
REMOVE STRUCTURE	1		EACH
AT STA. 318+90			
STRUC STEEL FOR SUBSTRUCTURE	960		LB
BROKEN CONCRETE RIPRAP	453		TON

GROUP 6A BRIDGE AT STA. 318+94

EPOXY COATED RE-STEEL	62,335	LB
SUBSURFACE DRAINAGE MATTING	40	SY
PIPE PILING	4,760	LF
STEEL SHEET PILING	2,933	SF
TEMP BRIDGE SHORING	LUMP	LUMP
GRANULAR BACKFILL	135	CY

GROUP 6B BRIDGE AT STA. 628+79

MOBILIZATION	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)	4,230	CY
RIPRAP FILTER FABRIC	76	SY
CONC FOR PVMT APPROACHES CLASS 47BD-4000	193	CY
EPOXY COATED RE-STEEL FOR PVMT APPROACH	26,795	LB
ABUTMENT NO.1 EXCAVATION	LUMP	LUMP
ABUTMENT NO.2 EXCAVATION	LUMP	LUMP
PIER NO.1 EXCAVATION	LUMP	LUMP
PIER NO.2 EXCAVATION	LUMP	LUMP
PRECOMPRESSED POLY FOAM JOINT	92	LF
EXPANSION BEARING, TFE TYPE	21	EACH
FIXED BEARING	7	EACH
47B-3000 CONC FOR BRIDGE	174	CY
47BD-4000 CONC FOR BRIDGE	369	CY
PREP BRIDGE	1	EACH
AT STA. 628+79		
STEEL SUPERSTRUCTURE	LUMP	LUMP
AT STA. 628+79		
STRUC STEEL FOR SUBSTRUCTURE	1,120	LB
BROKEN CONCRETE RIPRAP	165	TON
EPOXY COATED RE-STEEL	101,160	LB
SUBSURFACE DRAINAGE MATTING	53	SY
PIPE PILING	1,335	LF
TEMP BRIDGE SHORING	LUMP	LUMP
GRANULAR BACKFILL	180	CY

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
W-BEAM GUARDRAIL	375	LF
IMPACT ATTENUATOR	1	EACH
BRIDGE APPROACH SECTIONS	12	EACH
GUARDRAIL END TREATMENT, TYPE II	11	EACH

GROUP 9 BITUMINOUS

OVERLAY BROKEN LINES	22	STA
OVERLAY SOLID LINES	45	STA
PERMANENT PAVEMENT MARKING PAINT	4,600	LF
MOBILIZATION	LUMP	LUMP
ASPH CONCRETE FOR PATCHING, TYPE SP4(0.375)	100	TON
ASPH CONC, TYPE SP4(0.375)	900	TON
SURFACING 10"	1,848	SY
PERF GRADED BINDER (64-28)	54	TON
TACK COAT	910	GAL
WATER	36	MGAL
EARTH SHOULDER CONSTRUCTION	28	STA
SUBGRADE PREPARATION	1,848	SY
SURFACE UNDER GUARDRAIL	914	SY
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	5,452	BDAY
BARRICADE, TYPE III	4,568	BDAY
TEMPORARY SIGN DAY	126	EACH
SIGN DAY	24,999	EACH
PAVEMENT MARKING REMOVAL	2,600	LF
TEMP PVMT MARKING, TYPE II	6,100	LF
TEMP PVMT MARKING SURF PREP	3,000	LF
FLAGGING	26	DAY
CONCRETE PROTECTION BARRIER	1,425	LF
RELOCATE CONC PROTECTION BARRIER	1,425	LF
TEMPORARY RUMBLE STRIP	12	EACH
TEMPORARY TRAFFIC SIGNAL	3	EACH
FIELD OFFICE	1	EACH
TRAINING	2,000	HOURL
MOBILIZATION		LUMP
RENTAL OF LOADER, FULLY OPERATED	20	HOURL
RENTAL OF MOTOR GRADER, FULLY OPERATED	10	HOURL
RENTAL OF DUMP TRUCK, FULLY OPERATED	20	HOURL
RENTAL OF BACKHOE, FULLY OPERATED	10	HOURL
RENTAL OF SKID LOADER, FULLY OPERATED	20	HOURL