

NOTICE TO CONTRACTORS

CALL ORDER F28
FEDERAL PROJECT NO. EACSTPD-25-2(107)
LOCATION: ON N-25 NORTH OF WALLACE.
COUNTIES: LINCOLN

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on November 13, 2003 . At that time the bids will be opened and read for GR CULV BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: GRADING BITUMINOUS

Length: 12.2 MILES
START DATE 01/05/2004 WORKING DAYS 120
Price Range \$ 3,000,000 to \$ 6,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 3.00 %

Plans and specifications may be seen beginning October 21, 2003 at the Lincoln Central Office and October 27, 2003 at the District Engineer's Office at NORTH PLATTE

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	100 SHEETS	\$20.00
CROSS SECTIONS (SHEETS X1 THRU X127)	127 SHEETS	\$25.40
STANDARD PLANS	10 SHEETS	\$ 2.00

SHEET NO.	
1	TITLE PAGE
2	INDEX OF SHEETS
2T1-2T2	TYPICAL CROSS SECTIONS
2S1-2S3	SUMMARY OF QUANTITIES & DETOUR LOCATION MAP
2W1-2W11	WETLANDS
2H1-2H3	HORIZONTAL ALIGNMENT & CONTROL POINTS
2N1-2N2	GENERAL INFORMATION
3 - 25	PLAN & PROFILE SHEETS
26 - 34	EARTHWORK DATA SHEETS
35 - 44	DRAINAGE STRUCTURE CROSS SECTIONS
45 - 48	SPECIAL PLAN 1C BEDDING & BACKFILL REQUIREMENTS FOR CONCRETE PIPE, MCCMP, PCCMP, & PLASTIC PIPE
49 - 50	SPECIAL PLAN 2C 10' X 8' SEXTUPLE SPAN RC BOX CULVERT STA. 178+51.10
51	SPECIAL PLAN 3C SILT FENCE DETAILS
52	SPECIAL PLAN 4C EROSION CHECKS (ALL TYPES) & FABRIC SILT CHECKS
53	SPECIAL PLAN 5C EROSION CONTROL, TYPES "A" & "AA"
54	SPECIAL PLAN 6C EROSION CONTROL, TYPE "AAA" (OUTLET TREATMENT)
55 - 56	SPECIAL PLAN 7C MAILBOX SUPPORT POST
57	SPECIAL PLAN 8C MAILBOX TURNOUT
R1 - R22	RIGHT-OF-WAY SHEETS
X1 - X127	CROSS SECTIONS

STANDARD PLANS

108-R2	SUPERELEVATION PLAN FOR CONCRETE AND BITUMINOUS SURFACING
410-R3	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
501-R3	EROSION CONTROL
804	PRECAST CONCRETE R.O.W. MARKER
901-R8	HIGHWAY DELINEATORS
920-R5	(2 SHEETS) TRAFFIC CONTROL
921-R4	TRAFFIC CONTROL
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION	515,550	CY
WATER	7,732	MGAL
RIGHT-OF-WAY MARKERS	240	EACH
SLOPE PROTECTION	546,572	SY
SLOPE PROTECTION MULCH	547	TON
REMOVE DRIVEWAY	25	SY
REMOVE RETAINING WALL	1	EACH
REMOVE	1	EACH
CISTERN		
24" DRIVE PIPE 2,3,4,5,6,7 OR 8	1,686	LF
REMOVE FLARED- END SECTION	8	EACH
REMOVE HEADWALLS FROM CULV	2	EACH
REMOVE GUARDRAIL	278	LF
EROSION CONTROL, TYPE A	2,202	SY
EROSION CONTROL, TYPE C	13,179	SY
EROSION CONTROL, TYPE AAA	658	SY
EROSION CONTROL, TYPE HV	6,030	SY
EROSION CHECKS, TYPE A	120	BALE
EROSION CHECKS, TYPE C	378	BALE
EROSION CHECKS, TYPE HV	1,230	BALE
FABRIC SILT FENCE, COIR FIBER	15,365	LF

GROUP 4 CULVERTS

MOBILIZATION	LUMP	LUMP
REMOVE FLARED- END SECTION	19	EACH
REMOVE HEADWALLS FROM CULV	1	EACH
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL	1,334	CY
24" FLARED-END SECTION	28	EACH
30" FLARED-END SECTION	4	EACH
36" FLARED-END SECTION	2	EACH
24" CULV PIPE 2,3,4,5,6,7,8	822	LF
30" CULV PIPE 2,3,4,5,6,7,8	149	LF
36" CULV PIPE 2,3,4,5,6,7,8	50	LF
24" CULV PIPE 3,4,5	106	LF

GROUP 4A CULVERT AT STA. 178+51

MOBILIZATION	LUMP	LUMP
PREPARATION OF STRUCTURE	1	EACH
AT STA. 178+51		
EXCAVATION FOR BOX CULVERTS	1,045	CY
47B-3000 OR AX-3000 CONC FOR BOX CULV	366	CY
RE-STEEL FOR BOX CULVERT	40,071	LB

GROUP 9 BITUMINOUS

OVERLAY BROKEN LINES	645	STA
MOBILIZATION	LUMP	LUMP
DELINEATOR, TYPE III	33	EACH
INSTALL CHEVRONS	16	EACH
GRAVEL SURFACE COURSE	265	CY
GRAVEL EMBEDMENT	6	STA
SPEC SURF CRSE FOR MAILBOX TURNOUTS	152	SY
MAILBOX POST	2	EACH
BIT FOUNDATION COURSE 5"	167,651	SY
ASPH CONCRETE FOR PATCHING, TYPE	100	TON
SP4 SPECIAL(0.5)		
ASPH CONC, TYPE SP4 SPECIAL(0.5)	54,080	TON
PLACE ASPH CONC FOR DRIVE & INTER	1,997	SY
PERF GRADED BINDER (64-22)	2,925	TON

PREP OF INTER & DRIVE	1,997	SY
TACK COAT	42,440	GAL
WATER	862	MGAL
EARTH SHOULDER CONSTRUCTION	1,289	STA
SUBGRADE PREPARATION	538	STA
TRENCHED WIDENING	212	STA
COLD MILLING, CLASS 3	106	STA
COLD MILLING, CLASS 4	538	STA
COLD MILLING, CLASS 3	538	STA
TYPE A		
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE III	5,825	BDAY
TEMPORARY SIGN DAY	270	EACH
SIGN DAY	8,683	EACH
CONTRACTOR FURNISHED SIGN DAY	2,299	EACH
FLAGGING	30	DAY
FURNISHING AND OPERATING PILOT VEHICLE	15	DAY
TRAFFIC CONTROL MANAGEMENT	30	DAY
FIELD OFFICE	1	EACH
MOBILIZATION		LUMP
CONSTRUCTION STAKING AND SURVEYING		LUMP
RENTAL OF LOADER, FULLY OPERATED	170	HOURL
RENTAL OF MOTOR GRADER, FULLY OPERATED	20	HOURL
RENTAL OF DUMP TRUCK, FULLY OPERATED	170	HOURL
RENTAL OF BACKHOE, FULLY OPERATED	150	HOURL
RENTAL OF SKID LOADER, FULLY OPERATED	170	HOURL