

# NOTICE TO CONTRACTORS

CALL ORDER F33  
 FEDERAL PROJECT NO. BRO-7024(23)  
 LOCATION: ON A COUNTY ROAD SOUTHWEST OF GOTHENBURG.  
 COUNTIES: DAWSON

The Nebraska Department of Roads will receive sealed bids for  
 DAWSON COUNTY in Room of the Central Office Building at  
 1500 Hwy 2 at Lincoln, until 1:30 P.M. on November 13, 2003 .  
 At that time the bids will be opened and read for  
 BRIDGE

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR  
 WHO IS QUALIFIED FOR: BRIDGES  
 START DATE 07/19/2004 WORKING DAYS 75  
 Price Range \$ 100,000 to \$ 500,000

Plans and specifications may be seen beginning October 21, 2003 at the Lincoln  
 Central Office and October 27, 2003 at the District Engineer's Office at NORTH PLATTE  
 Additional letting information may be found at the Nebraska Department of Roads  
 Web Site at <http://www.dor.state.ne.us/letting/>.  
 This project is funded under the Federal-Aid Highway Act, all appropriate Federal  
 requirements will apply.

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	23	SHEETS	\$ 4.60
CROSS SECTIONS (SHEETS X1 THRU X3)	3	SHEETS	\$ .60
STANDARD PLANS	4	SHEETS	\$ .80

## SHEET NO.

1	TITLE PAGE
2T	TYPICAL CROSS SECTIONS
2S	SUMMARY OF QUANTITIES
3	PLAN & PROFILE SHEET, STA. 4+00 TO STA. 16+00
4 - 13	SPECIAL PLAN 1 PRESTRESSED GIRDER BRIDGE (NU-1600) STA. 9+92.00
14 - 22	SPECIAL PLAN 1C GUARDRAIL PROTECTION
X1 - X3	CROSS SECTIONS

## STANDARD PLANS

920-R5	(2 SHEETS) TRAFFIC CONTROL
921-R4	TRAFFIC CONTROL
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and  
 should not be used for bidding purposes. The Department  
 reserves the right to change these quantities without notice.

## GROUP 6 BRIDGE AT STA.9+92

BARRICADE, TYPE III	1,584	BDAY
SIGN DAY	264	EACH
CONTRACTOR FURNISHED SIGN DAY	2,376	EACH
MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER	20	MGAL
EARTHWORK MEASURED IN EMBANKMENT	1,488	CY
RIPRAP FILTER FABRIC	270	SY
ABUTMENT NO.1 EXCAVATION	LUMP	LUMP
ABUTMENT NO.2 EXCAVATION	LUMP	LUMP
EXPANSION BEARING, TFE TYPE	6	EACH
FIXED BEARING	6	EACH
47B-3000 CONC FOR BRIDGE	127	CY
47BD-5000 CONC FOR BRIDGE	196	CY

GROUP 6 BRIDGE AT STA.9+92

PRECAST/PRESTRESSED CONC SUPERSTR	LUMP	LUMP
AT STA. 9+92		
RE-STEEL FOR BRIDGE	32,780	LB
REMOVE STRUCTURE	1	EACH
AT STA. 10+00		
STRUC STEEL FOR SUBSTRUCTURE	580	LB
ROCK RIPRAP, TYPE B	182	TON
HP 8"X36# STEEL PILING	560	LF
HP 10"X42# STEEL PILING	1,820	LF
TEST PILE	2	EACH
W-BEAM GUARDRAIL	40	LF
BRIDGE APPROACH SECTIONS	4	EACH
MELT, TYPE I	3	EACH
END ANCHORAGE ASSEMBLY	1	EACH
GRANULAR BACKFILL	255	CY
COVER CROP SEEDING	1	ACRE