

NOTICE TO CONTRACTORS

CALL ORDER N21

STATE PROJECT NO. S-20-1(1024)
 LOCATION: ON US-20 WEST OF CRAWFORD.
 COUNTIES: DAWES SIOUX

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on November 13, 2003 . At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 9.5 MILES
 START DATE 04/05/2004 WORKING DAYS 120
 Price Range \$ 1,000,000 to \$ 3,000,000

Plans and specifications may be seen beginning October 21, 2003 at the Lincoln Central Office and October 27, 2003 at the District Engineer's Office at BRIDGEPORT
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	62 SHEETS	\$ 12.40
CROSS SECTIONS (SHEETS X1 THRU X38)	38 SHEETS	\$ 7.20
STANDARD PLANS	7 SHEETS	\$ 1.40

SHEET NO.

1	TITLE PAGE
2T1-2T5	TYPICAL CROSS SECTIONS
2S1-2S2	SUMMARY OF QUANTITIES
2W1-2W9	WETLANDS
2N	GENERAL INFORMATION
3 - 11	PLAN SHEETS
12	TRAFFIC CONTROL PLAN
13	TRAFFIC CONTROL PLAN--BRIDGE CURB REPAIR
14	TYPICAL PAVEMENT MARKING PLAN
15	TEMPORARY PAVEMENT MARKING PLAN
16 - 22	DRAINAGE STRUCTURE CROSS SECTIONS
23	SPECIAL PLAN 1C REMODEL BRIDGE RAIL STA. 1113+23.43
24	SPECIAL PLAN 2C REMODEL BRIDGE RAIL STA. 1232+45.75
25	SPECIAL PLAN 3C BRIDGE REPAIR STA. 1232+45.75
26	SPECIAL PLAN 4C DOWELING INTO EXISTING CONCRETE BOX CULVERT FOR CULVERT EXTENSION
27 - 29	SPECIAL PLAN 5C 8' X 8' SINGLE SPAN RC BOX CULVERT STA. 216+05.00
30 - 31	SPECIAL PLAN 6C 10' X 3' SINGLE SPAN RC BOX CULVERT STA. 232+62.00
32	SPECIAL PLAN 7C CONCRETE FLUME, TYPE I
33 - 34	SPECIAL PLAN 8C CONCRETE FLUME, TYPE VII
35 - 37	SPECIAL PLAN 9C CABLE GUARDRAIL
38 - 45	SPECIAL PLAN 10C GUARDRAIL PLAN
46	SPECIAL PLAN 11C EROSION CONTROL, TYPES "A" & "AA"
X1 - X38	CROSS SECTIONS

STANDARD PLANS

108-R2	SUPERELEVATION PLAN FOR CONCRETE AND BITUMINOUS SURFACING
428-R2	CONCRETE PLUGS AND FIELD PIPE TAP DETAILS
501-R3	EROSION CONTROL
920-R5	(2 SHEETS) TRAFFIC CONTROL
1108	(2 SHEETS) REINFORCED CONCRETE BOX CULVERTS SINGLE SPAN WITH 8-FOOT RISE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	34,608	BDAY
BARRICADE, TYPE III	2,132	BDAY
TEMPORARY SIGN DAY	1,352	EACH
SIGN DAY	10,928	EACH
OVERLAY BROKEN LINES	1,511	STA
OVERLAY SOLID LINES	3,023	STA
FLAGGING	126	DAY
FURNISHING AND OPERATING PILOT VEHICLE	45	DAY
MOBILIZATION		LUMP
GENERAL CLEARING AND GRUBBING		LUMP
EARTHWORK MEASURED IN EMBANKMENT	3,488	CY
REMOVE CONCRETE FLUME	12	EACH
GRAVEL SURFACE COURSE	135	CY
CAST IRON GRATE & FRAME	1,904	LB
FLUME SPILLWAY	30	LF
CONCRETE FLUME, TYPE I	4	EACH
PREPARATION OF STRUCTURE AT STA. 216+05	1	EACH
PREPARATION OF STRUCTURE AT STA. 232+62	1	EACH
PREPARATION OF STRUCTURE AT STA. 307+00	1	EACH
EXCAVATION FOR BOX CULVERTS	365	CY
47B-3000 OR AX-3000 CONC FOR BOX CULV	117	CY
47B-3000 CONC FOR INLET & JUNCTION BOXES	7	CY
47B-3000 OR AX-3000 FOR CONC BOX CULV PL	4	CY
RE-STEEL FOR BOX CULVERT	11,407	LB
RE-STEEL FOR INLET & JCT BOX	546	LB
47BD-4000 CONC FOR BRIDGE	6	CY
RE-STEEL FOR BRIDGE	990	LB
PREP BRIDGE AT STA.1232+45	1	EACH
W-BEAM GUARDRAIL	125	LF
CABLE GUARDRAIL	3,217	LF
REMOVE & SALVAGE GUARDRAIL	10,861	LF
RESET GUARDRAIL	3,568	LF
BRIDGE APPROACH SECTIONS	8	EACH
TERMINAL ANCHORAGE SECTIONS	22	EACH
INTERMEDIATE ANCHORAGE SECTIONS	1	EACH
GUARDRAIL END TREATMENT, TYPE II	8	EACH
4" YELLOW EPOXY PVMT MARKING	40,000	LF
4" WHITE EPOXY PVMT MARKING	100,000	LF
HYDRATED LIME	443	TON
HYDRATED LIME SLURRY STABILIZATION	513	STA
ASPH CONC FOR STATE MAINT PATCHING, TYPE SPS	200	TON
ASPH CONCRETE FOR PATCHING, TYPE SP4(0.375)	1,000	TON
ASPH CONC, TYPE SPS	12,380	TON
ASPH CONC, TYPE SP4(0.375)	21,910	TON
PLACE ASPH CONC FOR DRIVE & INTER	8,676	SY
PERF GRAD BIND (58-28)FOR ST MAINT PATCH	10	TON
PERF GRADED BINDER (58-28)	668	TON
PERF GRADED BINDER (64-28)	1,237	TON
CONSTRUCTING ASPH CONC CURB	5,374	LF
EMUL ASPH FOR HYDRATE LIME STABILIZATION	107,994	GAL
TACK COAT	44,410	GAL
RENTAL OF LOADER, FULLY OPERATED	50	HOURL
RENTAL OF MOTOR GRADER, FULLY OPERATED	50	HOURL
RENTAL OF DUMP TRUCK, FULLY OPERATED	50	HOURL
RENTAL OF SKID LOADER, FULLY OPERATED	50	HOURL
WATER	343	MGAL
EARTH SHOULDER CONSTRUCTION	1,008	STA

GROUP 9 BITUMINOUS

COLD MILLING, CLASS 3	202,713	SY
COLD MILLING, CLASS 3	8,143	SY
A		
SURFACE UNDER GUARDRAIL	1,531	SY
ASPH PVMT SMOOTHNESS TESTING	LUMP	LUMP
SEEDING, TYPE B	28	ACRE
EROSION CONTROL	28,229	SY
EROSION CONTROL, TYPE A	464	SY
MULCH	63	TON
15" CULV PIPE 3,4,5,6	162	LF