

# NOTICE TO CONTRACTORS

CALL ORDER N24

STATE PROJECT NO. PEP-71-3(1039)

LOCATION: ON N-71, SCOTTSBLUFF NORTH.

COUNTIES: SCOTTS BLUFF

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on November 13, 2003 . At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 6.7 MILES

START DATE 08/16/2004 WORKING DAYS 40

Price Range \$ 500,000 to \$ 1,000,000

Plans and specifications may be seen beginning October 21, 2003 at the Lincoln Central Office and October 27, 2003 at the District Engineer's Office at BRIDGEPORT

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

PLANS (NOT INCLUDING STANDARDS)	4 SHEETS	\$ .80
STANDARD PLANS	2 SHEETS	\$ .40

## SHEET NO.

1	TITLE PAGE
2S	SUMMARY OF QUANTITIES & TYPICAL CROSS SECTIONS
3	TRAFFIC CONTROL PLAN
4	TEMPORARY PAVEMENT MARKING PLAN

## STANDARD PLANS

920-R5 (2 SHEETS) TRAFFIC CONTROL

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

## GROUP 9 BITUMINOUS

BARRICADE, TYPE II	7,040 BDAY
BARRICADE, TYPE III	304 BDAY
TEMPORARY SIGN DAY	480 EACH
SIGN DAY	5,472 EACH
OVERLAY BROKEN LINES	1,065 STA
OVERLAY SOLID LINES	2,130 STA
FLAGGING	60 DAY
FURNISHING AND OPERATING PILOT VEHICLE	30 DAY
FIELD OFFICE	1 EACH
MOBILIZATION	LUMP LUMP
HYDRATED LIME	270 TON
HYDRATED LIME SLURRY STABILIZATION	354 STA
ASPH CONC FOR STATE MAINT PATCHING, TYPE SP4(0.375)	200 TON
ASPH CONCRETE FOR PATCHING, TYPE SP4(0.375)	200 TON
ASPH CONC, TYPE SP4(0.375)	16,670 TON
PERF GRAD BIND (64-28)FOR ST MAINT PATCH	10 TON
PERF GRADED BINDER (64-28)	910 TON
EMUL ASPH FOR HYDRATE LIME STABILIZATION	65,300 GAL
TACK COAT	10,990 GAL
RENTAL OF LOADER, FULLY OPERATED	20 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	20 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	20 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	20 HOUR

GROUP 9 BITUMINOUS

WATER	177	MGAL
EARTH SHOULDER CONSTRUCTION	709	STA
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP
SEEDING, TYPE B	20	ACRE
MULCH	45	TON