

NOTICE TO CONTRACTORS

CALL ORDER N37  
STATE PROJECT NO. RD-183-1(1017)  
LOCATION: ON US-183, ALMA SOUTH.  
COUNTIES: HARLAN

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on November 13, 2003 . At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BRIDGES BITUMINOUS

Length: 7 MILES  
START DATE 09/20/2004 WORKING DAYS 20  
Price Range \$ 500,000 to \$ 1,000,000

Plans and specifications may be seen beginning October 21, 2003 at the Lincoln Central Office and October 27, 2003 at the District Engineer's Office at MCCOOK  
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

NOTICE TO BIDDERS

To be eligible for the award of this contract, bidders shall submit a completed bidding proposal for both Call Order No. F34, {Project No. BR-S31C(102)} and Call Order No. N37, {Project No. RD-183-1(1017)}.

Award of Contract, if awarded, will be made on the combined bid for both contracts.  
Separate contracts will be awarded for each Call Order Number.  
Please order plans and proposals accordingly.

PLANS (NOT INCLUDING STANDARDS)	5 SHEETS	\$ 1.00
STANDARD PLANS	2 SHEETS	\$ .40

SHEET NO.	
1	TITLE PAGE & SUMMARY OF QUANTITIES
2T	TYPICAL CROSS SECTIONS
3	TRAFFIC CONTROL PLAN
4	PERMANENT PAVEMENT MARKING PLAN
5	TEMPORARY PAVEMENT MARKING PLAN

STANDARD PLANS

920-R5 (2 SHEETS) TRAFFIC CONTROL

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE III	164	BDAY
TEMPORARY SIGN DAY	240	EACH
SIGN DAY	3,116	EACH
OVERLAY BROKEN LINES	733	STA
OVERLAY SOLID LINES	1,466	STA
PERMANENT PAVEMENT MARKING PAINT	91,600	LF
FLAGGING	30	DAY
FURNISHING AND OPERATING PILOT VEHICLE	15	DAY
FIELD OFFICE	1	EACH
MOBILIZATION	LUMP	LUMP
ASPH CONC FOR STATE MAINT PATCHING, TYPE SP4(0.5)	500	TON
ASPH CONCRETE FOR PATCHING, TYPE SP4(0.5)	500	TON
ASPH CONC, TYPE SP4(0.5)	10,870	TON

GROUP 9 BITUMINOUS

PERF GRAD BIND (70-28)FOR ST MAINT PATCH	27	TON
PERF GRADED BINDER (70-28)	613	TON
TACK COAT	14,930	GAL
FOG SEAL	13,490	GAL
RENTAL OF LOADER, FULLY OPERATED	40	HOURL
RENTAL OF MOTOR GRADER, FULLY OPERATED	40	HOURL
RENTAL OF DUMP TRUCK, FULLY OPERATED	40	HOURL
RENTAL OF SKID LOADER, FULLY OPERATED	40	HOURL
COLD MILLING, CLASS 3	373	STA
ASPH PVMT SMOOTHNESS TESTING	LUMP	LUMP