

NOTICE TO CONTRACTORS

CALL ORDER F03
FEDERAL PROJECT NO. BRO-7066(34)
LOCATION: ON A COUNTY ROAD SOUTHEAST OF LORTON
COUNTIES: OTOE

The Nebraska Department of Roads will receive sealed bids for
OTOE COUNTY in Room 104 of the Central Office Building at
1500 Hwy 2 at Lincoln, until 1:30 P.M. on January 29, 2004 .
At that time the bids will be opened and read for
GR CULV

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR
WHO IS QUALIFIED FOR: GRADING CULVERTS
START DATE 08/30/2004 WORKING DAYS 45
Price Range \$ 100,000 to \$ 500,000
THIS PROJECT CONTAINS A DBE GOAL OF 5.0 %

Plans and specifications may be seen beginning January 06, 2004 at the Lincoln
Central Office and January 12, 2004 at the District Engineer's Office at LINCOLN
Additional letting information may be found at the Nebraska Department of Roads
Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal
requirements will apply.

PLANS (NOT INCLUDING STANDARDS)	18 SHEETS	\$ 3.60
STANDARD PLANS	7 SHEETS	\$ 1.40

SHEET NO.

1	TITLE PAGE
2T1	TYPICAL CROSS SECTION & SUMMARY OF QUANTITIES
2N1	INLET STRUCTURE DIMENSIONS
2N2	INLET STRUCTURE REINFORCING
2N3	BILL OF BARS
2N4	COUPLING BAND PLAN
2N5	FOUNDATION DRAIN PLAN
2N6	STILLING BASIN PLAN
2N7	EXCAVATION PLAN
2N8	CATHODIC PROTECTION ON CULVERT
2N9	BARROW SITE
R1	RIGHT-OF-WAY SHEET, SURVEY INFORMATION
3	PLAN & PROFILE
4	CULVERT CROSS SECTION
5 - 7	ROADWAY CROSS SECTIONS
8	BORROW PIT CROSS SECTIONS

STANDARD PLANS

435-R1	(3 SHEETS) MANHOLE
920-R5	(2 SHEETS) TRAFFIC CONTROL
921-R4	TRAFFIC CONTROL
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and
should not be used for bidding purposes. The Department
reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
LARGE TREE REMOVAL		5 EACH
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		88 MGAL
EARTHWORK MEASURED IN EMBANKMENT	33,898	CY
SALVAGING AND PLACING TOPSOIL	8,960	SY
RIPRAP FILTER FABRIC	915	SY
CRUSHED ROCK EMBEDMENT	15	STA
CRUSHED ROCK SURFACE COURSE	386	TON

GROUP 1 GRADING

ROCK RIPRAP, TYPE C	1,610 TON
SEEDING, TYPE A	3 ACRE
SEEDING, TYPE C	2 ACRE
COVER CROP SEEDING	5 ACRE
MULCH	11 TON

GROUP 4 CULVERTS

MOBILIZATION	LUMP	LUMP
CAST IRON RING & COVER		345 LB
MANHOLE		1 EACH
AT STA. 16+00 - 42' RT.		
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL		450 CY
PLUG VALVE		1 EACH
47B-3000 OR AX-3000 CONC FOR BOX CULV		92 CY
RE-STEEL FOR BOX CULVERT	12,450 LB	
96" CORRUGATED METAL PIPE		140 LF
4" PERFORATED P.V.C. PIPE UNDERDRAIN		360 LF
8" P.V.C. SEWER PIPE		575 LF
12" P.V.C. SEWER PIPE		80 LF
REMOVE STRUCTURE		1 EACH
AT STA. 15+55.31		
STEEL SHEET PILING		384 SF
GRANULAR BACKFILL		173 CY

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE III		1,080 BDAY
SIGN DAY		1,440 EACH
CONTRACTOR FURNISHED SIGN DAY		360 EACH
FIELD OFFICE		1 EACH
MOBILIZATION	LUMP	LUMP