

NOTICE TO CONTRACTORS

CALL ORDER F04
 FEDERAL PROJECT NO. STPE-STPB-SRR-3701(1)
 LOCATION: LEWIS & CLARK VISITOR CENTER ACCESS ROAD.
 COUNTIES: OTOE

The Nebraska Department of Roads will receive sealed bids for
 OTOE COUNTY in Room 104 of the Central Office Building at
 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on January 29, 2004 .
 At that time the bids will be opened and read for
 GRAD,CULV,ELEC,BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR
 WHO IS QUALIFIED FOR: GRADING BITUMINOUS

START DATE 05/03/2004 WORKING DAYS 35
 Price Range \$ 500,000 to \$ 1,000,000
 THIS PROJECT CONTAINS A DBE GOAL OF 8.0 %

Plans and specifications may be seen beginning January 06, 2004 at the Lincoln
 Central Office and January 12, 2004 at the District Engineer's Office at LINCOLN
 Additional letting information may be found at the Nebraska Department of Roads
 Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal
 requirements will apply.

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	25	SHEETS	\$ 5.00
CROSS SECTIONS (SHEETS X1 THRU X6)	6	SHEETS	\$ 1.20
STANDARD PLANS	16	SHEETS	\$ 3.20

SHEET NO.

1	TITLE PAGE
2T1-2T2	TYPICAL CROSS SECTIONS
2S	SUMMARY OF QUANTITIES
2N1	GENERAL INFORMATION
2L1-2L2	GEOMETRICS & GRADES
2L3	GEOMETRICS & GRADES & PARKING LOT PAVEMENT MARKING DETAIL
2L4	CONSTRUCTION & REMOVALS
3 - 4	PLAN & PROFILE SHEETS
5 - 8	ROADWAY LIGHTING PLANS
9 - 10	DRAINAGE STRUCTURE CROSS SECTIONS
11	SPECIAL PLAN 1C SILT FENCE DETAILS
12	SPECIAL PLAN 2C EROSION CHECKS (ALL TYPES) & FABRIC SILT CHECKS
13	SPECIAL PLAN 3C SLOPE PROTECTION NETTING
14	SPECIAL PLAN 4C CURB RAMPS
15	TEMPORARY PAVEMENT MARKING PLAN
16	TRAFFIC CONTROL PLAN--LANE CLOSURE (FREEWAY-INTERSTATE) (HIGHWAY N-2)
17	TYPICAL PAVEMENT MARKING PLAN (ACCESS ROAD)
18	TYPICAL PAVEMENT MARKING PLAN WITH PLOWABLE RAISED PAVEMENT MARKERS RURAL EXPRESSWAY (LEFT TURN LANE)
X1 - X6	CROSS SECTIONS

STANDARD PLANS

108-R2	SUPERELEVATION PLAN FOR CONCRETE AND BITUMINOUS SURFACING
301-R8	(3 SHEETS) PAVEMENT DETAILS
329-R5	(4 SHEETS) 6 TO 16 INCH CONCRETE PAVEMENT
410-R3	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
425-R3	COLLARS AND ELBOWS FOR CONCRETE PIPES
914-R3	PULL BOX DETAIL
920-R5	(2 SHEETS) TRAFFIC CONTROL
921-R4	TRAFFIC CONTROL
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

REMOVE CONC PROTECTION BARRIER	400	LF
MOBILIZATION	LUMP	LUMP
LARGE TREE REMOVAL	1	EACH
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)	31,104	CY
WATER	40	MGAL
SALVAGING AND PLACING TOPSOIL	21,800	SY
REMOVE PAVEMENT	1,094	SY
SAWING PAVEMENT	806	LF
ROCK RIPRAP, TYPE B	957	TON
IMPACT ATTENUATOR	1	EACH
REMOVE IMPACT ATTENUATOR	1	EACH
COVER CROP SEEDING	3	ACRE
EROSION CONTROL, TYPE A	12,315	SY
EROSION CHECKS, TYPE A	84	BALE
FABRIC SILT FENCE-HIGH POROSITY	2,319	LF

GROUP 4 CULVERTS

MOBILIZATION	LUMP	LUMP
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL	310	CY
24" REINFORCED CONCRETE PIPE	326	LF
24" CONCRETE FLARED-END SECTION	8	EACH
ROCK RIPRAP, TYPE B	48	TON

GROUP 8B ELECTRICAL

MOBILIZATION	LUMP	LUMP
PULL BOX, TYPE PB-5	1	EACH
ST LIGHT UNIT SL-BT-40-12-0.25	1	EACH
1 1/2" CONDUIT, JACKED	125	LF
1 1/2" CONDUIT IN TRENCH	200	LF
STREET LIGHT CABLE, NO. 6 BARE	570	LF
STREET LIGHT CABLE, NO. 6 USE	1,140	LF
RELOCATE STREET LIGHTING UNIT	1	EACH

GROUP 9 BITUMINOUS

PERMANENT PAVEMENT MARKING PAINT	6,436	LF
MOBILIZATION	LUMP	LUMP
TIE BARS	296	EACH
CONC 47B-3500 BARRIER CURB	417	LF
COMB CONC 47B-3500 CURB & GUTTER	1,286	LF
CONC 47B-3000 SIDEWALKS	616	SY
CONC 47B-3000 MEDIAN SURFACING	407	SY
CONC 47B-3000 IMPRINTED MEDIAN SURF	61	SY
9" CONC PVMT, 47B-3500	891	SY
HANDI SYM PREF PVMT MRKING T-4	3	EACH
24" WHT PREF PVMT MKING T-4	40	LF
FOUNDATION COURSE	10,364	SY
ASPH CONC, TYPE SP4 SPECIAL(0.5)	2,680	TON
PERF GRADED BINDER (64-28)	144	TON
TACK COAT	1,660	GAL
WATER	37	MGAL
EARTH SHOULDER CONSTRUCTION	35	STA
SUBGRADE PREPARATION	9,198	SY
TREE GRATE	8	EACH

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	600	BDAY
BARRICADE, TYPE III	515	BDAY
TEMPORARY SIGN DAY	240	EACH
SIGN DAY	1,320	EACH
CONTRACTOR FURNISHED SIGN DAY	55	EACH
FLASHING ARROW PANEL	20	DAY
FIELD OFFICE	1	EACH
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED	25	HOUR
RENTAL OF BACKHOE, FULLY OPERATED	25	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	25	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	25	HOUR