

NOTICE TO CONTRACTORS

CALL ORDER F09
FEDERAL PROJECT NO. STPD-32-5(105)
LOCATION: N-32, MADISON EAST
COUNTIES: MADISON STANTON

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on January 29, 2004 . At that time the bids will be opened and read for GRAD,SEED,GDRL,BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 3.5 MILES
START DATE 06/28/2004 WORKING DAYS 70
Price Range \$ 1,000,000 to \$ 3,000,000

Plans and specifications may be seen beginning January 06, 2004 at the Lincoln Central Office and January 12, 2004 at the District Engineer's Office at NORFOLK
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

NOTICE TO BIDDERS

To be eligible for the award of this contract, bidders shall submit a completed bidding proposal for both Call Order No. F09, {Project No. STPD-32-5(105)} and Call Order No. N11, {Project No. S-57-3(1008)}.

Award of Contract, if awarded, will be made on the combined bid for both contracts.
Separate contracts will be awarded for each Call Order Number.
Please order plans and proposals accordingly.

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	44 SHEETS	\$ 8.80
CROSS SECTIONS (SHEETS X1 THRU X37)	37 SHEETS	\$ 7.40
STANDARD PLANS	7 SHEETS	\$ 1.40

SHEET NO.

1	TITLE PAGE
2T1-2T5	TYPICAL CROSS SECTIONS
2S1-2S4	SUMMARY OF QUANTITIES
2W1-2W4	WETLANDS
2H	CONTROL POINT TIES
2N	GENERAL INFORMATION
3 - 6	PLAN SHEETS
7	TRAFFIC CONTROL PLAN
8	TEMPORARY PAVEMENT MARKING PLAN
9	PAVEMENT MARKING PLAN
10 - 11	EARTHWORK DATA SHEETS
12 - 15	DRAINAGE STRUCTURE CROSS SECTIONS
16 - 22	SPECIAL PLAN 1C GUARDRAIL PLAN
23 - 25	SPECIAL PLAN 2C 5' X 7' SINGLE SPAN RC BOX CULVERT STA. 127+47.59
26	SPECIAL PLAN 3C MAILBOX TURNOUT
27 - 28	SPECIAL PLAN 4C MAILBOX SUPPORT POST
29	SPECIAL PLAN 5C EROSION CONTROL, TYPE "AAA" (OUTLET TREATMENT)
30	SPECIAL PLAN 6C SILT FENCE DETAILS
X1 - X37	CROSS SECTIONS

STANDARD PLANS

108-R2	SUPERELEVATION PLAN FOR CONCRETE AND BITUMINOUS SURFACING
410-R3	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
501-R3	EROSION CONTROL
901-R8	HIGHWAY DELINEATORS
920-R5	(2 SHEETS) TRAFFIC CONTROL

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		77 MGAL
REMOVE DELINEATOR UNITS		36 EACH
EARTHWORK MEASURED IN EMBANKMENT	5,158	CY
REMOVE ASPHALT SURFACE		424 SY
REMOVE ASPH SURF FROM PAVEMENT		890 SY
24" DRIVEWAY CULVERT PIPE		52 LF
REMOVE FLARED- END SECTION		1 EACH
PREPARATION OF STRUCTURE		1 EACH
AT STA. 127+47.59		
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL		2 CY
EXCAVATION FOR BOX CULVERTS		30 CY
47B-3000 OR AX-3000 CONC FOR BOX CULV		28 CY
RE-STEEL FOR BOX CULVERT	2,428	LB
42" CORRUGATED METAL PIPE		8 LF
42" METAL FLARED-END SECTION		1 EACH
REMOVE GUARDRAIL		675 LF
RENTAL OF LOADER, FULLY OPERATED		20 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED		20 HOUR
RENTAL OF BACKHOE, FULLY OPERATED		20 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED		20 HOUR
EROSION CONTROL	2,011	SY
EROSION CONTROL, TYPE AAA		177 SY
FABRIC SILT FENCE-LOW POROSITY	1,925	LF

GROUP 5 SEEDING

MOBILIZATION	LUMP	LUMP
SEEDING, TYPE B		10 ACRE
EROSION CONTROL, TYPE B	2,224	SY
MULCH		22 TON

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
W-BEAM GUARDRAIL		150 LF
BRIDGE APPROACH SECTIONS		4 EACH
GUARDRAIL END TREATMENT, TYPE II		4 EACH

GROUP 9 BITUMINOUS

MOBILIZATION	LUMP	LUMP
DELINEATOR, TYPE III		36 EACH
CRUSHED ROCK SURFACE COURSE		20 CY
SPEC SURF CRSE FOR MAILBOX TURNOUTS		36 SY
MAILBOX POST		2 EACH
CONC PVMT REPAIR TYPE A FULL DEPTH		34 SY
CONC PVMT REPAIR TYPE B FULL DEPTH		423 SY
CONC PVMT REPAIR TYPE C FULL DEPTH	3,195	SY
BITUMINOUS PATCHING		8 TON
CONC PVMT, PR-3500		22 SY
JOINT REPAIR		
STOP AHEAD SYMBOL		1 EACH
ASPH CONC, TYPE SP4(0.5)	17,670	TON
PLACE ASPH CONC FOR DRIVE & INTER		561 SY
PERF GRADED BINDER (64-28)		954 TON
PREP OF INTER & DRIVE		256 SY
TACK COAT	15,620	GAL
WATER		93 MGAL
EARTH SHOULDER CONSTRUCTION		370 STA
TRENCHED WIDENING		370 STA
MILLING CONC FOR INLAYS		4 EACH

GROUP 9 BITUMINOUS

SURFACE UNDER GUARDRAIL	449	SY
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	16,250	BDAY
BARRICADE, TYPE III	860	BDAY
TEMPORARY SIGN DAY	720	EACH
SIGN DAY	4,255	EACH
OVERLAY BROKEN LINES	366	STA
OVERLAY SOLID LINES	732	STA
FLAGGING	100	DAY
FURNISHING AND OPERATING PILOT VEHICLE	45	DAY
FIELD OFFICE	1	EACH
MOBILIZATION	LUMP	LUMP