

NOTICE TO CONTRACTORS

CALL ORDER F10
 FEDERAL PROJECT NO. BRO-7002(5)
 LOCATION: ON A COUNTY ROAD NORTH OF BRUNSWICK
 COUNTIES: ANTELOPE

The Nebraska Department of Roads will receive sealed bids for ANTELOPE COUNTY in Room 104 of the Central Office Building at 1500 Hwy 2 at Lincoln, until 1:30 P.M. on January 29, 2004. At that time the bids will be opened and read for CULVERT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: CULVERTS

START DATE 08/23/2004 WORKING DAYS 35
 Price Range \$ 100,000 to \$ 500,000

Plans and specifications may be seen beginning January 06, 2004 at the Lincoln Central Office and January 12, 2004 at the District Engineer's Office at NORFOLK. Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	7 SHEETS	\$ 1.40
CROSS SECTIONS (SHEETS X1 THRU X6)	6 SHEETS	\$ 1.20
STANDARD PLANS	11 SHEETS	\$ 2.20

SHEET NO.

1	TITLE PAGE
2T	TYPICAL CROSS SECTION
3	PLAN & PROFILE
4	DRAINAGE STRUCTURE CROSS SECTIONS
5 - 6	SPECIAL PLAN 1C 10' X 8' QUADRUPLE SPAN RC BOX CULVERT STA. 15+00.00
R1	RIGHT-OF-WAY SHEET
X1 - X6	CROSS SECTIONS

STANDARD PLANS

301-R8	(3 SHEETS) PAVEMENT DETAILS
329-R5	(4 SHEETS) 6 TO 16 INCH CONCRETE PAVEMENT
920-R5	(2 SHEETS) TRAFFIC CONTROL
921-R4	TRAFFIC CONTROL
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 4 CONCRETE BOX CULVERT AT STA. 15+00

BARRICADE, TYPE III	828	BDAY
SIGN DAY	1,104	EACH
CONTRACTOR FURNISHED SIGN DAY	138	EACH
MOBILIZATION	LUMP	LUMP
LARGE TREE REMOVAL	1	EACH
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)	645	CY
WATER	7	MGAL
REMOVE ASPHALT SURFACE	374	SY
7" CONC PVMT 47B-3500	444	SY
EXCAVATION FOR BOX CULVERTS	549	CY

GROUP 4 CONCRETE BOX CULVERT AT STA. 15+00

47B-3000 OR AX-3000 CONC FOR BOX CULV	208 CY
RE-STEEL FOR BOX CULVERT	22,759 LB
REMOVE STRUCTURE	1 EACH
AT STA. 14+99	
EARTH SHOULDER CONSTRUCTION	4 STA
SUBGRADE PREPARATION	444 SY
COVER CROP SEEDING	1 ACRE