

NOTICE TO CONTRACTORS

CALL ORDER F21
 FEDERAL PROJECT NO. BRO-7047(11)
 LOCATION: ON A COUNTY ROAD NORTHWEST OF ELBA
 COUNTIES: HOWARD

The Nebraska Department of Roads will receive sealed bids for HOWARD COUNTY in Room 104 of the Central Office Building at 1500 Hwy 2 at Lincoln, until 1:30 P.M. on January 29, 2004 . At that time the bids will be opened and read for BRIDGE

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BRIDGES
 START DATE 08/02/2004 WORKING DAYS 65
 Price Range \$ 100,000 to \$ 500,000

Plans and specifications may be seen beginning January 06, 2004 at the Lincoln Central Office and January 12, 2004 at the District Engineer's Office at GRAND ISLAND
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.
 This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

PLANS (NOT INCLUDING STANDARDS)	21	SHEETS	\$ 4.20
STANDARD PLANS	4	SHEETS	\$.80

SHEET NO.

1	TITLE PAGE
2T	TYPICAL CROSS SECTION OF IMPROVEMENT & SUMMARY OF QUANTITIES
3	PLAN & PROFILE
4 - 6	CROSS SECTIONS
7 - 13	SPECIAL PLAN 1 DOUBLE TEE BEAM BRIDGE STA. 44+10.00
14 - 20	SPECIAL PLAN 1C GUARDRAIL PLAN
21	RIGHT-OF-WAY

STANDARD PLANS

920-R5	(2 SHEETS) TRAFFIC CONTROL
921-R4	TRAFFIC CONTROL
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 6 BRIDGE AT STA. 44+10.00

BARRICADE, TYPE III	1,416	B DAY
SIGN DAY	1,652	EACH
CONTRACTOR FURNISHED SIGN DAY	472	EACH
MOBILIZATION	LUMP	LUMP
LARGE TREE REMOVAL	1	EACH
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)	1,000	CY
WATER	25	MGAL
EARTHWORK MEASURED IN EMBANKMENT	3,535	CY
SALVAGING AND PLACING TOPSOIL	7,100	SY
GRAVEL SURFACE COURSE	170	CY
ABUTMENT NO.1 EXCAVATION	LUMP	LUMP
ABUTMENT NO.2 EXCAVATION	LUMP	LUMP
BENT NO.1 EXCAVATION	LUMP	LUMP
BENT NO.2 EXCAVATION	LUMP	LUMP
47B-3000 CONC FOR BRIDGE	177	CY
47BD-4000 CONC FOR BRIDGE	91	CY

GROUP 6 BRIDGE AT STA. 44+10.00

	LUMP	LUMP
PRECAST/PRESTRESSED CONC SUPERSTR AT STA. 44+10.00		
RE-STEEL FOR BRIDGE	22,460	LB
REMOVE STRUCTURE AT STA. 44+32 LT.		1 EACH
STRUC STEEL FOR SUBSTRUCTURE	1,810	LB
ROCK RIPRAP, TYPE B	525	TON
HP 12"X53# STEEL PILING	1,450	LF
STEEL SHEET PILING	2,420	SF
BRIDGE APPROACH SECTIONS	4	EACH
MELT	4	EACH
SEEDING, TYPE A	2	ACRE
COVER CROP SEEDING	2	ACRE
MULCH	5	TON