

NOTICE TO CONTRACTORS

CALL ORDER F22
 FEDERAL PROJECT NO. STPD-BR-39-2(105)
 LOCATION: N-39, SOUTH OF SILVER CREEK.
 COUNTIES: MERRICK POLK

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on January 29, 2004 . At that time the bids will be opened and read for GR CULV SEED BR GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 9.8 MILES
 START DATE 03/29/2004 WORKING DAYS 135
 Price Range \$ 1,000,000 to \$ 3,000,000
 THIS PROJECT CONTAINS A DBE GOAL OF 3.0 %

Plans and specifications may be seen beginning January 06, 2004 at the Lincoln Central Office and January 12, 2004 at the District Engineer's Office at GRAND ISLAND

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	119	SHEETS	\$ 23.80
CROSS SECTIONS (SHEETS X1 THRU X100)	100	SHEETS	\$ 20.00
STANDARD PLANS	17	SHEETS	\$ 3.40

SHEET NO.

1	TITLE PAGE
2T1-2T5	TYPICAL CROSS SECTIONS
2S1-2S4	SUMMARY OF QUANTITIES & DETOUR LOCATION MAP
2W1-2W9	WETLANDS
2H1-2H5	HORIZONTAL ALIGNMENT & CONTROL POINTS
2N	GENERAL INFORMATION
2P1-2P2	PHASING PLANS--GEOMETRICS
2L	LARGE SCALE PLAN SHEET
3 - 12	PLAN SHEETS
13 - 16	PLAN & PROFILE SHEET
17	TRAFFIC CONTROL PLAN
18	TYPICAL TRAFFIC CONTROL PLAN--PHASE I
19	TRAFFIC CONTROL PLAN--BRIDGE CURB REPAIR
20	TYPICAL TRAFFIC SIGNAL CONTROL PLAN FOR ONE LANE, TWO WAY OPERATION
21	TYPICAL YIELD CONTROL FOR LOW VOLUME, ONE LANE, TWO WAY OPERATION
22 - 23	TRAFFIC SIGNAL PLAN
24	TEMPORARY PAVEMENT MARKING PLAN
25 - 30	EARTHWORK DATA SHEETS
31 - 43	DRAINAGE STRUCTURE CROSS SECTIONS
44 - 60	SPECIAL PLAN 1 PRESTRESSED INVERTED TEE BRIDGE STA. 699+75.00
61 - 64	SPECIAL PLAN 1C BEDDING & BACKFILL REQUIREMENTS FOR CONCRETE PIPE, MCCMP, PCCMP, & PLASTIC PIPE
65 - 66	SPECIAL PLAN 2C 12' X 7' QUADRUPLE SPAN RC BOX CULVERT STA. 621+59.00
67 - 68	SPECIAL PLAN 3C 6' X 4' TWIN SPAN RC BOX CULVERT STA. 702+60.00
69 - 70	SPECIAL PLAN 4C 6' X 5' TWIN SPAN RC BOX CULVERT STA. 706+77.00
71	SPECIAL PLAN 5C CONCRETE APRON

72 - 73 SPECIAL PLAN 6C REMODEL BRIDGE RAIL
 STA. 799+03.46
 74 - 81 SPECIAL PLAN 7C GUARDRAIL PLAN
 82 SPECIAL PLAN 8C SILT FENCE DETAILS
 83 SPECIAL PLAN 9C EROSION CHECKS (ALL TYPES)
 & FABRIC SILT CHECKS
 84 - 85 SPECIAL PLAN 10C MAILBOX SUPPORT POST
 86 SPECIAL PLAN 11C MAILBOX TURNOUT
 R1 - R7 RIGHT-OF-WAY SHEETS
 X1 - X100 CROSS SECTIONS

STANDARD PLANS

108-R2 SUPERELEVATION PLAN FOR CONCRETE AND
 BITUMINOUS SURFACING
 301-R8 (3 SHEETS) PAVEMENT DETAILS
 410-R3 (2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
 501-R3 EROSION CONTROL
 617-R3 (2 SHEETS) CONCRETE PILING
 804 PRECAST CONCRETE R.O.W. MARKER
 901-R8 HIGHWAY DELINEATORS
 920-R5 (2 SHEETS) TRAFFIC CONTROL
 921-R4 TRAFFIC CONTROL
 923 TRAFFIC CONTROL--ROAD CLOSURE
 1204 (2 SHEETS) REINFORCED CONCRETE BOX CULVERTS
 TWIN SPAN WITH 4-FOOT RISE

Quantities shown herein are FOR INFORMATION ONLY and
 should not be used for bidding purposes. The Department
 reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
LARGE TREE REMOVAL		44 EACH
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		180 MGAL
RIGHT-OF-WAY MARKERS		10 EACH
EARTHWORK MEASURED IN EMBANKMENT	11,970	CY
REMOVE PAVEMENT		512 SY
REMOVE ASPHALT SURFACE		2,111 SY
REMOVE GUARDRAIL		2,962 LF
EROSION CONTROL		9,106 SY
EROSION CONTROL, TYPE HV		910 SY
EROSION CHECKS, TYPE HV		24 BALE
FABRIC SILT FENCE-LOW POROSITY		4,090 LF

GROUP 4 CULVERT

MOBILIZATION	LUMP	LUMP
RIPRAP FILTER FABRIC		17 SY
PRECAST REINF CONC BOX CULVERT 6' X 5'		132 LF
PRECAST REINF CONC BOX CULVERT 6' X 4'		156 LF
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL		19 CY
EXCAVATION FOR BOX CULVERTS		611 CY
TEMPORARY SHORING	LUMP	LUMP
AT STA. 592+05		
TEMPORARY SHORING	LUMP	LUMP
AT STA. 642+65		
TEMPORARY SHORING	LUMP	LUMP
AT STA. 742+73		
47B-3000 OR AX-3000 CONC FOR BOX CULV		381 CY
RE-STEEL FOR BOX CULVERT	41,057	LB
24" FLARED-END SECTION		2 EACH
REMOVE STRUCTURE		1 EACH
AT STA. 592+05		
REMOVE STRUCTURE		1 EACH
AT STA. 642+65		

REMOVE STRUCTURE		1 EACH
AT STA. 706+72		
REMOVE STRUCTURE		1 EACH
AT STA. 742+73		
REMOVE STRUCTURE		1 EACH
AT STA. 702+73		
BROKEN CONCRETE RIPRAP		8 TON
24" CULV PIPE 2,4,5,7,8		52 LF

GROUP 4A CULVERT AT STA. 621+59

MOBILIZATION	LUMP	LUMP
EXCAVATION FOR BOX CULVERTS		381 CY
TEMPORARY SHORING	LUMP	LUMP
AT STA. 621+59		
47B-3000 OR AX-3000 CONC FOR BOX CULV		334 CY
RE-STEEL FOR BOX CULVERT		42,744 LB
REMOVE STRUCTURE		1 EACH
AT STA. 621+59		

GROUP 5 SEEDING

MOBILIZATION	LUMP	LUMP
SEEDING, TYPE B		28 ACRE
MULCH		63 TON

GROUP 6 BRIDGE AT STA. 699+75

MOBILIZATION	LUMP	LUMP
RIPRAP FILTER FABRIC		150 SY
CONC FOR PVMT APPROACHES CLASS 47BD-4000		189 CY
EPOXY COATED RE-STEEL FOR PVMT APPROACH		20,990 LB
ABUTMENT NO.1 EXCAVATION	LUMP	LUMP
ABUTMENT NO.2 EXCAVATION	LUMP	LUMP
47B-3000 CONC FOR BRIDGE		74 CY
47BD-4000 CONC FOR BRIDGE		97 CY
PRECAST/PRESTRESSED CONC SUPERSTR	LUMP	LUMP
AT STA. 699+75		
REMOVE STRUCTURE		1 EACH
AT STA. 699+68		
STRUC STEEL FOR SUBSTRUCTURE		2,320 LB
BROKEN CONCRETE RIPRAP		180 TON
EPOXY COATED RE-STEEL		34,440 LB
CONCRETE PILING		1,810 LF
STEEL SHEET PILING		3,451 SF
TEMP BRIDGE SHORING	LUMP	LUMP
GRANULAR BACKFILL		140 CY

GROUP 6A BRIDGE AT STA. 799+03.46

MOBILIZATION	LUMP	LUMP
47BD-4000 CONC FOR BRIDGE		81 CY
RE-STEEL FOR BRIDGE		10,885 LB
PREP BRIDGE		1 EACH
AT STA. 799+03.46		
STRUC STEEL FOR BRIDGE RAIL		3,295 LB

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
W-BEAM GUARDRAIL		25 LF
BRIDGE APPROACH SECTIONS		8 EACH
GUARDRAIL END TREATMENT, TYPE II		8 EACH

GROUP 9 BITUMINOUS

OVERLAY BROKEN LINES		1,509 STA
OVERLAY SOLID LINES		3,018 STA
MOBILIZATION	LUMP	LUMP
DELINEATOR, TYPE III		53 EACH

INSTALL CHEVRONS	24	EACH
GRAVEL SURFACE COURSE	414	CY
CLAY SURFACE COURSE	136	CY
GRAVEL EMBEDMENT	3	STA
SPEC SURF CRSE FOR MAILBOX TURNOUTS	276	SY
MAILBOX POST	15	EACH
CONCRETE 47B-3500 MEDIAN CURB	225	LF
CONC 47B-3000 MEDIAN SURFACING	60	SY
CONCRETE CLASS 47B-3500 ISLAND NOSE	1	EACH
BIT FOUNDATION COURSE 4"	963	SY
ASPH CONC FOR STATE MAINT PATCHING, TYPE SPS	1,000	TON
ASPH CONCRETE FOR PATCHING, TYPE SP4 SPECIAL(0.5)	500	TON
ASPH CONC, TYPE SPS	5,300	TON
ASPH CONC, TYPE SP4 SPECIAL(0.5)	36,460	TON
PLACE ASPH CONC FOR DRIVE & INTER	4,275	SY
PERF GRAD BIND (58-28)FOR ST MAINT PATCH	54	TON
PERF GRADED BINDER (64-22)	1,995	TON
PERF GRADED BINDER (58-28)	286	TON
PREP OF INTER & DRIVE	537	SY
TACK COAT	37,640	GAL
RENTAL OF LOADER, FULLY OPERATED	90	HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	50	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	90	HOUR
RENTAL OF BACKHOE, FULLY OPERATED	40	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	90	HOUR
WATER	273	MGAL
EARTH SHOULDER CONSTRUCTION	985	STA
SUBGRADE PREPARATION	8,974	SY
COLD MILLING, CLASS 3	492	STA
SURFACE UNDER GUARDRAIL	383	SY
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	19,588	BDAY
BARRICADE, TYPE III	4,932	BDAY
TEMPORARY SIGN DAY	720	EACH
SIGN DAY	21,546	EACH
CONTRACTOR FURNISHED SIGN DAY	204	EACH
PAVEMENT MARKING REMOVAL	4,450	LF
TEMP PVMT MARKING, TYPE II	16,000	LF
TEMP PVMT MARKING SURF PREP	7,500	LF
FLAGGING	154	DAY
FURNISHING AND OPERATING PILOT VEHICLE	35	DAY
CONCRETE PROTECTION BARRIER	1,480	LF
RELOCATE CONC PROTECTION BARRIER	2,090	LF
TEMPORARY RUMBLE STRIP	4	EACH
TEMPORARY TRAFFIC SIGNAL	1	EACH
TRAFFIC CONTROL MANAGEMENT	240	DAY
FIELD OFFICE	1	EACH
TRAINING	1,000	HOUR
MOBILIZATION	LUMP	LUMP
IMPACT ATTENUATOR	1	EACH