

NOTICE TO CONTRACTORS

CALL ORDER N02

STATE PROJECT NO. S-33-6(1011)
 LOCATION: ON N-33, CRETE - DORCHESTER.
 COUNTIES: LANCASTER SALINE

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on January 29, 2004 . At that time the bids will be opened and read for GR CULV SEED GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 13 MILES
 START DATE 04/05/2004 WORKING DAYS 135
 Price Range \$ 3,000,000 to \$ 6,000,000

Plans and specifications may be seen beginning January 06, 2004 at the Lincoln Central Office and January 12, 2004 at the District Engineer's Office at LINCOLN
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	98 SHEETS	\$ 19.60
CROSS SECTIONS (SHEETS X1 THRU X98)	98 SHEETS	\$ 19.60
STANDARD PLANS	22 SHEETS	\$ 4.40

SHEET NO.

1	TITLE PAGE
2	INDEX OF SHEETS
2T1-2T10	TYPICAL CROSS SECTIONS
2S1-2S11	SUMMARY OF QUANTITIES
2W1-2W16	WETLANDS
2H1-2H5	CONTROL POINT TIES
2N	GENERAL INFORMATION
2L1-2L4	LARGE SCALE PLAN SHEETS
2L5	GRADES
3 - 15	PLAN SHEETS
16	TRAFFIC CONTROL PLAN
17 - 18	PAVEMENT MARKING PLAN
19	PAVEMENT MARKING DETAILS
20	TEMPORARY PAVEMENT MARKING PLAN
21 - 27	EARTHWORK DATA SHEETS
28 - 32	DRAINAGE STRUCTURE CROSS SECTIONS
33 - 34	SPECIAL PLAN 1C 6' X 6' SINGLE SPAN RC BOX CULVERT STA. 264+68.90
35 - 37	SPECIAL PLAN 2C 12' X 10' TWIN SPAN RC BOX CULVERT STA. 462+17.90
38 - 39	SPECIAL PLAN 3C 10' X 8' TRIPLE SPAN RC BOX CULVERT STA. 488+78.80
40 - 41	SPECIAL PLAN 4C AREA INLET W/GRATE STA. 548+93.50
42 - 46	SPECIAL PLAN 5C GUARDRAIL PLAN
47 - 48	SPECIAL PLAN 6C MAILBOX SUPPORT POST
49	SPECIAL PLAN 7C EROSION CHECKS (ALL TYPES) & FABRIC SILT CHECKS
50	SPECIAL PLAN 8C CURB RAMPS
X1 - X98	CROSS SECTIONS

STANDARD PLANS

108-R2	SUPERELEVATION PLAN FOR CONCRETE AND BITUMINOUS SURFACING
301-R8	(3 SHEETS) PAVEMENT DETAILS
329-R5	(4 SHEETS) 6 TO 16 INCH CONCRETE PAVEMENT

STANDARD PLANS

403-R2 (2 SHEETS) BENDS AND BREAKS FOR CONCRETE
BOX CULVERTS
410-R3 (2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
428-R2 CONCRETE PLUGS AND FIELD PIPE TAP DETAILS
501-R3 EROSION CONTROL
901-R8 HIGHWAY DELINEATORS
920-R5 (2 SHEETS) TRAFFIC CONTROL
921-R4 TRAFFIC CONTROL
1106 (2 SHEETS) REINFORCED CONCRETE BOX CULVERTS
SINGLE SPAN WITH 6-FOOT RISE
1306 (2 SHEETS) REINFORCED CONCRETE BOX CULVERTS
TRIPLE SPAN WITH 6-FOOT RISE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		170 MGAL
REMOVE DELINEATOR UNITS		140 EACH
EARTHWORK MEASURED IN EMBANKMENT	11,225	CY
REMOVE PAVEMENT	1,338	SY
SAWING PAVEMENT	380	LF
REMOVE ASPHALT SURFACE	9,041	SY
REMOVE WALK	19	SY
REMOVE CURB	3,563	LF
REMOVE CONCRETE MEDIAN SURFACING	860	SY
REMOVE CONCRETE DITCH LINER	789	SY
REMOVE & SALVAGE GUARDRAIL	1,000	LF
EROSION CONTROL, TYPE HV	7,446	SY
EROSION CHECKS, TYPE HV	40	BALE

GROUP 4 CULVERTS

MOBILIZATION	LUMP	LUMP
ABANDON INLET		1 EACH
CAST IRON COVER, GRATE & FRAME	925	LB
REMOVE HEADWALLS FROM CULV	2	EACH
PREPARATION OF STRUCTURE	1	EACH
AT STA. 264+68.9		
PREPARATION OF STRUCTURE	1	EACH
AT STA. 410+13.5		
PREPARATION OF STRUCTURE	1	EACH
AT STA. 1252+24.1		
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL	1	CY
EXCAVATION FOR BOX CULVERTS	103	CY
47B-3000 OR AX-3000 CONC FOR BOX CULV	51	CY
47B-3000 CONC FOR INLET & JUNCTION BOXES	2	CY
47B-3000 OR AX-3000 CONC FOR PIPE PLUG	1	CY
RE-STEEL FOR BOX CULVERT	4,417	LB
RE-STEEL FOR INLET & JCT BOX	246	LB
36" CORRUGATED METAL PIPE	20	LF
36" METAL FLARED-END SECTION	1	EACH

GROUP 4A CULVERT AT STA. 462+17.9

MOBILIZATION	LUMP	LUMP
RIPRAP FILTER FABRIC	376	SY
PREPARATION OF STRUCTURE	1	EACH
AT STA. 462+17.9		
EXCAVATION FOR BOX CULVERTS	63	CY
47B-3000 OR AX-3000 CONC FOR BOX CULV	78	CY
RE-STEEL FOR BOX CULVERT	6,479	LB
BROKEN CONCRETE RIPRAP	30	TON
STEEL SHEET PILING	585	SF

GROUP 4B CULVERT AT STA. 488+78.8

MOBILIZATION	LUMP	LUMP
PREPARATION OF STRUCTURE AT STA. 488+78.8		1 EACH
EXCAVATION FOR BOX CULVERTS		90 CY
47B-3000 OR AX-3000 CONC FOR BOX CULV		89 CY
RE-STEEL FOR BOX CULVERT		8,532 LB

GROUP 5 SEEDING

MOBILIZATION	LUMP	LUMP
SEEDING, TYPE B		36 ACRE
MULCH		81 TON

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
W-BEAM GUARDRAIL		237 LF
GUARDRAIL END TREATMENT, TYPE II		4 EACH

GROUP 9 BITUMINOUS

OVERLAY BROKEN LINES		1,368 STA
OVERLAY SOLID LINES		2,680 STA
MOBILIZATION	LUMP	LUMP
DELINEATOR, TYPE III		143 EACH
INSTALL CHEVRONS		32 EACH
REMOVE ASPH SURF FROM PAVEMENT		1,144 SY
CRUSHED ROCK SURFACE COURSE		515 TON
MAILBOX POST		6 EACH
TIE BARS		3,465 EACH
COMB CONC 47B-3500 CURB & GUTTER		7 LF
CONC 47B-3000 SIDEWALKS		30 SY
8" CONCRETE BASE COURSE		18,470 SY
CONC PVMT REPAIR TYPE A FULL DEPTH		85 SY
CONC PVMT REPAIR TYPE B FULL DEPTH		901 SY
CONC PVMT REPAIR TYPE C FULL DEPTH		2,466 SY
CONC PVMT REPAIR TYPE A PARTIAL DEPTH		33 SY
BITUMINOUS PATCHING		89 TON
8" CONC PVMT, 47B-3500		219 SY
CONC PVMT, PR-3500		811 SY
JOINT REPAIR		
ADJUST MANHOLE TO GRADE		5 EACH
4" WHT PREF PVMT MRKING T-4		550 LF
4" YEL PREF PVMT MRKING T-4		12,150 LF
12" WHT PREF PVMT MRKING T-4		180 LF
12" YEL PREF PVMT MRKING T-4		1,750 LF
24" WHT PREF PVMT MKING T-4		100 LF
RR XING SYMBOL PREFORMED PVMT MRKING T-4		5 EACH
ASPH CONC FOR STATE MAINT PATCHING, TYPE SPS		500 TON
ASPH CONCRETE FOR PATCHING, TYPE SPS		500 TON
ASPH CONC, TYPE SPS		28,790 TON
ASPH CONC, TYPE SP4(0.5)		44,320 TON
PLACE ASPH CONC FOR DRIVE & INTER		13,014 SY
PERF GRAD BIND (58-28)FOR ST MAINT PATCH		27 TON
PERF GRADED BINDER (58-28)		1,571 TON
PERF GRADED BINDER (64-28)		2,393 TON
TACK COAT		65,480 GAL
RENTAL OF LOADER, FULLY OPERATED		60 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED		60 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED		60 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED		60 HOUR
WATER		396 MGAL
EARTH SHOULDER CONSTRUCTION		1,358 STA
SUBGRADE PREPARATION		18,689 SY
MILLING CONC FOR INLAYS		26 EACH

GROUP 9 BITUMINOUS

SURFACE UNDER GUARDRAIL	619 SY
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP LUMP

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	47,360 BDAY
BARRICADE, TYPE III	1,620 BDAY
TEMPORARY SIGN DAY	1,824 EACH
SIGN DAY	17,987 EACH
FLAGGING	144 DAY
FURNISHING AND OPERATING PILOT VEHICLE	72 DAY
FIELD OFFICE	1 EACH
MOBILIZATION	LUMP LUMP