

NOTICE TO CONTRACTORS

CALL ORDER N12
 STATE PROJECT NO. S-81-4(1017)
 LOCATION: ON US-81, N-13 TO SOUTH JCT. N-98.
 COUNTIES: PIERCE

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on January 29, 2004 . At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 6.9 MILES
 START DATE 08/02/2004 WORKING DAYS 50
 Price Range \$ 1,000,000 to \$ 3,000,000

Plans and specifications may be seen beginning January 06, 2004 at the Lincoln Central Office and January 12, 2004 at the District Engineer's Office at NORFOLK
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

PLANS (NOT INCLUDING STANDARDS)	10 SHEETS	\$2.00
STANDARD PLANS	2 SHEETS	\$.40

SHEET NO.	
1	TITLE PAGE
2T1-2T3	TYPICAL CROSS SECTIONS
2S1-2S3	SUMMARY OF QUANTITIES & TYPICAL CROSS SECTIONS
2N	GENERAL INFORMATION
3	TRAFFIC CONTROL PLAN
4	TEMPORARY PAVEMENT MARKING PLAN

STANDARD PLANS
 920-R5 (2 SHEETS) TRAFFIC CONTROL

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	850	B DAY
BARRICADE, TYPE III	360	B DAY
TEMPORARY SIGN DAY	762	EACH
SIGN DAY	5,280	EACH
OVERLAY BROKEN LINES	1,100	STA
OVERLAY SOLID LINES	2,200	STA
FLAGGING	100	DAY
FURNISHING AND OPERATING PILOT VEHICLE	50	DAY
FIELD OFFICE	1	EACH
MOBILIZATION	LUMP	LUMP
CONC PVMT REPAIR TYPE A FULL DEPTH	107	SY
CONC PVMT REPAIR TYPE B FULL DEPTH	196	SY
CONC PVMT REPAIR TYPE C FULL DEPTH	292	SY
CONC PVMT, PR-3500	220	SY
JOINT REPAIR		
ASPH CONC FOR STATE MAINT PATCHING, TYPE TYPE SPS	500	TON
ASPH CONCRETE FOR PATCHING, TYPE SPS	100	TON
ASPH CONC, TYPE SPS	5,500	TON
ASPH CONC, TYPE SP4(0.375)	16,210	TON
PERF GRAD BIND (58-28)FOR ST MAINT PATCH	27	TON
PERF GRADED BINDER (58-28)	307	TON
PERF GRADED BINDER (64-28)	875	TON
TACK COAT	29,430	GAL

GROUP 9 BITUMINOUS

RENTAL OF LOADER, FULLY OPERATED	35	HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	35	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	35	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	35	HOUR
COLD MILLING, CLASS 3	733	STA
RUMBLE STRIPS, ASPHALT	733	STA
CONC SURF MILLING	98,293	SY
NON-WOVEN PVMT OVERLAY FABRIC	98,293	SY
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP