

NOTICE TO CONTRACTORS

CALL ORDER N25

STATE PROJECT NO. RD-30-5(1036)

LOCATION: ON US-30, HALL/MERRICK COUNTY LINE - CHAPMAN.

COUNTIES: MERRICK

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on January 29, 2004 . At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 7.8 MILES

START DATE 06/01/2004 WORKING DAYS 75

Price Range \$ 1,000,000 to \$ 3,000,000

Plans and specifications may be seen beginning January 06, 2004 at the Lincoln Central Office and January 12, 2004 at the District Engineer's Office at GRAND ISLAND

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	27 SHEETS	\$ 5.40
CROSS SECTIONS (SHEETS X1 THRU X11)	11 SHEETS	\$ 2.20
STANDARD PLANS	4 SHEETS	\$.80

SHEET NO.

1	TITLE PAGE
2T1-2T5	TYPICAL CROSS SECTIONS
2S1-2S3	SUMMARY OF QUANTITIES
2N	GENERAL INFORMATION
3 - 10	PLAN SHEETS
11	TRAFFIC CONTROL PLAN
12	TYPICAL PAVEMENT MARKING PLAN
13	PAVEMENT MARKING PLAN
14	TEMPORARY PAVEMENT MARKING PLAN
15	EARTHWORK DATA SHEET
16	DRAINAGE STRUCTURE CROSS SECTIONS
17	SPECIAL PLAN 1C CONCRETE HEADWALL
18 - 19	SPECIAL PLAN 2C MAILBOX SUPPORT POST
X1 - X11	CROSS SECTIONS

STANDARD PLANS

901-R8	HIGHWAY DELINEATORS
920-R5	(2 SHEETS) TRAFFIC CONTROL
921-R4	TRAFFIC CONTROL

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	7,040	B DAY
BARRICADE, TYPE III	496	B DAY
TEMPORARY SIGN DAY	906	EACH
SIGN DAY	8,074	EACH
OVERLAY BROKEN LINES	1,233	STA
OVERLAY SOLID LINES	2,467	STA
FLAGGING	134	DAY
FURNISHING AND OPERATING PILOT VEHICLE	67	DAY
FIELD OFFICE	1	EACH
MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER	28	MGAL
DELINEATOR, TYPE III	15	EACH

GROUP 9 BITUMINOUS

EARTHWORK MEASURED IN EMBANKMENT	589	CY
REMOVE PAVEMENT	2,179	SY
GRAVEL SURFACE COURSE	25	CY
MAILBOX POST	4	EACH
CONC PVMT REPAIR TYPE A FULL DEPTH	6	SY
CONC PVMT REPAIR TYPE B FULL DEPTH	84	SY
CONC PVMT REPAIR TYPE C FULL DEPTH	871	SY
CONC PVMT, PR-3500	710	SY
JOINT REPAIR		
REMOVE & SALVAGE FES	2	EACH
REMOVE HEADWALLS FROM CULV	1	EACH
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL	9	CY
47B-3000 OR AX-3000 CONC FOR HDWL	1	CY
RE-STEEL FOR HEADWALL	102	LB
24" CORRUGATED METAL PIPE	39	LF
INSTALL 24" METAL F.E.S.	2	EACH
4" WHT PREF PVMT MRKING T-4	380	LF
4" YEL PREF PVMT MRKING T-4	7,000	LF
12" YEL PREF PVMT MRKING T-4	550	LF
HYDRATED LIME	356	TON
HYDRATED LIME SLURRY STABILIZATION	412	STA
ASPH CONC FOR STATE MAINT PATCHING, TYPE SP5(0.375)	200	TON
ASPH CONCRETE FOR PATCHING, TYPE SP5(0.375)	50	TON
ASPH CONC, TYPE SPS	8,370	TON
ASPH CONC, TYPE SP5(0.375)	17,970	TON
PLACE ASPH CONC FOR DRIVE & INTER	1,470	SY
PERF GRAD BIND (64-28)FOR ST MAINT PATCH	12	TON
PERF GRADED BINDER (58-28)	457	TON
PERF GRADED BINDER (64-28)	1,153	TON
PREP OF INTER & DRIVE	486	SY
EMUL ASPH FOR HYDRATE LIME STABILIZATION	127,250	GAL
TACK COAT	37,090	GAL
RENTAL OF LOADER, FULLY OPERATED	80	HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	80	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	80	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	80	HOUR
EARTH SHOULDER CONSTRUCTION	19	STA
SUBGRADE PREPARATION	2,845	SY
COLD MILLING, CLASS 3	412	STA
COLD MILLING, CLASS 3	71,534	SY
TYPE A		
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP
SEEDING, TYPE B	23	ACRE
MULCH	52	TON