

NOTICE TO CONTRACTORS

CALL ORDER F33  
FEDERAL PROJECT NO. EACSTPD-23-2(119)  
LOCATION: ON N-23, MADRID - ELSIE.  
COUNTIES: PERKINS

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on March 04, 2004 . At that time the bids will be opened and read for GRAD,CULV,SEED,BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 8.3 MILES  
START DATE 06/14/2004 WORKING DAYS 80  
Price Range \$ 1,000,000 to \$ 3,000,000  
THIS PROJECT CONTAINS A DBE GOAL OF 3.0 %

Plans and specifications may be seen beginning February 10, 2004 at the Lincoln Central Office and February 17, 2004 at the District Engineer's Office at MCCOOK  
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

NOTICE TO BIDDERS

To be eligible for the award of this contract, bidders shall submit a completed bidding proposal for Call Order No. F33, {Project No. EACSTPD-23-2(119)} and Call Order No. N35, {Project No. PEP-23-2(1028)}. Award of Contract, if awarded, will be made on the combined bid for these call order nos. Separate contracts will be awarded for each Call Order Number. Please order plans and proposals accordingly.

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	75	SHEETS	\$ 15.00
CROSS SECTIONS (SHEETS X1 THRU X67)	67	SHEETS	\$ 13.40
STANDARD PLANS	7	SHEETS	\$ 1.40

SHEET NO.

1	TITLE PAGE
2T1-2T2	TYPICAL CROSS SECTIONS
2S1-2S2	SUMMARY OF QUANTITIES
2W1-2W7	WETLANDS
2H	HORIZONTAL ALIGNMENT & CONTROL POINTS
2N1	GENERAL INFORMATION
3 - 10	PLAN SHEETS
11	TRAFFIC CONTROL PLAN
12	TEMPORARY PAVEMENT MARKING PLAN
13	TYPICAL PAVEMENT MARKING PLAN
14 - 18	EARTHWORK DATA SHEETS
19 - 38	DRAINAGE STRUCTURE CROSS SECTIONS
39	SPECIAL PLAN 1C CONCRETE FLUME, TYPE I
40 - 41	SPECIAL PLAN 2C CONCRETE FLUME, TYPE VII
42 - 43	SPECIAL PLAN 3C MAILBOX SUPPORT POST
44	SPECIAL PLAN 4C MAILBOX TURNOUT
45	SPECIAL PLAN 5C EROSION CONTROL, TYPES "A" & "AA"
46	SPECIAL PLAN 6C EROSION CHECKS (ALL TYPES) & FABRIC SILT CHECKS
47 - 49	SPECIAL PLAN 7C TYPICAL URBAN TRAFFIC CONTROL PLAN
R1 - R14	RIGHT-OF-WAY SHEETS
X1 - X67	CROSS SECTIONS

STANDARD PLANS

108-R2	SUPERELEVATION PLAN FOR CONCRETE AND BITUMINOUS SURFACING
410-R3	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
804	PRECAST CONCRETE R.O.W. MARKER
901-R8	HIGHWAY DELINEATORS
920-R5	(2 SHEETS) TRAFFIC CONTROL

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER	1,007	MGAL
RIGHT-OF-WAY MARKERS	2	EACH
REMOVE DELINEATOR UNITS	47	EACH
EARTHWORK MEASURED IN EMBANKMENT	26,860	CY
REMOVE DRIVEWAY	381	SY
30" DRIVE PIPE 2,3,4,5,6,7 OR 8	36	LF
EROSION CONTROL, TYPE A	2,726	SY
EROSION CHECKS, TYPE HV	480	BALE

GROUP 4 CULVERTS

MOBILIZATION	LUMP	LUMP
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL	91	CY
24" FLARED-END SECTION	10	EACH
36" FLARED-END SECTION	8	EACH
48" FLARED-END SECTION	2	EACH
54" FLARED-END SECTION	2	EACH
96" STRUCTURAL PLATE PIPE	38	LF
24" CULV PIPE 3,4,5	36	LF
36" CULV PIPE 3,4,5	12	LF

GROUP 5 SEEDING

MOBILIZATION	LUMP	LUMP
SEEDING, TYPE A	10	ACRE
SEEDING, TYPE B	23	ACRE
MULCH	75	TON

GROUP 9 BITUMINOUS

PERMANENT PAVEMENT MARKING PAINT	112,000	LF
MOBILIZATION	LUMP	LUMP
DELINEATOR, TYPE III	66	EACH
GRAVEL SURFACE COURSE	105	CY
SPEC SURF CRSE FOR MAILBOX TURNOUTS	97	SY
MAILBOX POST	2	EACH
CAST IRON GRATE & FRAME	3,808	LB
ADJUST MANHOLE TO GRADE	4	EACH
FLUME SPILLWAY	386	LF
CONCRETE FLUME, TYPE I	39	EACH
47B-3000 CONC FOR INLET & JUNCTION BOXES	14	CY
RE-STEEL FOR INLET & JCT BOX	1,024	LB
HYDRATED LIME	357	TON
HYDRATED LIME SLURRY STABILIZATION	412	STA
SHOULDER SUBGRADE PREPARATION	152	STA
ASPH CONCRETE FOR PATCHING, TYPE SP4(0.375)	500	TON
ASPH CONC, TYPE SP4(0.375)	31,370	TON
PLACE ASPH CONC FOR DRIVE & INTER	4,086	SY
PERF GRADED BINDER (64-28)	2,039	TON
CONSTRUCTING ASPH CONC CURB	13,399	LF
EMUL ASPH FOR HYDRATE LIME STABILIZATION	86,920	GAL
TACK COAT	29,570	GAL
FOG SEAL	1,650	GAL
WATER	208	MGAL
WATER FOR CEMENT STABILIZATION	83	MGAL
EARTH SHOULDER CONSTRUCTION	678	STA
TRENCHED WIDENING	821	STA
COLD MILLING, CLASS 3	9,633	SY
CEMENT STABILIZED BITUMINOUS	25	STA
CEMENT	329	TON
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP
15" CULV PIPE 3,4,5,6	236	LF

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	28,000	BDAY
BARRICADE, TYPE III	556	BDAY
TEMPORARY SIGN DAY	540	EACH
SIGN DAY	9,046	EACH
OVERLAY BROKEN LINES	1,316	STA
OVERLAY SOLID LINES	2,632	STA
FLAGGING	90	DAY
FURNISHING AND OPERATING PILOT VEHICLE	45	DAY
FIELD OFFICE	1	EACH
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED	40	HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	40	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	40	HOUR
RENTAL OF BACKHOE, FULLY OPERATED	10	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	40	HOUR
TEMPORARY SILT FENCE	500	LF
TEMPORARY BALE CHECK	200	BALE
TEMPORARY EARTH CHECK	600	LF
TEMPORARY MULCH	20	TON