

NOTICE TO CONTRACTORS

CALL ORDER F06
 FEDERAL PROJECT NO. BRO-7020(16)
 LOCATION: ON A COUNTY ROAD NORTHWEST OF BANCROFT.
 COUNTIES: CUMING

The Nebraska Department of Roads will receive sealed bids for
 CUMING COUNTY in Room 104 of the Central Office Building at
 1500 Hwy 2 at Lincoln, until 1:30 P.M. on April 08, 2004 .
 At that time the bids will be opened and read for
 GRAD,BR,GDRL

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR
 WHO IS QUALIFIED FOR: BRIDGES
 START DATE 05/24/2004 WORKING DAYS 110
 Price Range \$ 500,000 to \$ 1,000,000

Plans and specifications may be seen beginning March 16, 2004 at the Lincoln
 Central Office and March 22, 2004 at the District Engineer's Office at NORFOLK
 Additional letting information may be found at the Nebraska Department of Roads
 Web Site at <http://www.dor.state.ne.us/letting/>

THIS PROJECT IS SUBJECT TO TRIBAL EMPLOYMENT RIGHTS OFFICE (TERO) TAX AND INDIAN
 EMPLOYMENT PREFERENCE GOALS.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal
 requirements will apply.

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	39	SHEETS	\$ 7.80
STANDARD PLANS	5	SHEETS	\$ 1.00

SHEET NO.	
1	TITLE PAGE
2T1	TYPICAL CROSS SECTIONS
2S	SUMMARY OF QUANTITIES
3	PLAN & PROFILE SHEET
4 - 7	CULVERT CROSS SECTIONS
8 - 10	ROADWAY CROSS SECTIONS
11	CHANNEL CROSS SECTION LAYOUT
12 - 13	CHANNEL CROSS SECTIONS
14	CHANNEL GRADING PLAN
15	RIGHT-OF-WAY PLAN
16 - 30	SPECIAL PLAN 1 ROLLED BEAM GIRDER BRIDGE STA. 2+98.500
31 - 37	SPECIAL PLAN 1C GUARDRAIL PROTECTION
38	SPECIAL PLAN 2C CONCRETE HEADWALL

STANDARD PLANS

M425	COLLARS AND ELBOWS FOR CONCRETE PIPES
M920	(2 SHEETS) TRAFFIC CONTROL
M921	TRAFFIC CONTROL
M923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and
 should not be used for bidding purposes. The Department
 reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
LARGE TREE REMOVAL		1 EACH
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		355 kL
EARTHWORK MEASURED IN EMBANKMENT		5,488 m3
600 mm DRIVEWAY CULVERT PIPE		36 m
GRAVEL SURFACE COURSE		75 m3
CRUSHED ROCK EMBEDMENT		2 StaM
CRUSHED ROCK SURFACE COURSE		75 m3
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL		142 m3

47B-20 OR AX-20 CONC FOR HDWL	1 m3
RE-STEEL FOR HEADWALL	66 kg
600 mm CULVERT PIPE	125 m
COVER CROP SEEDING	1 ha

GROUP 6 BRIDGE AT STA. 2+98.5

MOBILIZATION	LUMP	LUMP
RIPRAP FILTER FABRIC	2,725	m2
ABUTMENT NO.1 EXCAVATION	LUMP	LUMP
ABUTMENT NO.2 EXCAVATION	LUMP	LUMP
PIER NO.1 EXCAVATION	LUMP	LUMP
PIER NO.2 EXCAVATION	LUMP	LUMP
EXPANSION BEARING, TFE TYPE	12	EACH
FIXED BEARING	4	EACH
47B-20 CONC FOR BRIDGE	322	m3
47BD-30 CONC FOR BRIDGE	183	m3
REMOVE STRUCTURE	1	EACH
AT STA. 3+00		
STEEL SUPERSTRUCTURE	LUMP	LUMP
AT STA. 2+98.5		
STRUC STEEL FOR SUBSTRUCTURE	2,786	kg
STRUC STEEL FOR SUPERSTRUCTURE	268	kg
ROCK RIPRAP, TYPE B	2,660	Mg
EPOXY COATED RE-STEEL	41,595	kg
SUBSURFACE DRAINAGE MATTING	55	m2
HP 250 mm X 62 kg STEEL PILING	520	m
HP 310 mm X 79 kg STEEL PILING	729	m
STEEL SHEET PILING	396	m2
GRANULAR BACKFILL	80	m3

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
BRIDGE APPROACH SECTIONS	4	EACH
MELT	4	EACH

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE III	2,632	B DAY
SIGN DAY	3,008	EACH
CONTRACTOR FURNISHED SIGN DAY	376	EACH
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED	10	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	10	HOUR
RENTAL OF BACKHOE, FULLY OPERATED	10	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	10	HOUR
TEMPORARY SILT FENCE	100	m
TEMPORARY BALE CHECK	56	BALE
TEMPORARY EARTH CHECK	50	m