

NOTICE TO CONTRACTORS

CALL ORDER F20
 FEDERAL PROJECT NO. STPE-1670(3)
 LOCATION: ON A COUNTY ROAD NORTHEAST OF CALLAWAY
 COUNTIES: CUSTER

The Nebraska Department of Roads will receive sealed bids for
 CUSTER COUNTY in Room 104 of the Central Office Building at
 1500 Hwy 2 at Lincoln, until 1:30 P.M. on April 08, 2004 .
 At that time the bids will be opened and read for
 BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR
 WHO IS QUALIFIED FOR: BITUMINOUS

Length: 10.6 KILOMETERS
 START DATE 09/13/2004 WORKING DAYS 25
 Price Range \$ 500,000 to \$ 1,000,000
 THIS PROJECT CONTAINS A DBE GOAL OF 3.0 %

Plans and specifications may be seen beginning March 16, 2004 at the Lincoln
 Central Office and March 22, 2004 at the District Engineer's Office at NORTH PLATTE
 Additional letting information may be found at the Nebraska Department of Roads
 Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal
 requirements will apply.

PLANS (NOT INCLUDING STANDARDS)	16 SHEETS	\$ 3.20
STANDARD PLANS	5 SHEETS	\$ 1.00

SHEET NO.

1	TITLE SHEET
2T	TYPICAL SECTIONS
2S	SUMMARY OF QUANTITIES
3 - 10	PLAN & PROFILE SHEETS
11 - 12	SPECIAL PLAN 1C MAILBOX SUPPORT POST
13	SPECIAL PLAN 2C MAILBOX TURNOUT
14	TEMPORARY PAVEMENT MARKING PLAN
15	TYPICAL PAVEMENT MARKING PLAN

STANDARD PLANS

M108-R1	SUPERELEVATION PLAN FOR CONCRETE AND BITUMINOUS SURFACING
M920	(2 SHEETS) TRAFFIC CONTROL
M921	TRAFFIC CONTROL
M922	TRAFFIC CONTROL DEVICES

Quantities shown herein are FOR INFORMATION ONLY and
 should not be used for bidding purposes. The Department
 reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	8,800	BDAY
BARRICADE, TYPE III	192	BDAY
TEMPORARY SIGN DAY	300	EACH
SIGN DAY	3,072	EACH
OVERLAY BROKEN LINES	211	StaM
OVERLAY SOLID LINES	423	StaM
PERMANENT PAVEMENT MARKING PAINT	35,000	m
FLAGGING	20	DAY
FIELD OFFICE	1	EACH
MOBILIZATION	LUMP	LUMP
SPEC SURF CRSE FOR MAILBOX TURNOUTS	143	m2
MAILBOX POST	5	EACH
ASPH CONCRETE FOR PATCHING, TYPE SP4 SPECIAL(9.5)	480	Mg
ASPH CONC, TYPE SP4 SPECIAL(9.5)	20,250	Mg
PLACE ASPH CONC FOR DRIVE & INTER	2,515	m2
PERF GRADED BINDER (64-28)	1,119	Mg
PREP OF INTER & DRIVE	2,360	m2
TACK COAT	64,690	L
RENTAL OF LOADER, FULLY OPERATED	45	HOUR

RENTAL OF MOTOR GRADER, FULLY OPERATED	40 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	45 HOUR
RENTAL OF BACKHOE, FULLY OPERATED	5 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	45 HOUR
WATER	636 kL
EARTH SHOULDER CONSTRUCTION	211 StaM
COLD MILLING, CLASS 3	960 m2
TEMPORARY SILT FENCE	200 m
TEMPORARY MULCH	40 Mg