

NOTICE TO CONTRACTORS

CALL ORDER F22
FEDERAL PROJECT NO. NH-6-4(120)
LOCATION: US-6/US-34 EAST OF HEARTWELL.
COUNTIES: KEARNEY ADAMS

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on April 08, 2004 . At that time the bids will be opened and read for GR CULV BR GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 3.5 MILES
START DATE 06/14/2004 WORKING DAYS 80
Price Range \$ 1,000,000 to \$ 3,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 4.0 %

Plans and specifications may be seen beginning March 16, 2004 at the Lincoln Central Office and March 22, 2004 at the District Engineer's Office at MCCOOK

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	49	SHEETS	\$ 9.80
CROSS SECTIONS (SHEETS X1 THRU X39)	39	SHEETS	\$ 7.80
STANDARD PLANS	9	SHEETS	\$ 1.80

SHEET NO.

1	TITLE PAGE
2T1-2T5	TYPICAL CROSS SECTIONS
2S1-2S7	SUMMARY OF QUANTITIES
2N	GENERAL INFORMATION
3 - 7	PLAN SHEETS
8	TRAFFIC CONTROL PLAN
9	TYPICAL TRAFFIC SIGNAL CONTROL PLAN FOR ONE LANE, TWO WAY OPERATION
10	TEMPORARY TRAFFIC SIGNAL
11	TYPICAL PAVEMENT MARKING PLAN
12	TEMPORARY PAVEMENT MARKING PLAN
13 - 15	EARTHWORK DATA SHEETS
16 - 20	DRAINAGE STRUCTURE CROSS SECTIONS
21 - 23	SPECIAL PLAN 1C EXPANSION JOINT REPAIR REMODEL BRIDGE RAIL APPROACH SLAB DETAILS STA. 126+79.80
24	SPECIAL PLAN 2C CONCRETE COLLAR STA. 292+23.00
25 - 35	SPECIAL PLAN 3C GUARDRAIL PLAN
36 - 37	SPECIAL PLAN 4C MAILBOX SUPPORT POST
X1 - X39	CROSS SECTIONS

STANDARD PLANS

410-R3	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
501-R3	EROSION CONTROL
901-R8	HIGHWAY DELINEATORS
920-R5	(2 SHEETS) TRAFFIC CONTROL
921-R4	TRAFFIC CONTROL
1104	(2 SHEETS) REINFORCED CONCRETE BOX CULVERTS SINGLE SPAN WITH 4-FOOT RISE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		105 MGAL
EARTHWORK MEASURED IN EMBANKMENT		4,675 CY
REMOVE PAVEMENT		312 SY
REMOVE ASPHALT SURFACE		375 SY
REMOVE CURB		104 LF
REMOVE GUARDRAIL		2,675 LF
EROSION CONTROL		5,995 SY

GROUP 4 CULVERTS

MOBILIZATION	LUMP	LUMP
PREPARATION OF STRUCTURE AT STA. 213+34		1 EACH
PREPARATION OF STRUCTURE AT STA. 292+23		1 EACH
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL		8 CY
EXCAVATION FOR BOX CULVERTS		29 CY
47B-3000 OR AX-3000 CONC FOR BOX CULV		28 CY
47B-3000 OR AX-3000 CONC FOR CONCRETE CO		2 CY
RE-STEEL FOR BOX CULVERT		2,678 LB
RE-STEEL FOR COLLARS		155 LB
36" ROUND EQUIVALENT RCP		4 LF
36" RND EQUIV CONCRETE FES		1 EACH

GROUP 6 BRIDGE AT STA. 126+79.80

MOBILIZATION	LUMP	LUMP
CONC FOR PVMT APPROACHES CLASS 47BD-4000		102 CY
EPOXY COATED RE-STEEL FOR PVMT APPROACH		9,005 LB
EXPANSION JOINT		164 LF
47BD-4000 CONC FOR BRIDGE		5 CY
PREP BRIDGE		1 EACH
AT STA. 126+79.80		
EPOXY COATED RE-STEEL		890 LB

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
W-BEAM GUARDRAIL		537 LF
CABLE GUARDRAIL		1,872 LF
BRIDGE APPROACH SECTIONS		4 EACH
TERMINAL ANCHORAGE SECTIONS		8 EACH
GUARDRAIL END TREATMENT, TYPE II		4 EACH

GROUP 9 BITUMINOUS

OVERLAY BROKEN LINES		370 STA
OVERLAY SOLID LINES		741 STA
PERMANENT PAVEMENT MARKING PAINT		42,700 LF
MOBILIZATION	LUMP	LUMP
DELINEATOR, TYPE III		9 EACH
INSTALL CHEVRONS		4 EACH
GRAVEL SURFACE COURSE		107 CY
MAILBOX POST		4 EACH
CONC PVMT REPAIR TYPE A FULL DEPTH		26 SY
CONC PVMT REPAIR TYPE B FULL DEPTH		1,053 SY
CONC PVMT REPAIR TYPE C FULL DEPTH		322 SY
BITUMINOUS PATCHING		69 TON
CONC PVMT, PR-3500		312 SY
JOINT REPAIR		
ASPH CONC FOR STATE MAINT PATCHING, TYPE SP4 (0.5)		500 TON

GROUP 9 BITUMINOUS

ASPH CONCRETE FOR PATCHING, TYPE SPS	100 TON
ASPH CONC, TYPE SPS	7,840 TON
ASPH CONC, TYPE SP4(0.5)	10,720 TON
PLACE ASPH CONC FOR DRIVE & INTER SURFACING 8"	2,973 SY
PERF GRAD BIND (64-28)FOR ST MAINT PATCH	380 SY
PERF GRADED BINDER (58-28)	27 TON
PERF GRADED BINDER (64-28)	428 TON
TACK COAT	578 TON
FOG SEAL	17,190 GAL
WATER	7,910 GAL
WATER FOR FLY ASH STABILIZATION	93 MGAL
EARTH SHOULDER CONSTRUCTION	197 MGAL
MILLING CONC FOR INLAYS	370 STA
SURFACE UNDER GUARDRAIL	2 EACH
FLY ASH STABILIZED BITUMINOUS	1,274 SY
FLY ASH	370 STA
ASPH PVMT SMOOTHNESS TESTING	1,480 TON
SEEDING, TYPE B	LUMP LUMP
MULCH	6 ACRE
	15 TON

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	1,320 BDAY
BARRICADE, TYPE III	600 BDAY
TEMPORARY SIGN DAY	1,190 EACH
SIGN DAY	8,412 EACH
PAVEMENT MARKING REMOVAL	900 LF
TEMP PVMT MARKING, TYPE II	2,350 LF
TEMP PVMT MARKING SURF PREP	1,000 LF
FLAGGING	160 DAY
FURNISHING AND OPERATING PILOT VEHICLE	70 DAY
TEMPORARY RUMBLE STRIP	4 EACH
TEMPORARY TRAFFIC SIGNAL	1 EACH
TRAFFIC CONTROL MANAGEMENT	138 DAY
FIELD OFFICE	1 EACH
MOBILIZATION	LUMP LUMP
RENTAL OF LOADER, FULLY OPERATED	20 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	20 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	20 HOUR
RENTAL OF BACKHOE, FULLY OPERATED	20 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	20 HOUR
TEMPORARY SILT FENCE	200 LF