NOTICE TO CONTRACTORS

CALL ORDER F25

FEDERAL PROJECT NO. STPE-7259(1)

LOCATION: ON A COUNTY ROAD NORTHEAST OF HYANNIS

COUNTIES: CHERRY

The Nebraska Department of Roads will receive sealed bids for CHERRY COUNTY in Room 104 of the Central Office Building at

1500 Hwy 2 at Lincoln, until 1:30 P.M. on April 08, 2004

At that time the bids will be opened and read for

CULVERT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR

WHO IS QUALIFIED FOR: CULVERTS

START DATE 08/30/2004 WORKING DAYS 25
Price Range \$ 0 to \$ 100,000

Plans and specifications may be seen beginning March 16, 2004 at the Lincoln Central Office and March 22, 2004 at the District Engineer's Office at AINSWORTH Additional letting information may be found at the Nebraska Department of Roads Web Site at http://www.dor.state.ne.us/letting/.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

SHEETS

\$ 1.60

SHEETS \$ 1.20

PLANS (NOT INCLUDING STANDARDS) 8
STANDARD PLANS 6

SHEET NO.

1206

1	TITLE PAGE		
2T	TYPICAL CROSS SECTION OF IMPROVEMENT		
	& SUMMARY OF QUANTITIES		
3	PLAN & PROFILE SHEET, STA. 0+00 TO STA. 2+33.51		
4	ROADWAY CROSS SECTIONS		
5	DRAINAGE STRUCTURE CROSS SECTION		
6	BOX CULVERT PLAN		
7	BOX CULVERT SECTIONS		
8	RIGHT-OF-WAY STRIP MAP		
STANDARD PLANS			
920-R5	(2 SHEETS) TRAFFIC CONTROL		
921-R4	TRAFFIC CONTROL		
923	TRAFFIC CONTROLROAD CLOSURE		

(2 SHEETS) REINFORCED CONCRETE BOX CULVERTS

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

TWIN SPAN WITH 6-FOOT RISE

GROUP 4 CULVERT AT STA. 1+17

BARRICADE, TYPE III	576	BDAY
SIGN DAY	768	EACH
CONTRACTOR FURNISHED SIGN DAY	96	EACH
MOBILIZATION	LUMP	LUMP
EXCAVATION FOR BOX CULVERTS	153	CY
47B-3000 OR AX-3000 CONC FOR BOX CULV	90	CY
RE-STEEL FOR BOX CULVERT	10,991	LB
REMOVE STRUCTURE	1	EACH
AT STA. 1+17		
RENTAL OF LOADER, FULLY OPERATED	10	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	10	HOUR
RENTAL OF BACKHOE, FULLY OPERATED	10	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	10	HOUR
TEMPORARY SILT CHECK	200	LF
TEMPORARY SILT FENCE 20		LF