

NOTICE TO CONTRACTORS

CALL ORDER 205
 FEDERAL PROJECT NO. BRO-7028(46)
 LOCATION: ON A COUNTY ROAD, BENNINGTON SOUTHWEST
 COUNTIES: DOUGLAS

The Nebraska Department of Roads will receive sealed bids for DOUGLAS COUNTY in Room 104 of the Central Office Building at 1500 Hwy 2 at Lincoln, until 1:30 P.M. on April 17, 2008. At that time the bids will be opened and read for GR BR GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BRIDGES

START DATE 06/16/2008 WORKING DAYS 75
 Price Range \$ 250,000 to \$ 1,000,000
 THIS PROJECT CONTAINS A DBE GOAL OF 4.0 %

Plans and specifications may be seen beginning March 25, 2008 at the Lincoln Central Office and March 31, 2008 at the District Engineer's Office at OMAHA
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	40 SHEETS	\$	10.00
STANDARD PLANS	13 SHEETS	\$	3.25

SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS & DETAILS
2-S1 - 2-S2	SUMMARY OF QUANTITIES
2-L1	DRIVEWAY DETAIL
2-L2 - 2-L3	DRAINAGE STRUCTURE DETAILS
2-L4	STRUCTURE GRADING PLAN
3 - 5	PLAN & PROFILE SHEETS STA. 6+00.00 TO STA. 14+70.00
6 - 10	GRADING CROSS SECTIONS (ROADWAY)
11 - 13	GRADING CROSS SECTIONS (DRIVEWAY)
14 - 24	SPECIAL PLAN 1 CONCRETE SLAB BRIDGE STA. 11+20.00
25 - 33	SPECIAL PLAN 1C GUARDRAIL PLAN
34	RIGHT-OF-WAY SHEET

STANDARD PLANS

301-R9	(3 SHEETS) PAVEMENT DETAILS
329-R7	(4 SHEETS) 8 TO 16 INCH CONCRETE PAVEMENT
502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
LARGE TREE REMOVAL		1 EACH
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		24 MGAL
EARTHWORK MEASURED IN EMBANKMENT		1,366 CY
SAWING PAVEMENT		12 LF
REMOVE ASPHALT SURFACE		1,363 SY

REMOVE DRIVEWAY	184 SY
18" DRIVEWAY CULVERT PIPE	24 LF
24" DRIVEWAY CULVERT PIPE	52 LF
CRUSHED ROCK SURFACE COURSE	30 TON
CAST IRON GRATE & FRAME	270 LB
REMOVE HEADWALLS FROM CULV	1 EACH
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL	215 CY
47B-3000 CONC FOR INLET & JUNCTION BOXES	1 CY
RE-STEEL FOR INLET & JCT BOX	80 LB
24" CORRUGATED METAL PIPE	58 LF
COVER CROP SEEDING	1 ACRE
FABRIC SILT FENCE-LOW POROSITY	1,502 LF

GROUP 6 BRIDGE AT STA. 11+20.00

MOBILIZATION	LUMP	LUMP
RIPRAP FILTER FABRIC		743 SY
CONC FOR PVMT APPROACHES CLASS 47BD-4000		127 CY
EPOXY COATED RE-STEEL FOR PVMT APPROACH		14,861 LB
ABUTMENT NO.1 EXCAVATION	LUMP	LUMP
ABUTMENT NO.2 EXCAVATION	LUMP	LUMP
BENT NO.1 EXCAVATION	LUMP	LUMP
BENT NO.2 EXCAVATION	LUMP	LUMP
47B-3000 CONC FOR BRIDGE		147 CY
47BD-4000 CONC FOR BRIDGE		85 CY
REMOVE STRUCTURE		1 EACH
AT STA. 11+20		
STRUC STEEL FOR SUBSTRUCTURE		885 LB
ROCK RIPRAP, TYPE B		936 TON
EPOXY COATED RE-STEEL		33,169 LB
HP 10"X42# STEEL PILING		3,010 LF
STEEL SHEET PILING		3,841 SF

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
BRIDGE APPROACH SECTIONS		4 EACH
MELT		4 EACH

GROUP 9 BITUMINOUS

MOBILIZATION	LUMP	LUMP
CONC CLASS 47B-3500 DRIVEWAY 8"		366 SY
HYDRATED LIME FOR ASPHALT MIXTURES		6 TON
ASPH CONC, TYPE SP4(0.5)		510 TON
PERF GRADED BINDER (64-28)		27 TON
TACK COAT		120 GAL
WATER		7 MGAL
EARTH SHOULDER CONSTRUCTION		8 STA
SUBGRADE PREPARATION		1,557 SY
SEEDING, TYPE B		1 ACRE
MULCH		2 TON

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE III		1,668 BDAY
SIGN DAY		2,224 EACH
CONTRACTOR FURNISHED SIGN DAY		556 EACH
FIELD OFFICE		1 EACH
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED		15 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED		15 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED		15 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.		15 HOUR