

NOTICE TO CONTRACTORS

CALL ORDER 400
STATE PROJECT NO. RD-81-2(1040)
LOCATION: US-81, EAST JCT. N-92 NORTH
COUNTIES: BUTLER POLK

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on April 17, 2008 . At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 9.5 MILES
START DATE 06/16/2008 WORKING DAYS 85
Price Range \$ 2,000,000 to \$ 4,000,000

Plans and specifications may be seen beginning March 25, 2008 at the Lincoln Central Office and March 31, 2008 at the District Engineer's Office at GRAND ISLAND

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	44 SHEETS	\$	11.00
STANDARD PLANS	13 SHEETS	\$	3.25

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T6	TYPICAL CROSS SECTIONS
2-S1 - 2-S3	SUMMARY OF QUANTITIES
2-W1 - 2-W9	PHOTO MAPS
2-H1 - 2-H4	HORIZONTAL ALIGNMENT & CONTROL POINTS
2-N1	GENERAL INFORMATION
2-N2	GENERAL INFORMATION--MILLED RUMBLE STRIPS
3 - 12	PLAN SHEETS
13	TEMPORARY PAVEMENT MARKING PLAN
14	PAVEMENT MARKING DETAILS
15	SPECIAL PLAN 1C CONCRETE FLUME, TYPE I
16	SPECIAL PLAN 2C MAILBOX TURNOUT
17 - 18	SPECIAL PLAN 3C MAILBOX SUPPORT POST
19 - 21	SPECIAL PLAN 4C CABLE GUARDRAIL

STANDARD PLANS

301-R9	(3 SHEETS) PAVEMENT DETAILS
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R7	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	31,460	BDAY
BARRICADE, TYPE III	612	BDAY
TEMPORARY SIGN DAY	1,000	EACH
SIGN DAY	10,019	EACH
OVERLAY BROKEN LINES	1,007	STA
OVERLAY SOLID LINES	2,086	STA
FLAGGING	170	DAY
FURNISHING AND OPERATING PILOT VEHICLE	85	DAY
FIELD OFFICE	1	EACH
MOBILIZATION	LUMP	LUMP
ROADWAY GRADING	4	STA
REMOVE ASPH SURF FROM PAVEMENT	10,378	SY
GRAVEL SURFACE COURSE	170	CY
CRUSHED ROCK SURFACE COURSE	55	CY
SPEC SURF CRSE FOR MAILBOX TURNOUTS	85	SY
MAILBOX POST	2	EACH
CONC 47B-3000 MEDIAN SURFACING	2,482	SY
CONC PVMT REPAIR TYPE A FULL DEPTH	15	CY
CONC PVMT REPAIR TYPE B FULL DEPTH	29	CY
CONC PVMT REPAIR TYPE C FULL DEPTH	184	CY
CONC PVMT, PR-3500	240	CY
JOINT REPAIR		
FLUME SPILLWAY	5	LF
CONCRETE FLUME, TYPE I	1	EACH
CABLE GUARDRAIL	704	LF
REMOVE GUARDRAIL	424	LF
TERMINAL ANCHORAGE SECTIONS	2	EACH
24" WHITE PREF PVMT MKING T-4 GROOVED	72	LF
RR XING SYMBOL PREF PVMT MRKING T-4 GRVD	2	EACH
HYDRATED LIME FOR ASPHALT MIXTURES	317	TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC	5	TON
GRANULAR SUBDRAIN	948	EACH
ASPH CONC FOR STATE MAINT PATCHING, TYPE SP4(0.5)	500	TON
ASPH CONCRETE FOR PATCHING, TYPE SPS	200	TON
ASPH CONCRETE FOR PATCHING, TYPE SP4(0.5)	100	TON
ASPH CONC, TYPE SPS	19,690	TON
ASPH CONC, TYPE SP4(0.5)	31,690	TON
PLACE ASPH CONC FOR DRIVE & INTER	5,908	SY
PERF GRAD BIND (64-28)FOR ST MAINT PATCH	27	TON
PERF GRADED BINDER (58-28)	1,063	TON
PERF GRADED BINDER (64-28)	1,711	TON
CONSTRUCTING ASPH CONC CURB	934	LF
PREP OF INTER & DRIVE	38	SY
TACK COAT	46,650	GAL
RENTAL OF LOADER, FULLY OPERATED	45	HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	30	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	45	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	45	HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	15	HOUR
WATER	252	MGAL
CRACKING & SEATING CONC PVMT	136,425	SY
EARTH SHOULDER CONSTRUCTION	1,006	STA
MILLING CONC FOR INLAYS	4	EACH
RUMBLE STRIPS, ASPHALT	965	STA

GROUP 9 BITUMINOUS

SURFACE UNDER GUARDRAIL	332 SY
NON-WOVEN PVMT OVERLAY FABRIC	139,290 SY
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP LUMP
SEEDING, TYPE B	29 ACRE
EROSION CONTROL, CLASS 1D	306 SY
EROSION CONTROL, CLASS 2A	45 SY
TEMPORARY SILT FENCE	1,500 LF
TEMPORARY MULCH	6 TON
MULCH	65 TON