

STATE OF NEBRASKA
DEPARTMENT OF ROADS
ADDENDUM NO. 3
PROJECT NO. IM-80-4(131)
CONTROL NO. 61336
CALL ORDER 600
I-80, COZAD INTERCHANGE
LETTING DATE: APRIL 17, 2008

On page 7 of Addendum No. 1 Amendment No. 1, items **O.** and **P.** are void and superseded by the following:

- O.** If the project involves construction phasing where temporary shoring is required, caution shall be exercised if removing shoring adjacent to the geofoam structure and backfill. No physical damage, loss of granular backfill, or misalignment shall be permitted. The Contractor shall be required to make provisions to prevent loss of backfill during shoring removal adjacent to geofoam structures.
- P.** The final surface of the EPS blocks shall be covered with a 30 mil thickness of High Density Polyethylene (HDPE) with a 2 foot overhang on all sides and a 1 foot minimum non-water tide overlap (if necessary). Caution shall be exercised during the placement of the cover material so as not to cause any damage to the EPS blocks.

DEPARTMENT OF ROADS



Claude Oie
Construction Engineer

Issued: April 11, 2008

CO:AH:600AD304

NOTICE: Only the contractors issued bidding proposals receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the contractor.