

NOTICE TO CONTRACTORS

CALL ORDER 605  
FEDERAL PROJECT NO. STPD-21-2(109)  
LOCATION: N-21, MONROE ST. TO I-80, COZAD  
COUNTIES: DAWSON

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on April 17, 2008. At that time the bids will be opened and read for GRAD CONC PAVE CULV

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: GENERAL

START DATE 07/07/2008 CALENDAR DAYS 132  
Price Range \$ 0 to \$ 500,000  
THIS PROJECT CONTAINS A DBE GOAL OF 5.0 %

Plans and specifications may be seen beginning March 25, 2008 at the Lincoln Central Office and March 31, 2008 at the District Engineer's Office at NORTH PLATTE. Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

NOTICE TO BIDDERS

To be eligible for the award of this contract, bidders shall submit a completed bidding proposal for Call Order No. 600, {Project No. IM-80-4(131)}, Call Order No. 605, {Project No. STPD-21-2(109)} and Call Order No. 610, {Project No. RD-21-2(1015)}. Award of Contract, if awarded, will be made on the combined bid for these call order nos. Separate contracts will be awarded for each Call Order Number. Please order plans and proposals accordingly.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	44 SHEETS	\$	11.00
CROSS SECTIONS (SHEETS X1 THRU X8)	8 SHEETS	\$	2.00
STANDARD PLANS	25 SHEETS	\$	6.25

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T8	TYPICAL CROSS SECTIONS
2-S1 - 2-S2	SUMMARY OF QUANTITIES
2-A1 - 2-A3	PHOTO MAPS
2-H1 - 2-H4	HORIZONTAL ALIGNMENT & CONTROL POINTS
2-N	GENERAL INFORMATION
2-P1 - 2-P2	PHASING PLANS
2-L1	GEOMETRICS
2-L2	GRADES
2-L3 - 2-L7	CONSTRUCTION
2-L8	REMOVALS
2-L9	EROSION CONTROL
3 - 5	PLAN & PROFILE SHEETS
6	TYPICAL TRAFFIC CONTROL PLAN (PHASED TEMPORARY TRAFFIC CONTROL)
7 - 9	TYPICAL URBAN TRAFFIC CONTROL PLAN
10	PAVEMENT MARKING PLAN
11	TYPICAL PAVEMENT MARKING PLAN
12	TEMPORARY PAVEMENT MARKING PLAN
13	EARTHWORK DATA SHEET
14	DRAINAGE STRUCTURE CROSS SECTION
15	SPECIAL PLAN 1C CURB RAMPS
R1	RIGHT-OF-WAY SHEET
X1 - X8	CROSS SECTIONS

STANDARD PLANS

301-R9	(3 SHEETS) PAVEMENT DETAILS
329-R7	(4 SHEETS) 8 TO 16 INCH CONCRETE PAVEMENT
410-R3	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
413-R1	BAR GRATE FOR FLARED END SECTIONS
425-R4	COLLARS AND ELBOWS FOR CONCRETE PIPES
435-R1	(3 SHEETS) MANHOLE
443-R7	(2 SHEETS) CURB INLETS AND JUNCTION BOX
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
804	PRECAST CONCRETE R.O.W. MARKER
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R7	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)		213 CY
WATER		3 MGAL
RIGHT-OF-WAY MARKERS		2 EACH
RE-ESTABLISH PROPERTY CORNER		2 EACH
REMOVE PAVEMENT		407 SY
SAWING PAVEMENT		336 LF
REMOVE WALK		64 SY
REMOVE CONCRETE MEDIAN SURFACING		496 SY
EROSION CONTROL, CLASS 1B		282 SY

GROUP 3 CONCRETE PAVEMENT

PAVEMENT MARKING REMOVAL		300 LF
MOBILIZATION	LUMP	LUMP
TIE BARS		326 EACH
CONCRETE CURB REPAIR TACK-ON CURB		5 LF
CONCRETE CURB REPAIR		31 LF
CONC 47B-3000 SIDEWALKS		130 SY
6"		
CONC 47B-3000 MEDIAN SURFACING		214 SY
CONC PVMT REPAIR TYPE A FULL DEPTH		7 CY
CONC PVMT REPAIR TYPE B FULL DEPTH		47 CY
CONC PVMT REPAIR TYPE C FULL DEPTH		104 CY
CONC PVMT REPAIR TYPE A PARTIAL DEPTH		1 CY
8" CONC PVMT, 47B-3500		877 SY
CONC PVMT, PR-3500		7 CY
JOINT REPAIR		
ADJUST MANHOLE TO GRADE		2 EACH
ARROW POLYUREA PVMT MRKING, GROOVED		14 EACH
5" WHI POLYUREA PVMT MRKING, GROOVED		4,700 LF
5" YEL POLYUREA PVMT MRKING, GROOVED		6,100 LF
HYDRATED LIME FOR ASPHALT MIXTURES		22 TON
ASPH CONCRETE FOR PATCHING, TYPE		25 TON
SP4(0.5)		
ASPH CONC, TYPE SP4(0.5)		2,216 TON
PERF GRADED BINDER (64-28)		121 TON
TACK COAT		2,094 GAL
WATER		3 MGAL
SUBGRADE PREPARATION		877 SY
COLD MILLING, CLASS 3		19 STA
COLD MILLING, CLASS 4		1,080 SY
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP

GROUP 4 CULVERTS

MOBILIZATION	LUMP	LUMP
REMOVE FLARED- END SECTION		1 EACH
47B-3000 CONC FOR CONCRETE CO		1 CY
RE-STEEL FOR COLLARS		43 LB
BAR GRATE FOR 24" CONC FES		1 EACH
24" CONCRETE FLARED-END SECTION		1 EACH
24" REINF CONCRETE SEWER PIPE		41 LF

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	1,200	B DAY
BARRICADE, TYPE III	300	B DAY
TEMPORARY SIGN DAY	60	EACH
SIGN DAY	2,944	EACH
CONTRACTOR FURNISHED SIGN DAY	60	EACH
OVERLAY SOLID LINES	232	STA
FLASHING ARROW PANEL	120	DAY
FLAGGING	30	DAY
FIELD OFFICE	1	EACH
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED	10	HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	5	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	10	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	10	HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	5	HOUR
TEMPORARY SILT FENCE	200	LF