

NOTICE TO CONTRACTORS

CALL ORDER 810
 FEDERAL PROJECT NO. NH-281-4(118)
 LOCATION: US-281, O'NEILL SOUTH
 COUNTIES: HOLT

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on November 12, 2009. At that time the bids will be opened and read for GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 7.4 MILES
 START DATE 06/28/2010 WORKING DAYS 60
 Price Range \$ 1,000,000 to \$ 3,000,000
 THIS PROJECT CONTAINS A DBE GOAL OF 2.0 %

Plans and specifications may be seen beginning October 20, 2009 at the Lincoln Central Office and October 26, 2009 at the District Engineer's Office at AINSWORTH
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded by the American Recovery and Reinvestment Act of 2009, all appropriate Federal requirements will apply.

| | | | | |
|---|----|--------|----|-------|
| INFORMATIONAL PROPOSAL | | EACH | \$ | 5.00 |
| PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS) | 47 | SHEETS | \$ | 11.75 |
| CROSS SECTIONS (SHEETS X1 THRU X29) | 29 | SHEETS | \$ | 7.25 |
| STANDARD PLANS | 11 | SHEETS | \$ | 2.75 |

SHEET NO.

| | |
|--------------|--|
| 1 | TITLE PAGE |
| 2-T | TYPICAL CROSS SECTIONS |
| 2-S | SUMMARY OF QUANTITIES |
| 2-W1 - 2-W14 | WETLANDS |
| 2-H1 - 2-H3 | HORIZONTAL ALIGNMENT & ORIENTATION |
| 2-N | GENERAL INFORMATION |
| 2-L1 - 2-L4 | EROSION CONTROL |
| 3 - 9 | PLAN SHEETS |
| 10 | TEMPORARY PAVEMENT MARKING PLAN |
| 11 | TYPICAL PAVEMENT MARKING PLAN--5" PAVEMENT MARKING |
| 12 | PAVEMENT MARKING DETAILS |
| 13 - 14 | EARTHWORK DATA SHEETS |
| 15 - 23 | SPECIAL PLAN 1C GUARDRAIL PLAN |
| 24 | SPECIAL PLAN 2C EROSION CHECKS (ALL TYPES) & FABRIC SILT CHECKS |
| X1 - X29 | CROSS SECTIONS |

STANDARD PLANS

| | |
|--------|--|
| 309 | MAILBOX SUPPORT POST |
| 501-R5 | (3 SHEETS) EROSION CONTROL |
| 502 | SILT FENCE DETAILS |
| 920-R5 | (2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE |
| 921-R5 | (2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE |
| 922-R7 | (2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING |

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 7 GUARDRAIL

| | | |
|----------------------------------|------|--------|
| MOBILIZATION | LUMP | LUMP |
| GENERAL CLEARING AND GRUBBING | LUMP | LUMP |
| WATER | | 4 MGAL |
| EARTHWORK MEASURED IN EMBANKMENT | | 190 CY |

| | |
|----------------------------------|----------|
| W-BEAM GUARDRAIL | 1,312 LF |
| REMOVE GUARDRAIL | 2,334 LF |
| BRIDGE APPROACH SECTIONS | 16 EACH |
| GUARDRAIL END TREATMENT, TYPE II | 16 EACH |
| COVER CROP SEEDING | 1 ACRE |
| EROSION CONTROL, CLASS 1D | 2,653 SY |
| EROSION CHECKS, TYPE WATTLE | 4,292 LF |

GROUP 9 BITUMINOUS

| | |
|---|------------|
| PERMANENT PAVEMENT MARKING PAINT | 91,020 LF |
| MOBILIZATION | LUMP LUMP |
| SLOPE PROTECTION | 2,420 SY |
| SLOPE PROTECTION MULCH | 3 TON |
| REMOVE ASPHALT SURFACE | 2,511 SY |
| MAILBOX POST | 16 EACH |
| 24" WHT WET RFLC PRF PVMT MKNG T4 GVD | 36 LF |
| RR XING WET RFLC PRF PVMT MKNG, T 4 GVD | 1 EACH |
| HYDRATED LIME FOR ASPHALT MIXTURES | 113 TON |
| HYD LIME FOR ASPH MIXES FOR ST MAIN PATC | 1 TON |
| ASPH CONC FOR STATE MAINT PATCHING, TYPE SP4(0.5) | 100 TON |
| ASPH CONCRETE FOR PATCHING, TYPE HRB | 200 TON |
| ASPH CONC, TYPE SPS | 7,700 TON |
| ASPH CONC, TYPE SP4(0.5) | 11,260 TON |
| HIGH RAP BASE | 11,650 TON |
| PERF GRAD BIND (64-28)FOR ST MAINT PATCH | 5 TON |
| PERF GRADED BINDER (58-34) | 414 TON |
| PERF GRADED BINDER (64-28) | 563 TON |
| PERF GRADED BINDER (52-34) | 385 TON |
| TACK COAT | 31,280 GAL |
| COLD MILLING, CLASS 3 | 391 STA |
| COLD MILLING, CLASS 3 TYPE A | 780 STA |
| RUMBLE STRIPS, ASPHALT | 764 STA |
| SURFACE UNDER GUARDRAIL | 2,143 SY |
| ASPH PVMT SMOOTHNESS TESTING I/D | LUMP LUMP |

GROUP 10 GENERAL ITEMS

| | |
|--|------------|
| BARRICADE, TYPE II | 5,200 BDAY |
| BARRICADE, TYPE III | 520 BDAY |
| TEMPORARY SIGN DAY | 840 EACH |
| SIGN DAY | 8,351 EACH |
| OVERLAY BROKEN LINES | 1,173 STA |
| OVERLAY SOLID LINES | 2,346 STA |
| FLAGGING | 120 DAY |
| FURNISHING AND OPERATING PILOT VEHICLE | 60 DAY |
| FIELD OFFICE | 1 EACH |
| TRAINING | 500 HOUR |
| MOBILIZATION | LUMP LUMP |
| RENTAL OF LOADER, FULLY OPERATED | 30 HOUR |
| RENTAL OF MOTOR GRADER, FULLY OPERATED | 20 HOUR |
| RENTAL OF DUMP TRUCK, FULLY OPERATED | 30 HOUR |
| RENTAL OF SKID LOADER, FULLY OPERATED | 30 HOUR |
| RENT CRAWLER MNTED HYD EXCAVATOR, F.O. | 10 HOUR |
| TEMPORARY SILT FENCE | 1,000 LF |
| MOWING | 40 HOUR |