

NOTICE TO CONTRACTORS

CALL ORDER 130
 STATE PROJECT NO. S-8-7(1012)
 LOCATION: N-8/N-50 IN PAWNEE CITY.
 COUNTIES: PAWNEE

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on July 26, 2007 . At that time the bids will be opened and read for GRAD CONC PAVE CULV

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: CULVERTS
 START DATE 09/24/2007 WORKING DAYS 35
 Price Range \$ 0 to \$ 500,000

Plans and specifications may be seen beginning July 03, 2007 at the Lincoln Central Office and July 09, 2007 at the District Engineer's Office at LINCOLN
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	25	SHEETS	\$	6.25
CROSS SECTIONS (SHEETS X1 THRU X13)	13	SHEETS	\$	3.25
STANDARD PLANS	23	SHEETS	\$	5.75

SHEET NO.

1	TITLE PAGE
2T1	TYPICAL CROSS SECTIONS
2S1-2S2	SUMMARY OF QUANTITIES & DETOUR LOCATION MAP
2H1-2H2	HORIZONTAL ALIGNMENT & CONTROL POINTS
2N	GENERAL INFORMATION
2L1	REMOVALS
2L2	CONSTRUCTION
2L3	GEOMETRICS & GRADES
2L4	SEDIMENT & EROSION CONTROL
3	EARTHWORK DATA SHEET
4	DRAINAGE STRUCTURE CROSS SECTIONS
5 - 13	SPECIAL PLAN 1C SINGLE 8' X 10' CBC WITH INLETS, MODIFIED ENDS & PAVED OUTLET, APRON ORIENTATION & NOTES STA. 33+92.00
14 - 15	SPECIAL PLAN 2C TEMPORARY SILT CHECKS
R1	RIGHT-OF-WAY SHEET
X1 - X13	CROSS SECTIONS

STANDARD PLANS

301-R9	(3 SHEETS) PAVEMENT DETAILS
329-R7	(4 SHEETS) 8 TO 16 INCH CONCRETE PAVEMENT
425-R4	COLLARS AND ELBOWS FOR CONCRETE PIPES
435-R1	(3 SHEETS) MANHOLE
501-R4	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
710-R4	(2 SHEETS) FENCE DETAILS
804	PRECAST CONCRETE R.O.W. MARKER
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R7	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
LARGE TREE REMOVAL		1 EACH
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		1 MGAL
RIGHT-OF-WAY MARKERS		6 EACH
EARTHWORK MEASURED IN EMBANKMENT		254 CY
REMOVE PAVEMENT		229 SY
SAWING PAVEMENT		235 LF
REMOVE WALK		97 SY
CLEAR TRACT		1 EACH
AT STA. 33+35.85 TO STA. 34+30.70 RT.		
CLEAR TRACT		1 EACH
AT STA. 34+00 TO STA. 34+25 LT.		
REMOVE UNDERGROUND TANK		1 EACH
EROSION CONTROL, CLASS 1C		427 SY
FABRIC SILT FENCE-LOW POROSITY		240 LF

GROUP 3 CONCRETE PAVEMENT

MOBILIZATION	LUMP	LUMP
TIE BARS		79 EACH
CONC 47B-3000 SIDEWALKS		68 SY
CONC 47B-3500 DRIVEWAY		42 SY
10" CONC PVMT, 47B-3500		229 SY
4' CHAIN-LINK FENCE		105 LF
END POST FOR 4' CH-LINK FENCE		4 EACH
CORNER POST FOR 4' CH-LNK FENCE		4 EACH
PULL POST FOR 4' CH-LNK FENCE		6 EACH
WATER		1 MGAL
EARTH SHOULDER CONSTRUCTION		1 STA
SUBGRADE PREPARATION		271 SY

GROUP 4 CULVERTS

MOBILIZATION	LUMP	LUMP
REMOVE INLET		4 EACH
RECONSTRUCT MANHOLE		1 EACH
REMOVE STRUCTURE		1 EACH
AT STA. 33+92		
EXCAVATION FOR BOX CULVERTS		1,104 CY
47B-3000 CONC FOR BOX CULV		173 CY
47B-3000 CONC FOR CONCRETE CO		1 CY
RE-STEEL FOR BOX CULVERT		15,471 LB
RE-STEEL FOR COLLARS		129 LB
24" REINFORCED CONCRETE PIPE		12 LF
CURB INLET SEDIMENT FILTER		2 EACH

GROUP 10 GENERAL

BARRICADE, TYPE III		1,656 BDAY
SIGN DAY		2,760 EACH
CONTRACTOR FURNISHED SIGN DAY		138 EACH
FIELD OFFICE		1 EACH
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED		5 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED		5 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED		5 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.		5 HOUR
TEMPORARY SILT FENCE		300 LF